

computing today

ISSN 0142-7210

JUL 1979

50p

**GETTING
INTIMATE
WITH
SUPERBOARD
IN DEPTH REVIEW**

**MPUs BY
EXPERIMENT**

**CLUB
SURVEY**



8K ON BOARD MEMORY!

5K RAM. 3K ROM or 4K RAM. 4K ROM (link selectable). Kit supplied with 3K RAM. 3K ROM. System expandable for up to 32K memory.

2 KEYBOARDS!

56 Key alphanumeric keyboard for entering high level language plus 16 key Hex pad for easy entry of machine code.

GRAPHICS!

64 character graphics option — includes transistor symbols! Only £18.20 extra!

MEMORY MAPPED

high resolution VDU circuitry using discrete TTL for extra flexibility. Has its own 2K memory to give 32 lines for 64 characters

KANSAS CITY

low error rate tape interface

2 MICROPROCESSORS

Z80 the powerful CPU with 158 instructions, including all 78 of the 8080, controls the MM57109 number cruncher. Functions include +, —, /, squares, roots, logs, exponentials, trig functions, inverses etc. Range 10^{-99} to 9×10^{99} to 8 figures plus 2 exponent digits.

EFFICIENT OPERATION

Why waste valuable memory on sub routines for numeric processing? The number cruncher handles everything internally!

RESIDENT BASIC

with extended mathematical capability. Only 2K memory used but more powerful than most 8K Basics!

1K MONITOR

resident in EPROM

SINGLE BOARD DESIGN

Even keyboards and power supply circuitry on the superb quality double sided plated through-hole PCB.

**ONLY
£275.00
+VAT**

**COMPLETE
KIT**



Cabinet size 19.0" x 15.7" x 3.3". Television by courtesy of Rumblelows Ltd., price £58.62


POWERTRAN

**PSI Comp 80.Z80 Based powerful scientific computer
Design being published in Wireless World — NOW!**

The kit for this outstandingly practical design by John Adams being published in a series of articles in Wireless World really is complete!

Included in the PSI COMP 80 scientific computer kit is a professionally finished cabinet, fibre-glass double sided, plated-through-hole printed circuit board, 2 keyboards PCB mounted for ease of construction, IC sockets, high reliability metal oxide resistors, power supply using custom designed toroidal transformer, 2K Basic and 1K monitor in EPROMS and, of course, wire, nuts, bolts, etc.

**SYSTEM
EXPANSION
COMING
SHORTLY!**



Kit also available as separate packs e.g. PCB, Keyboards, Cabinet, etc.

PCB size 16.0"x12.5"

Value Added Tax not included in prices

PRICE STABILITY: Order with confidence. Irrespective of any price changes we will honour all prices in this advertisement until August 31st, 1979. If this month's advertisement is mentioned with your order. Errors and VAT rate changes excluded.

EXPORT ORDERS: No VAT. Postage charged at actual cost plus 50p handling and documentation.

U.K. ORDERS: Subsequent to 8% surcharge for VAT. NO charge is made for carriage. Or current rate if charged.

SECURICOR DELIVER: For this optional service (U.K. mainland only) add £2.50 (VAT inclusive) per kit.

UK Carriage FREE

POWERTRAN COMPUTERS

(a division of POWERTRAN ELECTRONICS)

PORTWAY INDUSTRIAL ESTATE
ANDOVER HANTS SP10 3MN

ANDOVER
(0264) 64455

computing today

VOL 1. NO 5.
JULY '79

ACTING EDITOR: Ron Harris B.Sc
EDITORIAL ASSISTANT: Henry Budgett.
ART DIRECTOR: Diego Rincon.
PRODUCTION: Pete Howells, Paul Edwards,
Tony Strakas.
ADVERTISING: Chris Surgenor (Manager).
EDITORIAL DIRECTOR: Halvor Moorshead



	PAGE
NEWS If it happens you hear	6
MICROPROCESSORS BY EXPERIMENT The long awaited series on the workings of a CPU	13
SUPERBOARD II We get to grips with our cover subject!	20
SOFTSPOT Readers own programs for your entertainment	25 & 47 & 60
NASCOM PACKAGE This should sort you out	27
SHOW REPORT From America a report on a micro show	32
CLUB SURVEY We look at your local	37
BITS, BYTES AND PIECES This month we examine extended BASIC	42
PRINTOUT Readers response	46
BEGINNING BASIC This month we examine extended BASIC	49
D2 PROGRAMMING The art of machine code programming explained	53
APPRECIATING THE MICROPROCESSOR We do, will you?	63
INFORMATION Contents 3, Cartoons 11, Book Service 18, ETI Next Month 26, CT Next Month 41, Marketplace 59, T Shirts 67.	

Computing Today International is normally published on the third Friday of the month prior to the cover date.
COPYRIGHT: All material is subject to world wide Copyright protection. All reasonable care is taken in the preparation of the magazine to ensure accuracy but CT cannot be held responsible for it legally. Where errors do occur a correction will be published as soon as possible afterwards.

Distributed by Argus Distribution Ltd. Printed by LSG. Limited, Lincoln.

EDITORIAL AND ADVERTISEMENT OFFICE
145 Charing Cross Road, London WC2H 0EE. Telephone 01-437 1002/3/4/5

GENTLEMEN the PET DISK has landed...



The U.K. designed and manufactured Novapac disk system for Commodore's PET*, first seen at Compec '78, is (after extensive industrial evaluation), now available to the domestic user. Its unique saddle configuration continues the integrated design concept of your PET, with no trailing wires or bulky desktop modules.

- **Novapac** may be used with any available RAM plane.
- **Data transfer** takes place at 15,000 char/sec — effectively 1000 times faster than cassette!
- **Storage capacity** is 125 K/bytes (unformatted) on 40 tracks per diskette side.
- **Dual index sensors** permit dual side recording for 250 K/bytes per diskette.
- **Easy operation** full width doors prevent media damage.
- **System expandable** to ½ M/byte on-line storage (4 drives).
- **Dual head and 2D** versions provide 2 M/bytes on-line.
- **Industry Standard IBM 3740** recording format for industry-wide media compatibility only offered by NOVAPAC
- **Dedicated Intel 8048** microprocessor and 1771 FDC minimise PET software overhead.
- **Local hardware and software** support available, including applications, packaging for small business use.
- **Maybe used with N series Pet.**

The sophisticated Disk Operating System is disk resident, which allows for future DOS enhancements without hardware alterations. PDOS supports multiple file handling, dynamically allocating disk space to each as and when necessary. Any file may occupy from 1 to 600 sectors as required, at up to 16 non-contiguous locations on the disk, PDOS may be used alone, or within a BASIC program, and offers user-specified password security for any file. Multiple access-modes simplify BASIC program construction and the user may generate tailored DOS modules.

Novapac dual-disk system complete with PDOS and BASIC demonstration programs on disc **£950 + VAT**. Available from the manufacturer or selected dealers. Novapac with 32K add-on memory **£1150 + VAT**

Terms: 50% with order, balance on delivery
Full cash with order is subject to 5% discount
VAT-FREE Export arranged (Must be shipped by us)

analog electronics

47A Ridgeway Avenue, Coventry
Tel: 0203 417761

TRS 80 SOFTWARE

from the leaders in innovative software

We were first for the TRS 80 with Re number Basic

We were first with Level III

We were first with the Howe Monitors 1, 2 and 3.

We were first with the Newdost

And we are going to go on being first
SEND SAE FOR LIST

A. J. HARDING

(MOLIMERX)

28 Collington Ave.,
Bexhill, E. Sussex.
Tel. (0424) 220391



REPLACEMENT KEYBOARD

DESIGNED FOR USE

WITH THE MK 14 M.P.U.

FEATURES

- ★ Hand-Held Keyboard with Display
- ★ Positive Click Action Keys
- ★ Complete with Screened Miniature Cable
- ★ Ready Built and Tested
- ★ Easy to Connect to your Existing Unit

£16.50 + VAT, includes Post and Packing
(Mail order only)

FOR ELEKTOR SC/MP USERS

- ★ EPROM and RAM Card
- 4 1K (2708) EPROM with 2K (2102) RAM
- ★ EPROM Programmer (2708)

For further details please contact

Registered Office
1 MANOR ROAD
ENFIELD
MIDDLESEX



baud
instruments
limited

L.P. ENTERPRISES

Room CT
313 Kingston Road, Ilford
Essex, IG1 1PJ, England
01-553 1001

A COMPREHENSIVE SELECTION OF MICROCOMPUTER BOOKS AND MAGAZINES FOR THE HOBBYIST, EDUCATIONALIST, PROFESSIONAL AND RETAILER

Introduction to Microcomputers:	
Vol 0: Beginners Book	£5.95
Vol 1: Basic Concepts	£6.30
Vol 2: Some Real Microprocessors (without binder)	£18.95
Vol 2: Some Real Microprocessors (with binder)	£24.70
Vol 3: Some Real Support Devices (without binder)	£11.95
Vol 3: Some Real Support Devices (with binder)	£17.70
Updating subscription (6 issues) for Vol 2	£18.95
Updating subscription (6 issues) for Vol 3	£18.95
Updating subscriptions for Vol 2 & 3	£30.00
1 Updating issue (specify for Vol 2 or 3)	£4.00
1 Binder (Specify for Vol 2 or 3)	£5.75

6800 Programming for Logic Design	£6.30
8080 Programming for Logic Design	£6.30
Z80 Programming for Logic Design	£6.30

BASIC Computer Games	£5.50
What To Do After You Hit Return	£8.95
8080 Galaxy Game	£6.95
Programming the 6502	£7.95
Computer Rage (A Board Game)	£6.95
Artist and Computer	£3.95
PIMS — A data base management system	£5.95
Games, Tricks & Puzzles for a Hand Calculator	£2.49

Z80 Instruction Handbook	£2.95
8080 Programmers Pocket Guide	£1.95
8080 Hex Code Card	£1.95
8080 Octal Code Card	£1.95

Dr Dobbs Journal Vol 1	£10.00
Best of BYTE	£8.95
Scelbi BYTE Primer	£7.95
Best of Creative Computing Vol 1	£6.95
Best of Creative Computing Vol 2	£6.95
Best of MICRO — 6502 journal	£5.50

8080A/8085 Assembly Language Programming	£6.45
6800 Assembly Language Programming	£6.45
8080 Software Gourmet Guide and Cookbook	£6.95
6800 Software Gourmet Guide and Cookbook	£6.95
6800 Tracer — an aid to 6800 Program D-Bugging	£3.95
Program Design	£4.25

Magazine Subscriptions:	UK Price	Overseas Price
Subscriptions start with 3 weeks		
MICRO-6502 Journal (12 issues)	£14.50	£15.00
Personal Computing (12 issues)	£16.00	£17.00
Interface Age (12 issues)	£20.00	£21.00
Dr Dobbs Journal (10 issues)	£13.00	£13.50
Computer Music Journal (4 issues)	£10.50	£11.00
Recreational Computing	£8.00	£8.50
BYTE (12 issues)	£21.00	£21.00
Creative Computing (12 issues)	£16.00	£16.50
Kilobaud (12 issues)	£20.00	£21.00

THIS LIST CANCELS ALL PREVIOUS PRICE LISTS: EFFECTIVE JANUARY 1979 DUE TO FLUCTUATIONS OF THE DOLLAR. PRICES SUBJECT TO CHANGE WITHOUT NOTICE.

HOW TO ORDER

Please note our prices include postage and packing, but not insurance, if wanted add 12p for every £10 of books ordered. Make cheques, PO's etc. payable to:
L.P. Enterprises.
 CREDIT CARDS accepted
 BARCLAYCARD VISA / ACCESS
 DINERS CLUB / AMERICAN EXPRESS
 N.B. Diners Club orders cannot be accepted by telephone.
 Phone: 01-553 1001 for Credit Card orders (24-hr answering service)

Send to address above	All Orders must be Prepaid
Indicate Payment Method:	Total Enclosed £
..... My cheque, P.O., I.M.O. is enclosed in Sterling on U.K. Bank	
..... Charge to Barclaycard/Visa/Access/Diners/American Express	
Credit Card No	Expiry Date
Name	
Address	
	POSTCODE
Signature	

Microprocessors from Chips to Systems	£7.95
Microprocessor Interfacing Techniques	£8.15
Z80 Microcomputer Handbook	£7.50
TV Typewriter Cookbook	£7.50
T.T.L. Cookbook	£7.50
CMOS Cookbook	£7.95
IC OP-AMP Cookbook	£9.50
RTL Cookbook	£4.25
IC Timer Cookbook	£7.50
The Cheap Video Cookbook	£4.30

Introduction to Personal and Business Computing	£4.95
Getting Involved with your Own Computing	£4.75
Your Home Computer	£5.95
How to Profit from Your Personal Computer	£5.50
Calculating with BASIC	£4.95
Hobby Computers are Here	£3.95
New Hobby Computers	£3.95
Understanding Microcomputers and Small Computer Systems	£8.50

Users Guide to North Star BASIC	£10.00
Instant BASIC	£7.50
Basic BASIC	£6.50
Advanced BASIC	£6.00
My Computer Likes Me... When I Speak in BASIC	£2.75
Introduction to PASCAL	£3.95
SCALBAL — High Level Language + Supplements	£20.00

Accounts Payable and Accounts Receivable	£10.95
Payroll with Cost Accounting	£10.95
General Ledger	£10.95

Basic Software Library:	
Vol 1: Business and Games Programs	£17.50
Vol 2: Maths, Engineering and Statistical Programs	£17.50
Vol 3: Advanced Business Programs	£26.95
Vol 4: General Purpose Programs	£7.95
Vol 5: Experimenters Programs	£7.95
Vol 6: Miniature Business System	£32.50
Vol 7: Chess/Medbil/Wdproc Programs	£26.95

Some Common BASIC Programs	£6.30
Computer Programs that Work (in BASIC)	£2.55
First Book Of KIM	£7.00

8080 Standard Monitor	£9.95
8080 Standard Editor	£9.95
8080 Standard Assembler	£9.95
Special Package: 8080 Assembler, Editor, Monitor	£20.00
Bar Code Loader for 6800, 8080, Z80 and 6502	£1.75
Tiny Assembler for 6800 Systems	£5.75

Magazine Back Issues:	
Micro-6502 Journal	£1.50
Personal Computing	£1.75
Interface Age	£2.25
ROM	£1.75
Dr Dobbs Journal	£1.75
Computer Music Journal	£3.75
People's Computers (recent issues called Recreational Computing)	£1.75
BYTE	£2.25
Creative Computing	£1.75
Calculators and Computers	£1.75
Kilobaud — reprints only	TBA
73	£2.25
Magazine Storage Box (Holds 12)	£1.25

All publications are published in U.S.A. and shipped air-freight by **L.P. Enterprises**. In unusual cases, processing may exceed 30 days.
 Prices subject to change without notice.

TRADE ENQUIRIES WELCOME

PRINTER FOR EVENTS


The silent printer mechanism from Dataplus that we mentioned in last month's news is being built into a programmable event recorder.

The model 4001 is produced by Kinson Electronics of London

and is a 16 channel machine. It is being used to record the results of experiments on animals by the Life Sciences Laboratory. The printer was chosen for the application because it can operate at high speed, up to 400 cps, silently and thus not disturb the animals under observation. Dataplus are on 0242-30030.




PIN CONFIGURATION



PIN NAMES

AD ₀ -AD ₇	ADDRESS/DATA LINES
A ₈ , A ₉	ADDRESS LINES
CS	CHIP SELECT
CE ₁	CHIP ENABLE (10/0)
CE ₂	CHIP ENABLE
ALE	ADDRESS LATCH ENABLE
RD	READ ENABLE
WR	WRITE ENABLE

BLOCK DIAGRAM




RAM AN 8085A!

Rapid Recall's offering for the month is a 1K by 8 Static RAM for the 8085A CPU. Called the 8185 it is directly interfaceable to the multiplexed bus. Two

speeds are available to suit either a standard 8085 or the faster 8085A-2. The device uses a single 5V rail and operates in low current mode when not selected, thus reducing power consumption. Rapid Recall are on 062-85-24961.

WE'VE MOVED


OXFORD ST



FLETCH


145 Charing Cross Rd
London WC2H 0EE

Tel: 437 1002



GNASH YOU A DISK

Two new disks are available from Nashua. The SMD series offer capacities from 40 to 300 MB and can be supplied preformatted to suit a range of drives. All disks are certified before shipping and production standards meet or exceed all industry standards. The second disk is for top pack loading systems and is designated Model 4442. A 10MB version is available for the Data General 6070 drive and a 12.5MB version for the Wangco ST2422 for Data-




point 9374 drives. More details from Nashua Corporation, Computer Products Division, Cory House, Bracknell, Berkshire.

PROGRAMS AT 20P

Petsoft are offering 76 of their most popular financial and maths programs in a package for £15 incl. VAT, less than 20p a program. Developed by Adam Osborne many have appeared in his book, "Some Common Basic Programs" and all have been modified for the PET. Available at local dealers or mail order they will also soon be available on disk. The book is also available at £7.50. Petsoft are at 5-6 Vicarage Road, Edgbaston, B'ham B15 3ES.

TEK GRAPHICS BUILD

Using Tektronik 4010 graphics terminals the Strathclyde University Architecture and Building Aids computer system ABACUS is helping to promote the use of computers in the building trades. By using systems such as the ones developed at the university an architect can make changes to a design simply and quickly without resorting to traditional methods. Programs allow for analysis of heat losses, elevator systems and many other common requirements that would normally take hours of work. Tektronik are located at Beaverton House, PO Box 69, Harpenden, Hertfordshire.



MORE APPLES FOR US

Keen Computers of Nottingham are importing the Apple II into the UK after talks with the American parent company. They also hope to organize a dealership network in the UK for the machine in order to provide better support and service facilities than have previously been available. Software development for the machine is also to be expected. For more information contact Keen on 0602-583254.

FINTERM FROM TALLY

An intelligent printer terminal for financial applications is to be introduced by Tally of Reading. The M79 is designed for use in banks, building societies and other financial institutions for printing on a variety of media. Capable of handling passbooks, single

sheets or reel-fed stationery it can print at up to 200 CPS with a seven high 207 matrix head. An optical search facility allows it to add lines to a previously printed document in the right place. Produced in Germany by Tally's sister company it will be available in the UK from October, demonstration models are available now. Contact Tally on 0734-580141.



COBOL RULES OK

Micro Focus's CIS COBOL has been chosen by two firms to run on their machines. Computer Mart of Norwich are using it for data processing applications based on the Imsai micro-computer. North Star have also chosen it to run on their Shugart based disk systems with the Lifeboat Associates version of CP/M.

Supplied on two mini-floppies CIS COBOL is a subset of the ANSI standard COBOL and can operate in 32K of RAM. More information from Micro Focus at 58 Acacia Road, St. Johns Wood, London NW8 6AG.

SCOTS FIRST WITH HARD DISK

The Edinburgh based Micro-Centre computer shop is the first in the country to have the new Cromenco Z-2H micro with an integral 11MB hard disk. Costing £5748 it uses the 4 MHz Z80A CPU, with twin floppies, single hard disk and 64K of RAM. Housed in a table top cabinet it was first shown at the West Coast Computer Faire in May.

All systems supplied by Micro-Centre will be maintained by CFM under a special arrangement. Software is available at £65 per package and the range includes ANSI level 1 COBOL, Fortran IV, 16K Extended BASIC, and a WPS.

A multi-user BASIC will be available at £460. MicroCentre are on 031-225-2022.

DATA/DYNAMICS PROLIFERATE

Items of news from Data Dynamics this month.

They have just reduced the price of their WP system, the Artec International Display 2000 from £6950 to £5500. Comprising two units, a free-standing floppy disk and a printer/keyboard, the unit features a unique display system. Rather than using a VDU it has a single line plasma display that should prove both easier to read and reduce eye-strain. The second item is a new leaflet on their 5 level keyboard printer, the ZIP-ASR. Designed for use on private Telex networks the machine can be used to produce tapes off-line. For further material on these products contact Data Dynamics at Data House, Springfield Road, Hayes, Middx.

2020 IN THE SHADE

MicroSHADE of Calne are extending their range to stock the ITT2020 the licenced version of Apple. Supplies of this machine are hoped to relieve the delivery problems of Apples and also to boost the aftersales support. MicroSHADE are acting as agents for Telefusion, the wholesale distributors of the machine for the West Country, Norfolk and the North East. Shade live at 1 Patford Street, Calne, Wiltshire.

NEW INTEL SOFTWARE

A new editing system has been announced for Intellec development systems by Intel. Called CREDIT it allows a WP approach to the generation of high level and assembly language programs. Text can be edited by cursor control in Screen mode or by specific commands in Command mode. Macro commands can be constructed and executed by a two letter code. A constant option chart can be called by HELP thus allowing easy operation by anyone. Intel are at 4 Between Towns Road, Cowley, Oxford OX4 3NB.

UP A MYTH?


After much recent press comment on word processor systems the Managing Director of Abacus, Derek Rowe, has had a go at dispelling some of the mysticism. In a talk to sales staff he pointed out that a WP system is just that, it doesn't solve all the customers problems overnight. However, if you sell that client a computer with a WP package he can use it for other things as well, such as accounting. A most reasonable view, and one which may well help many business people to take a second look at the "miracle machines".



JAP MICROS ARRIVE


The range of SORD micro-computers from Japan are now available in the UK. Costing between £1000 and £4000 they use the 280 CPU and have all the usual peripheral options including floppies, printers etc. They appear to be S100 based

and the photo shows the top of the range M223 with its integral 1.4MB of disk store, RS232 port and a wide range of software including CAP Micro-products range. For more information the main distributor, Dectrade Ltd, may be contacted at 11 Musters Road, West Bridgford Nottingham or on 0602-861774.



NEW KEYBOARD

Rastra Electronics of Hammersmith are now supplying the new Synertek KTM-2 keyboard module. Providing the full ASCII set on a 24 by 40 matrix it gives a low-cost, high-performance display terminal capability. With the built in relative and absolute cursor addressing modes it is possible to produce animated graphics easily. The whole unit runs off a single 5V rail and is directly connectable to a video monitor. A modulator can be fitted to drive a standard TV. Further details of this and the rest of the SYM range from Rastra at 275-281 King Street, Hammersmith, London W6 9NF.



TEXAS ARRIVES

It's here at last and we can tell you all about it! No real surprises unfortunately, the system was launched on Sunday in Chicago after a Press announcement on Friday 1st June. Comprising 16K RAM, sound generator, full colour graphics and extended BASIC the system is called TI-99/4 and can drive any colour or black and white monitor or NTSC TV. Hopefully a PAL version will be available for the UK. Using plug-in solid state software modules containing up to five ROM's a range of software has been announced to coincide with the machine and the first batch includes Household Management and Budget, Football, Videographs, Demos and Diagnostics, Beginning Grammar and a few more. Future add-ons will be a printer, disk, RS232 interface, and a Solid State speech synthesiser. The synthesiser will use the same chip as the Speak and Spell machine and have a 200 word vocabulary. The BASIC is full floating point, 13 digits and is compatible with the ANSI specification. It has 24 statements, 14 commands, 16 colour graphics and four octaves of music. A BASIC guide and reference manual are supplied. UK Software modules will include Pre-school learning, Video Chess and Home Budgeting. The machine will be here in the fourth quarter and will sell for £645, Software costing £15 to £50 per module.

AIM TO BUBBLE


The AIM65 can now be equipped with a fully addressable 1 MB bubble memory. Using the new expansion motherboard available from Pelco at £136.50 you can add — on to your system to produce smart terminals or desk top computer.

A variety of modules are available to plug in, from the Rockwell system 65 to Motorola Exorciser, as well as some from Burr-Brown. The bufferboard is scheduled for June and pricing for the add-on boards including the bubble memory are available from Pelco at Enterprise House, 83-85 Western Road, Hove, Sussex BN3 1JB.

MICRO-BASED TRANSLATOR WITH HONG KONG LINK

A Hong Kong firm, working in conjunction with an American designer and a San Francisco software House and producing hand held translator units. Housed in a calculator style package the unit contains eleven IC's, 32K of RAM and a 32K plug-in ROM.

At a cost of \$200 in the States the firm is producing about 1000 a day at the moment, languages currently available are English, and a choice of French, German, Spanish, Portuguese, Italian or Japanese. Apart from acting as a language translator the unit can be used as an educational tool, future models are expected to contain such diverse information as recipes and Olympic records. For further data contact the Hong Kong Trade Development Council at 14-10 Cockspur St, London SW1Y 5DP



MICRO COURSES

Portsmouth Poly's Electrical and Electronic Engineering Section are running some courses for engineers who wish to get experience on micros. The first course is a three day introductory session and runs 4-6 June, 26-28 September and 3-5 December, fee is £85 inclusive. The second course is a follow up, again a three day course, and runs 9-11 July and 5-7 November, fee is £90. Both include hands-on experience. More advanced courses are planned and anyone who is interested should contact Mrs A.P. Sizer at the Poly, Anglesea Bldg., Anglesea Rd., Portsmouth PO1 3DJ or ring 0705-27681.

NANOCOMPUTER IS NEW ARRIVAL

This morning we had a new arrival in the office. The first production unit of a Z80 based educational and development kit. Produced by SGS-Ates it has 4K of RAM and 2K PROM on board with twin parallel ports and a single serial port. Using the basic hand held terminal it forms an educational and training system at £203. Upgrading is easily performed and card frames, experimental kits, power supplies etc. are soon to be available. We have a unit at the moment and will produce a test report in the next issue.

PETALECT

ELECTRONIC SERVICING LTD.

WANTED

Good Homes for Intelligent Pets

THE PET 2001/8 Computer

£550 plus VAT



This unbelievably versatile, compact, portable and self-contained unit has many varied applications and offers tremendous benefits in the worlds of

● BUSINESS and COMMERCE:

Can be used efficiently for Trend Analysis · Stock Control · Payroll · Invoicing · Inventory Control, etc.

● SCIENCE and INDUSTRY:

The 'PET' has a comprehensive set of scientific functions useful to scientists, engineers and industry.

● EDUCATION:

An ideal tool for teaching and it can be used to keep records, exam results, attendance figures, etc.

● ENTERTAINMENT:

Games including Backgammon, Noughts and Crosses, Pontoon, Black Jack and Moon Landing

PET COMPATIBLE DUAL FLOPPY DISC NOW AVAILABLE

NEW PETS NOW IN STOCK

We have six years' experience in servicing electronic calculators, mini-computers in S.E. England. 24-hour service contract available at £69.50 per annum. Credit and leasing terms available.

For full details and demonstration contact Peter Watts . . . Now!

PETALECT

ELECTRONIC SERVICING LTD

(Authorised Commodore Pet Dealer) Specialists in Electronic Servicing, Programming, Electronic Design and Prototype Manufacture

33 PORTUGAL ROAD, WOKING,
SURREY GU21 5JE.

Tel: Woking (04862) 69032/68497

BUILD THE 12,000 ALREADY SOLD NASCOM I COMPUTER



WE ARE THE SOLE APPROVED LONDON STOCKIST & NATIONAL DISTRIBUTOR

KITS IN STOCK:

● BRITISH DESIGN ● U.K. BEST SELLING KIT
FULL AFTER SALES SERVICE & GUARANTEE

NEW LOW PRICE

£165 + 10% VAT
POST FREE

FEATURES:

FREE B-BUG WITH EVERY KIT

- ★ SUPPLIED IN KIT FORM FOR SELF ASSEMBLY
- ★ FULL DOCUMENTATION SUPPLIED
- ★ FULLY SCREENED DOUBLE-SIDED PLATED THROUGH HOLE PRINTED CIRCUIT BOARD
- ★ FULL 48 KEY KEYBOARD INCLUDED
- ★ 2K X RAM
- ★ 2K X MONITOR PROGRAM PROVIDING
- ★ POWERFUL MOSTEK Z80 CPU
- ★ 16 X 48 CHARACTER DISPLAY INTERFACE TO STD. UN-MODIFIED TV
- ★ TV DISPLAY MEMORY MAPPED FOR HIGH SPEED ACCESS
- ★ ON BOARD EXPANSION TO 2K X 8 EPROM
- ★ ON BOARD EXPANSION FOR ADDITIONAL 161.0 LINES
- ★ MEMORY MAY BE EXPANDED TO FULL 60K

SOFTWARE (B-BUG)

- ★ 2K X 8 MONITOR PROGRAM PROVIDING
- ★ 8 OPERATING COMMANDS SUPPORTING MEM EXAMINE/MODIFY/TABULATE/COPY/BREAK/SINGLE STEP/EXECUTE/TAPE LOAD/TAPE DUMP
- ★ REFLECTIVE MONITOR ADDRESSING FOR FLEXIBLE MONITOR EXPANSION THROUGH USER PROGRAMS
- ★ MONITOR SUB-ROUTINES INCLUDE — DELAY ASCII CODING, BINARY TO HEX CONVERSION, CLR SCREEN, SCROLL UP, STRING PRINT, CURSOR SHIFT AND MANY OTHERS

EXPANSION

- ★ EXPANSION BUFFER BOARD £32.50
- ★ MEMORY KITS (INCLUSIVE ALL HARDWARE)
- 8K £85.00
- 16K £140.00
- 32K £200.00
- ★ I/O BOARD WITH DECODERS AND ALL HARDWARE EXCEPTICS £35.00
- WILL ACCEPT UP TO 3 PIO, 1 CTC AND 1 UART

OTHER HARDWARE

- ★ HENRY'S 3A POWER SUPPLY FOR UP TO 32K EXPANSION £24.50
- ★ 3A POWER SUPPLY FOR UP TO 32K EXPANSION MKII £29.50
- ★ 8A POWER SUPPLY FOR LARGER THAN 32K EXPANSION £80.00
- ★ EXPANSION CARD FRAME £29.50
- ★ EPROM PROGRAMMER KIT £13.95
- ★ KEYBOARD CABINET £3.50
- ★ PROGRAMMING MANUAL £4.00

NEW NEW T.4 Operating System in (2) 2708 EPROMS upwards compatible from £25.00
T2 & B Bug TINY BASIC £25.00
SUPER TINY BASIC (with Editor & Machine Utility routine) £35.00
ZEAP ASSEMBLER EDITOR £32.00 8K BASIC £45.00
● Demonstrations continuous daily — we welcome export. Educational and industrial enquiries.
FREE BROCHURE. SEND S.A.E. 9 1/2" x 6 1/2", STAMP 12 1/2p. VAT 8% ALL ITEMS EXCEPT BOOKS.

Henry's
Phone (01) 723 1008

All mail to:
Henry's Radio
404 Edgware Rd.
London, W2



Happy Memories

21L02 450 ns 78p 2114 450 ns £4.95 4116 300 ns £7.25
21L02 250 ns 95p 2114 250 ns £5.40 2708 450 ns £6.75

TRS-80 16K Memory Upgrade Kit: £70

S100 16K 250ns Static RAM Kit: £195 With 4K £81, 8K £119

Low Profile) Pins: 8 14 16 18 20 22 24 28 40
DIL Sockets) Pence: 9 10 11 15 16 18 20 25 35

Our new shop is now open at the address below. We shall be stocking a wide range of items to interest all those of you who are building or plan to build your own micro computer, why not pay us a visit? We are open from Mon to Sat 10 to 6 and often much later.

We stock a range of books covering fundamentals through to advanced topics (Like games)

We are NASCOM dealers for the South Coast.

Do-it-yourself with our range of wire wrapping aids and materials from the O.K. corral, or Box-it-yourself with a Vero enclosure after Soldering-it-yourself with Antex

Our stocks are rapidly increasing; please write or call for latest lists of available products. We welcome your suggestions for stock lines. What do you find difficult to obtain? (We know about buffers)

Please add 20p p&p to all orders less than £10 in value Cheques or P.O.s payable to 'Happy Memories'. Access or Barclaycard orders may be telephoned 24hrs a day.



Prices quoted include VAT
at 8% Please adjust for
any change in rate.



19 Bevois Valley Road, Southampton,
Hants. SO2 0JP Tel: (0703) 39267




"I've invented silicone chips capable of controlling nuclear fission".



"You mean . . ."



"Yes — fission chips!"



"An' what's more—my dad's home computer is bigger than your dad's!"

HOME
COMPUTERS



"I'd like to exchange it—my wife doesn't like the colour."

DOOR CHIMES 24 TUNES

ELECTRONIC DOOR TUNES

— £18.50 inc VAT

Waddington's Videomaster announce a doorbell that doesn't go Brrrring, Ding Dong or Bzzzzzz. Instead it plays 24 different classical and popular tunes. It will play the tune you select for your mood, the season or the visitor you are expecting to call. Door tunes is not only great fun and a wonderful ice breaker, but is also very functionally and beautifully designed to enhance your home. There is something for Christmas, something for your continental visitors or your reactions from the States and even something for the Queen. Door tunes is easy to install and has separate controls for volume, tone and tempo.

T.V. GAMES

PROGRAMMABLE COLOUR CARTRIDGE — £31.86 inc VAT

The TV Game can be compared to an audio cassette deck and is programmed to play a multitude of different games in COLOUR using various plug-in cartridges. Each cartridge contains up to 10 different sports games and the first cartridge containing 10 sports games is included free with the console. Other cartridges are currently available to enable you to play such games as Grand Prix Motor Racing, Super Wipeout and Stunt Rider. Further cartridges are to be released later this year, including Tank Battle, Hunt the Sub and Target. The console comes complete with two removable joystick player controls to enable you to move in all four directions (up/down/right/left) and built into these joystick controls are ball serve and target fire buttons. Other features include several difficulty option switches, automatic on screen digital scoring and colour coding on scores and balls. Lifelike sounds are transmitted through the TV's speaker simulating the actual game being played. Manufactured by Waddington's Videomaster and guaranteed for one year.



EXTRA CARTRIDGES

ROAD RACE — £9.58 inc VAT
Grand Prix motor racing with gear changes, crash noises etc.
SUPER WIPEOUT — £9.90 inc VAT
10 different games of blasting obstacles off the screen.
STUNT RIDER — £13.13 inc VAT
Motorcycle speed trials, jumping, obstacles, leaping various rows of up to 24 buses etc.

NON PROGRAMMABLE 6 Game — COLOURSCORE II — £14.58 inc. VAT.
10 Game — COLOUR SPORTSWORLD — £24.30 inc. VAT.
A/C MAINS ADAPTOR — £3.13 inc. VAT. (suitable for all three T.V. games above)

CHESS COMPUTERS

CHESS TEACHING TUTOR — £19.75 inc. VAT 1/2 PRICE OFFER !!



A special bulk purchase of these amazing chess teaching machines enables us to offer them at only £19.75 less than half recommended retail price of £45. The electronic chess tutor is a battery operated machine that can actually teach you to play chess and improve your game right up to championship level. This machine is not only for total beginners but also for established players wanting to play better chess. Unit contains the electronic chessboard with 32 chess pieces, a 64 page explanatory booklet and a set of 32 progressive programme cards including 6 beginners cards, 16 check mate positions, 9 miniature games, 5 openings, 3 and games 28 chess problems and 2 master games.

STAR CHESS — £59.50 inc. VAT

PLAY CHESS AGAINST YOUR PARTNER
Using your own TV to display the board and pieces. Star Chess is a new absorbing game for two players, which will interest and excite all ages. The unit plugs into the aerial socket of your TV set and displays the board and pieces in full colour for black and white on your TV screen. Based on the moves of chess, it adds even more excitement and interest to the game. For those who have never played, Star Chess is a novel introduction to the classic game of chess. For the experienced chess player, there are whole new dimensions of unpredictability and chance added to the strategy of the game. Not only can pieces be taken in conventional chess type moves, but each piece can also exchange rocket fire with its opponents. The unit comes complete with a free 18V mains adaptor, full instructions and twelve months guarantee.



CHESS CHALLENGER 7 — £92.50 inc. VAT




PLAY CHESS AGAINST THE COMPUTER
The stylish, compact, portable console can be set to play at seven different levels of ability from beginner to expert including "Mate in two" and "Chess by mail". The computer will only make responses which obey international chess rules. Castling, on passant, and promoting a pawn are all included as part of the computer's programme. It is possible to enter any given position from magazines or newspapers or alternatively establish your own board position and watch the computer react. The positions of all pieces can be verified by using the computer memory recall button. Price includes unit with wood grained housing and Staunton design chess pieces. Computer plays black or white and against itself and comes complete with a mains adaptor and 12 months guarantee.

OTHER CHESS COMPUTERS IN OUR RANGE INCLUDE: CHESS CHAMPION — 6 LEVEL — £85.50 inc. VAT.
CHESS CHALLENGER — 16 LEVELS — £164.50 inc. VAT. BORIS — MULTI-LEVEL — TALKING DISPLAY £175.50 inc. VAT.

DRAUGHTS COMPUTERS

CHECKER CHALLENGER —

PLAY DRAUGHTS/CHECKERS AGAINST THE COMPUTER
The draughts computer enables you to sharpen your skills, improve your game, and play whenever you want. The computer incorporates a sophisticated, reliable, decision-making microprocessor as its brain. Its high level of thinking ability enables it to respond with its best counter move like a skilled human opponent. You can select offence or defence and change playing difficulty levels at any time. Positions can be verified by computer memory recall. Machine does not permit illegal moves and can solve set problems. Computer comes complete with instructions, mains adaptor and twelve months guarantee.



FOR FREE BROCHURES — SEND S.A.E.

For FREE illustrated brochures and reviews on TV and chess games please send a stamped addressed envelope, and state which particular games you require information on.

Customers welcome at our shop in Welling — demonstrations daily — open from 10am-5.30pm Mon-Sat (10am-1pm Wed). To order by post please quote your name, address and Access/Barclaycard number. VAT is included in all prices above — Postage and Packing FREE.

AJD DIRECT SUPPLIES LIMITED, Dept. CT4, 102 Bellegrave Road, Welling, Kent, DA16 3QD. Tel: 01-303 9145 (Day) 01-850 8652 (Evenings)

OUR 1979 CATALOGUE

including the first edition of

STOP PRESS

- ★ Latest low prices
- ★ Fascinating new items
- ★ Special offers — a bargain on their own
- ★ Lowest prices ever for TTL
- ★ Free 45p worth of vouchers

RAM
2102A-2
1024 x 1 250ns
£1.19
16 for £16.96

C.P.U.
8080
£5.49

E. PROM
1702
£5.57

CATALOGUE
40p

JUST SEND
S.A.E. FOR
STOP
PRESS

CHROMASONIC electronics

DEPT. ETI 7, 56 FORTIS GREEN ROAD
MUSWELL HILL, LONDON N10 3HN
TELEPHONE: 01-883 3705/2289

USE OUR "ORDER
RING" LINES

VAT INCLUSIVE PRICES. P & P 25p

Crofton — Complete MICRO COMPUTER

Ready built and ready to run. Comprising:

- 24 K Ram
- Housed Monitor
- Housed Keyboard
- Floppy Disk Drive
- 8K Interactive Basic
- Manuals
- Printer Interface and Cable
- Switch Mode Power Supply

An unusual feature of the Crofton Best 1 Equipment is complete freedom of choice of operating levels between basic, disk operating system and monitor machine code. The user is at liberty to work at any level, move around between levels and not to 'Scratch or Clear' programmes at one level whilst working at another level.

TOTAL
£2071.00
Inclusive of VAT at 8%

Smaller systems and kits also available.

CROFTON
Electronics Limited
35 Grosvenor Road, Twickenham
Middlesex • Tel: 01-891 1923

MPU's BY EXPERIMENT

Ian Sinclair starts off his new series on the workings of microprocessors

One of the problems of getting heavily involved in the software aspect of microprocessing is that you tend to lose sight of the hardware which makes it all possible. Most of all, you tend not to learn enough about the microprocessor itself, which is rather a pity. The microprocessor has made the home computer possible, but its impact in other directions is going to be a lot more important; we shouldn't forget that home computing was (and still is!) the last application that the designers of most microprocessor (CPU) chips had in mind.

The aim of this series, therefore, is to find out what goes on in this important chunk of silicon. To do this, we've devised a bit of practical work which will guide you, with minimum cost, to a much better understanding of just one type of microprocessor. Just one, because time and money make it impossible to go through the action of all the major CPU chips which are on offer at the moment. The chip we've chosen to put in the pan is the familiar SC/MP by National Semiconductor, now referred to as the INS8060. The reasons for choosing this one are:

1. Easy availability — there's not much point in using a CPU which is available only to the trade, or at a high price.
2. A single voltage power supply. The modern INS8060 uses a single 5 V supply, and takes a modest current. The earlier SC/MP used dual +5 V and -7 V supplies, and is not suitable for this application.
3. A simple instruction set. The INS8060 is designed for machine control rather than for computing, so that its instruction set is reasonably short and simple.
4. A lot of useful facilities on one chip. By using the 8060, we've been able to keep the number of support chips, hence the cost, down to a minimum.

The Bare Essentials

At the starting level, we shall be working with the bare microprocessor and three small support chips, plus a lot of toggle switches and LEDs on a low-cost breadboard, the Eurobreadboard. This enables you to find out exactly what happens at each instruction, because this elementary layout has been designed so that the result of each clock pulse, and some of the actions between each clock pulse, can be examined. A major factor in choosing the Eurobreadboard format, incidentally, is that it can be used for other chips as well, unlike a PCB layout.

Once we've gone through the instruction set in detail, we shall need to look at how these instructions are used, and this brings us to the second phase of the work. For this we need more equipment, a hexadecimal keyboard and readout, RAM memory, and a monitor program to make it all go. The easiest and cheapest way of buying this lot is as the Science of Cambridge MK14, and that's what we'll use. Now if you're interested only in the basic microprocessor work and don't intend to buy the MK14, the buy-list for this particular section of the program is as shown. If you intend to stay with it to the bitter end, or have your own MK14 already,




Fig. 1. The Eurobreadboard which forms the basis of the microprocessor assessment unit. Note the numbering and lettering which lets us identify each row of contacts in the table of connections.

then you can use the SC/MP chip from the MK14 (provided that it is the modern, single-voltage supply type), so saving £8.50 or so on another INS8060. You may, of course, feel that you can use another 8060.

Let's start in right away with the bits of the breadboard system. The Eurobreadboard is conveniently shaped for this sort of work, and the latest versions have the rows of contacts numbered, and the columns lettered so that we can show the layout without needing to use too many drawings. Fitting the 40-pin CPU into any socket can sometimes be a bit of a struggle, and it's sometimes an advantage to open the spring contacts of the Eurobreadboard a bit rather than risk bending pins on the 8060. My own Eurobreadboard accepted the 8060 very easily, with just a gentle push needed to bed the chip right home. Remember that the 8060 is a NMOS chip, which means that it is possible to damage it by static from your fingers. Don't therefore try to place the 8060 on the board until all the connections are made and the rest of the circuits tested, and don't try to poke a pin into place by hand. Keep the 8060 in its protective packing until the last possible moment, and once it's in place on the board, leave it there.

Two of the other chips we've used are 74LS126's, which are the low-power TTL chips so readily available now. These can be put onto the board right away, positioning and wiring + and - connections as shown in Fig. 2. The remaining chip is a 74LS132, a quad Schmitt Nand gate, which is used for buffering and as a clock oscillator.

The remaining board wiring can now be completed, as shown also in Fig. 2 leaving only the off-board wiring, power supply connections, and the INS8060 to deal with. Of that, more later; first a word about basics.




Fig. 2. The TTL chips in place, and the board wiring ready for the first few experiments. Some circuit changes (shown on other photos) are made later, as detailed in the text (Part 3 onwards.)

What It Does

The circuit operates like this. One of the gates of the 74LS132 is used as a clock pulse generator, whose frequency can be altered by changing the capacitor marked C*. This clock pulse is put into the 8060 at its "clock in" (XIN) pin, which is pin number 37 on the big chip. I had originally hoped to use the push-button for clocking really slowly, but this caused rather erratic behaviour inside the 8060, of which more later. The push-button switch in this version now operates the input marked NHOLD, on pin number 6, whose function is to suspend operations just at the point when the microprocessor gates its data inputs to the switches that are connected to the 74LS126 buffers.

These eight data switches can be set to logic 1 (toggle pointing upwards in the prototype) or zero. We can't connect these switches directly to the data pins of the 8060, because the data pins of the 8060, in common with most other micros, are used for feeding signals in or out, and if we were trying to put data in at the same time as the microprocessor was trying to put data out, the microprocessor would lose the contest — and that's expensive. The data switch outputs therefore go to the inputs of the 74LS126 buffers, and the outputs of the buffers go to the data pins. These buffer circuits are three-state, meaning that there's a connection to their output pins only when the enable pins are at the correct voltage, high in the case of the 74LS126. That way, the voltages from the toggle switches are connected into the data pins only when the enable pins of the buffers are high. What switches the enable pins high? As we'll see, this is done by a pulse from the microprocessor itself, the output labelled NRDS from pin 2. There is one enable pin for each buffer, a




Fig. 3. How the on-board LEDs are used. A few extra LEDs are also used for odd items, later.

total of eight, and because eight enable inputs, even of these lower-power chips, are a bit much for the 8060 to drive, and because the NRDS signal is a negative-going pulse, one gate of the 74LS132 is used as an inverter and buffer.

One of the two remaining toggle switches is used for resetting the microprocessor, using pin 7. The voltage on this pin, labelled NRST has to be high (+5 V) for normal running, low to reset, and a simple toggle switch carries this action out in our circuit. The other toggle switch will be used to simulate a serial input, such as might be obtained from a cassette recorder.

The LEDs are used to indicate outputs. The eight LEDs which are mounted above the data toggle switches are operated from the data pins of the microprocessor, and will indicate either when data signals are being read in, in which case the LEDs will indicate the number to which the toggle switches are set, or when data is being written out from the microprocessor. In this second case, the number which is being written out need not agree with the number to which the toggle switches are set.

The other important group of LEDs are connected to four of the address pins, A0 to A3 inclusive. These LEDs are set in a row so as to indicate a binary number, the number of the address in memory which the INS 8060 is trying to address. We don't have any memory chips — as you'll see, you're the memory!

The other LEDs are used to indicate what the microprocessor is doing. One is connected to pin 4, labelled NENOUT, and indicates one particular stage in the processing of an instruction. Three more LEDs are used to indicate the stage of 'flags', outputs which can be programmed in any way the user wants (one of the features, incidentally, which makes the 8060 such a useful control device). The other two LEDs are used to indicate the state of pins 39 and 23. Pin 39, labelled NADS is another indicator of a stage in processing an instruction; pin 23, labelled SOUT is an output for bit-by-bit serial data.

Construction Details

Meanwhile, on with the construction. The circuit diagram is shown in Fig. 4. IC4a is used as the clock pulse generator, whose frequency is set by the value of C*. This value is 250 uF for the first few experiments, but a 25 uF capacitor is used later, so that this capacitor should be accessible and not buried under lots of wiring — this is just one of the many reasons for using a breadboard. There will also be an additional capacitor and resistor to plug in later. Only three of the NAND gates of the 74LS132 are used initially.

The push-button has a 0.1 uF capacitor wired across its contacts to help eliminate switch bounce problems, and is connected to IC4b, another of the 74LS132 gates. The out-

MPU's BY EXPERIMENT




Fig. 4. The circuit diagram — where several identical circuits exist (as on the address and data lines) only one is shown.



Fig. 5. The control panel. The row of eight toggle switches are for data entry, with D7 at the left and D0 at the right. The LED indicators are mounted above the switches. The bottom row is (from left to right), SIN, RESET, PUSH.

put of this operates the 8060 NHOLD input. With this input (on pin 6) low, the microprocessor stops just at the stage when data is to be fed in or out. When this pin is switched high, operations continue normally after a short delay. This way, we can examine what is happening one stage at a time.

Various outputs of the 8060, including the four lowest order address lines, are taken through 2k7 limiting resistors to LEDs, so that the logic voltages can be read as 1 (glowing) or 0. LEDs are also used on the data lines, but are separately mounted along with the data switches. For the prototype, which was as untidy as a rat's nest as you are ever likely to meet, I used an aluminium panel, earthed to the Eurobreadboard negative line, on which the toggle data switches were mounted as shown in Fig. 4. Two more toggle switches (reset and serial input) were mounted in a row underneath along with a push-button switch which is used as the GO switch. A set of eight LEDs is strung on to a Vero-board strip, as also shown in Fig. 5 and Fig. 6 along with limiting resistors of 2k7, and the strip is secured to the panel with double-sided Sellotape (all high-technology stuff, you'll note, even if I did cut out the panel with my teeth). Switches and LEDs can then be labelled, starting with 7 for the left-hand side and going down to 0 for the right-hand side. These numbers correspond to the numbering of the data pins of the 8060. I must confess I didn't number the switches or LEDs on the prototype — by that time I knew where everything was.

Another ten LEDs are mounted on the Eurobreadboard itself, as listed in the connections table. These LEDs are used to show what voltages exist on the 8060 output lines, including four of the address lines. Four address lines permit sixteen program addresses to be displayed, and when you find out what is involved in each step of program you'll stop saying 'only sixteen' so loudly.

Wiring Up

A 2k7 current-limiting resistor has been used for each LED, and various 10k pull-up resistors have been connected at inputs. Once again, the connections list shows what is conn-

ected to each socket row of the Eurobreadboard — another advantage notched up. The TTL ICs can be inserted first, since they will not come to any harm during wiring up.

Check each connection as you make it, and also again before you plug in the 8060. It's a good idea also to ensure that each LED is working before we have to start worrying about what the microprocessor is doing, so after checking the wiring, apply 5 V from a (preferably) stabilised supply (or use a 4.5 V battery), just to see what happens. None of the LEDs should light when the power goes on — put the room lights out, or pull the curtains to check this, because the glow from these small LEDs is a bit feeble. If all is well, no glow, use a piece of insulated wire with about 5 mm stripped from each end, as a checker. Plug one end of the wire into a spare hole in the +5 V row (X1 or Y2). Now plug the other end into a hole of one of the LED driving rows — try number A5 to start with. Check that the LED operated by this line (NENOUT on the 8060) is lit, and then try another one, such as A9. Check each LED in this way to ensure that you won't be let down by a faulty or reverse-connected LED, but make sure that you connect to the correct end of the limiting resistor. The miniature LEDs I used had one lead, the anode, longer than the other (Fig. 7), but a different variety of LED might be differently identified. Remember at this stage to check that there is an earth lead from the aluminium panel to the Eurobreadboard. The prototype used one of the Eurobreadboard fixing bolts to provide an earth simply by curling the bare end of a piece of single-core wire under it, and plugging the other end into the earth line on Y1.

While you have power on, check the effect of earthing line D18. This enables the buffers, so that with this line earthed each of the data switches, DBS0 to DBS7 should control its own LED DLED0 to DLED7.

The Final Link

With all of this checked out and working correctly, the final step can be taken. Switch off, remove the power supply leads, and put a shorting link between the + and — lines on the board (X1 and Y1). Take the INS8060 carefully out of its pack, locate the pip which identifies pin 1, and place the 8060 on the board so that its pin 1 lines up with line A1 of the Eurobreadboard. At this side of the board, the 8060 has to go off-centre — I allowed three spare holes at the side of the 8060 in the A column, and two spare on the B column.

Providing each hole has been pre-used by poking a lead into it, just take it off and put it back in its pack while you open each contact out a bit with a piece of 16 gauge wire, or the wire end of a large wire-ended capacitor. Then try again — and the INS8060 should slip in with just a gentle push. Everything is now ready for the first set of experiments detailed next month.




Fig. 6. How the toggle switches are wired.




Fig. 7. Miniature LEDs as used in the prototype.




Fig. 8. The back of the panel after wiring — note the cuts in the Veroboard.




Fig. 9. The complete prototype — this was taken at a later stage, so that C+ is a smaller value, and another extra capacitor is visible. These changes are made in Part 3.

TABLE 1

USE OF INS8060 PINS

Pin	Label		Pin	Label	
1	NWDS	not used	21	FLG1	to LED
2	NRDS	operates gate	22	FLG2	to LED
3	NENIN	earthed	23	SOUT	to LED
4	NENOUT	to LED	24	SIN	from switch
5	NBREQ	4k7 to +5V	25	ADD00	to LED
6	NHOLD	from gate	26	ADD01	to LED
7	NRST	from switch	27	ADD02	to LED
8	CONT	to +5 V	28	ADD03	to LED
9	DB7		29	ADD04	
10	DB6		30	ADD05	
11	DB5		31	ADD06	
12	DB4	to buffers and LEDs	32	ADD07	All open-circuit
13	DB3		33	ADD08	
14	DB2		34	ADD09	
15	DB1		35	ADD10	
16	DB0		36	ADD11	
17	SENSA	Earthed	37	XIN	from clock
18	SENSB	Earthed	38	XOUT	open circuit
19	FLGO	to LED	39	NADS	to LED
20	GND	to negative(earth)	40	VCC	to +5 V

INVENTORY

ICs

1 x INS8060
2 x 74LS126
1 x 74LS132

Other Semiconductors

20 x miniature LEDs (18 fitted initially, other two used later.)

Resistors

20 x 2k7; 1/8 W
6 x 10k 1/8 W
1 x 4k7 1/8 W
1 x 560R, 1/8 W

Capacitors, all 12V working or more.

1 x 0.1 uF
1 x 6.8uF
1 x 25 uF
1 x 250 uF

Hardware

1 x Eurobreadboard (later type with numbered rows and lettered columns).
10 x miniature toggle switches. (DBS0 to DBS7, SIN, RESET)
1 x miniature push-button switch (PUSH)
2 x 8BA bolts & nuts (to secure Eurobreadboard to panel)
Aluminium panel, about 260 mm x 100 mm
Wire, 18 gauge, solid core; or 1/0.6 mm
NOTE: DO NOT USE STRANDED WIRE FOR EUROREADBOARD WIRING.

MPU's BY EXPERIMENT

TABLE 2

EUROBREADBOARD CONNECTIONS

CHIPS: INS8060 Pin 1 on line A1
74LS126 No. 1 has pin 1 on line C1 ; No. 2 has pin 1 on C9
74LS132 Pin 1 on C17.

Supplies: X1 and Y2 are linked and used for +5 V.
X2 and Y1 are linked and used for earth.

In the table, NC means no connections, and SW indicates a connection to a switch, the centre connection of the toggle switches.

Pin	Connection	Pin	Connection	Pin	Connection	Pin	Connection
A1	NC	B10	NC	C1	link to C8	D1	link to Y2
A2	link to X1; D18	B11	NC	C2	link to DBS7	D2	link to D8
A3	link to Y1	B12	NC	C3	link to A9	D3	link to DBS5
A4	2k7 to A22	B13	2k7 to B25	C4	link to C8	D4	link to A11
A5	4k7 to X1	B14	2k7 to B24	C5	link to DBS6	D5	link to D8
A6	link to D23	B15	2k7 to B23	C6	link to A10	D6	link to DBS4
A7	10k to Y1; reset SW	B16	2k7 to B22	C7	link to X2	D7	link to A12
A8	link to X1	B17	10k to X2. link to SIN SW	C8	links C1,C4,C9,C12,D20	D8	links D2,D5,D10,D13,D20
A9	link to DLED7; C3	B18	2k7 to C25	C9	link to C8	D9	link to Y2
A10	link to DLED6; C6	B19	2k7 to A25	C10	link to DBS3	D10	link to D8
A11	link to DLED5; D4	B20	2k7 to A24	C11	link to A13	D11	link to DBS1
A12	link to DLED4; D7	B21	NC	C12	link to C8	D12	link to A15
A13	link to DLED3; C11	B22	2k7 to B16; LED to X2	C13	link to DBS2	D13	link to D8
A14	link to DLED2; C14	B23	2k7 to B15; LED to X2	C14	link to A14	D14	link to DBS0
A15	link to DLED1; D12	B24	2k7 to B14; LED to X2	C15	link to X2	D15	link to A16
A16	link to DLED0; D15	B25	2k7 to B13; LED to X2	C16	NC	D16	links B2; 2k7 to D25
A17	link to Y1	B1	link to X1	C17	NC	D17	link to Y2
A18	link to Y1	B2	link to D16	C18	NC	D18	link to A2
A19	2k7 to A23	B3	NC	C19	NC	D19	10k to Y2
A20	link to Y1	B4	link to C22	C20	560R to C22; C ⁺ to X2	D20	links to D8; C8
A21	NC	B5	NC	C21	link to Y2	D21	10k to Y2
A22	2k7 to A4; LED to X2	B6	NC	C22	560R to C20; link to B4	D22	links to P/B SW; 10k to Y2
A23	2k7 to A19; LED to X2	B7	NC	C23	link to X2	D23	link to A6
A24	2k7 to B20; LED to X2	B8	NC	C24	NC	D24	NC
A25	2k7 to B19; LED to X2	B9	NC	C25	2k7 to B18; LED to X2	D25	2k7 to D16; LED to X2

Note: some of the NC lines are used later in the series.

ACKNOWLEDGEMENTS

I am very grateful to all the following who contributed, knowingly or otherwise, to this project.

Ben Mullett, of National Semiconductor, who patiently answered a lot of questions about slow clocking of the INS8060.

Greenbank Electronics, who supplied the 8060 and other


chips, and are always so very helpful over the phone.

DTV, who rushed data books to me at a time when no-one else could supply them.

David George Sales, who supplied the Eurobreadboards.

Watford Electronics, who supplied other bits and pieces.

Curtis Lane & Co (Sudbury) who printed the photos.



10. Veroboard layout for LED and resistors, copper side. Note track breaks and check LED polarity before fitting.

computing today

technical book service

What Is A Microprocessor ?

2 Cassette tapes plus a 72 page book deal with many aspects of microprocessors including Binary and Hexadecimal counting, Programming etc. **£10.75.**

NEW:

Adams, C. BEGINNERS GUIDE TO COMPUTERS AND MICROPROCESSORS WITH PROJECTS **£5.60**

Understanding building programming and operating your own microcomputer.

NEW:

Albrecht, B. BASIC FOR HOME COMPUTERS. A self teaching guide **£4.75**

Shows you how to read, write and understand basic programming language used in the new personal size microcomputers.

Albrecht B. BASIC. A self teaching guide (2nd edition) **£4.50**

Teach yourself the programming language BASIC. You will learn how to use the computer as a tool in home or office and you will need no special maths or science background.

Alcock, D. ILLUSTRATING BASIC **£2.60**

This book presents a popular and widely available language called BASIC, and explains how to write simple programs.

Altman, I. MICROPROCESSORS **£10.65**

Gives a general overview of the technology design ideas and explains practical applications.

Altman, L. APPLYING MICROPROCESSORS **£12.00**

Follow volume which takes you into the second and third generation devices.

Aspinall, D. INTRO TO MICROPROCESSORS **£6.40**

Explains the characteristics of the component.

NEW:

Barden, W. Z-80 MICROCOMPUTER HANDBOOK **£7.65**

Barden, W. HOW TO BUY AND USE MINI-COMPUTERS AND MICROCOMPUTERS **£7.75**

Discusses these smaller computers and shows how they can be used in a variety of practical and recreational tasks in the home or business.

Barden, W. HOW TO PROGRAM MICRO-COMPUTERS **£7.00**

This book explains assembly language programming of microcomputers based on the Intel 8080, Motorola MC6800 and MOS Technology MCS6502 micro-processor.

Barna, A. INTRODUCTION TO MICRO-COMPUTERS AND MICROPROCESSORS **£7.50**

Provides the basic knowledge required to understand microprocessor systems. Presents a fundamental discussion of many topics in both hardware and software.

Bibbero, R. J. MICROPROCESSORS IN INSTRUMENTS AND CONTROL **£12.45**

Introduces the background elements, paying particular regard to the dynamics and computational instrumentation required to accomplish real-time data processing tasks.

Lancaster, D. TV TYPEWRITER COOK-BOOK **£7.75**

An in-depth coverage of tv typewriters (tv's) the only truly low cost microcomputer and small display interface.

Lancaster, D. CHEAP VIDEO COOK-BOOK **£6.50**

Lesea, A. MICROPROCESSOR INTERFACING TECHNIQUES **£7.50**

NEW:

Leventhal. INTRO TO MICROPROCESSORS **£16.70**

NEW:

Lewis, T. G. MIND APPLIANCE HOME COMPUTER APPLICATIONS **£4.75**

NEW:

Libes, S. SMALL COMPUTER SYSTEMS HANDBOOK **£5.75**

The Primer written for those new to the field of personal home computers.

NEW:

Lippiatt. ARCHITECTURE OF SMALL COMPUTER SYSTEMS **£4.35**

NEW:

Moody, R. FIRST BOOK OF MICRO-COMPUTERS **£3.85**

(the home computer owners best friend).

McGlynn, D. R. MICROPROCESSORS — Technology, Architecture & Applications **£8.40**

This introduction to the 'computer-on-a-chip' provides a clear explanation of the important new device.

McMurrin, PROGRAMMING MICRO-PROCESSORS **£5.50**

A practical programming guide that includes architecture, arithmetic/logic operations, fixed and floating point computations, data exchange with peripheral devices computers and other programming aids.

NEW:

Nagin, P. BASIC WITH STYLE **£4.00**

Programming Proverbs. Principles of good programming with numerous examples to improve programming style and producing.

NEW:

Ogden. SOFTWARE DESIGN FOR MICRO-COMPUTERS **£7.00**

NEW:

Ogden. MICROCOMPUTER DESIGN **£7.05**

Peatman, J. B. MICROCOMPUTER BASED DESIGN **£19.00**

This book is intended for undergraduate courses on microprocessors.

NEW:

Bursky, D. MICROCOMPUTER BOARD DATA MANUAL £5.40

Bursky, D. MICROPROCESSOR DATA £5.40

Includes complete description of the processor. Support circuits, Architecture, Software, etc.

Coan, J. S. BASIC BASIC £7.50

An introduction to computer programming in BASIC language.

Coan, J. S. ADVANCED BASIC £7.30

Applications and problems.

NEW:

Duncan. MICROPROCESSOR SOFTWARE ENGINEERING £13.50

NEW:

Freiberger, S. CONSUMERS GUIDE TO PERSONAL COMPUTING AND MICROCOMPUTERS £5.50

NEW:

Frenzel, L. GETTING ACQUAINTED WITH MICROPROCESSORS £7.10

This is an invaluable book for those who want to know more about hobby and personal computing.

Gilmore, C. M. BEGINNERS GUIDE TO MICROPROCESSORS £4.75

Gosling, R. E. BEGINNING BASIC £3.25

Introduces BASIC to first time users.

Graham, N. MICROPROCESSOR PROGRAMMING FOR COMPUTER HOBBYISTS £7.00

Haviland, N. P. THE COMPULATOR BOOK £6.20

Building super calculators and minicomputer hardware with calculator chips.

Heiserman, D. L. MINIPROCESSORS FROM CALCULATORS TO COMPUTERS £4.85

Hilburn, J. L. MICROCOMPUTERS, MICROPROCESSORS, HARDWARE, SOFTWARE AND APPLICATIONS £16.95

Complete and practical introduction to the design, programming operation, uses and maintenance of modern microprocessors, their integrated circuits and other components.

Klingman, E. MICROPROCESSOR SYSTEMS DESIGN £16.95

Outstanding for its information on real microprocessors, this text is both an introduction and a detailed information source treating over a dozen processors, including new third generation devices. No prior knowledge of microprocessors or microelectronics is required for the reader.

Kemeny, J. G. BASIC PROGRAMMING £6.10

A basic text.

Korn, G. A. MICROPROCESSOR AND SMALL DIGITAL COMPUTER SYSTEMS FOR ENGINEERS AND SCIENTISTS £19.00

This book covers the types, languages, design software and applications of microprocessors.

Rao, G. U. MICROPROCESSOR AND MICROPROCESSOR SYSTEMS £20.50

A completely up-to-date report on the state-of-the-art of microprocessors and microcomputers written by one of the leading experts.

Rony, P. H. THE 8080A BUGBOOK: Microcomputer Interfacing & Programming £8.15

The principles, concepts and applications of an 8-bit microcomputer based on the 8080 microprocessor IU chip. The emphasis is on a computer as a controller.

Scelbi. 6800 SOFTWARE GOURMET GUIDE AND COOKBOOK £7.80

Scelbi. 8080 SOFTWARE GOURMET GUIDE AND COOKBOOK £7.80

Scelbi. UNDERSTANDING MICROCOMPUTERS £7.60

Gives the fundamental concepts of virtually all microcomputers.

NEW:

Schoman, K. THE BASIC WORKBOOK £3.70

Creative techniques for beginning programmers.

NEW:

Sirion, D. BASIC FROM THE GROUND UP £6.00

Soucek, B. MICROPROCESSORS AND MICROCOMPUTERS £18.80

Here is a description of the applications programming and interfacing techniques common to all microprocessors.

NEW:

Spracklen, D. SARGON £9.75

A computer chess program in Z-80 assembly language.

NEW:

Tracton. 57 PRACTICAL PROGRAMS & GAMES IN BASIC £6.40

Programs for everything from Space war games to Blackjack.

Waite. M. MICROCOMPUTER PRIMER £6.25

Introduces the beginner to the basic principles of the microcomputer.

Ward. MICROPROCESSOR / MICROPROGRAMMING HANDBOOK £6.00

Authoritative practical guide to microprocessor construction programming and applications.

NEW:

Veronis. MICROPROCESSOR £12.85

Zaks, R. INTRODUCTION TO PERSONAL AND BUSINESS COMPUTING £7.50

Zaks, R. MICROPROCESSORS FROM CHIPS TO SYSTEMS £7.50

Note that all prices include postage and packing. Please make cheques, etc, payable to Computing Today Book Service (Payment in U.K. currency only please) and send to:

Computing Today Book Service,
P.O. Box 79,
Maidenhead, Berks.



After trying out the much publicised Superboard II for a month David Sinfield presents his report

The Superboard from Ohio Scientific is a ready-built single board Mostek 6502 based micro. On board there is 4K of RAM as standard and eight empty sockets for a further 4K. Further expansion is possible using the OSI 48 line bus. Ohio have peripherals available using this bus and I understand that they will be coming into this country soon. 8K Microsoft BASIC is in ROM as is the 65 V machine code monitor.

Wafercon sockets for cassette, video, and simply implemented RS232 ports are provided as well as the OSI bus, which is via a DIL socket. The wafercons are not ideal as it is difficult to provide a mechanically sound joint and if disturbed too often the wiring can come adrift.

The software scanned keyboard has 53 keys, positive but sensitive, but some of these seem to have no function. Auto repeat operates if any key is held down for more than about half a second.

On the documentation front there are four slim volumes entitled Users Manual, Technical Report, BASIC Reference Manual and Graphics Reference Manual. These get you through the initial stages of BASIC programming but anyone new to computing would be well advised to provide themselves with a decent BASIC text book and anything they could find on the 6502.

Having listed what you do get just a mention of what's needed before Superboard is up and running. First a power supply capable of 5 V @ 3 A (more if extra memory is added) with a ripple of less than 200 mV.

The video output is a conventional NSTC to run a

Mr D. Sinfield

monitor or a modified TV. If an unmodified TV is to be used a UHF modulator will be needed. Using our circuit the modulator can be encased with and powered by the power supply. All the components, including the modulator are readily available and only a modicum of electronic knowledge is needed to put them together. Alternatively a ready built PSU e.g. Tooting Computing "BIAS", can be obtained.

Any cassette can be used as long as it has a microphone input and extension speaker or earphone socket though some fiddling with the volume control may be necessary.

Orft We Jolly Well Go


So with all the connections in the right places according to the instruction manual and the power on things should start to happen. Our first attempt lead to a "rolling" picture and as our TV didn't have the vertical hold control accessible we were stuck. The problem of course is that Superboard has a 60Hz sync pulse on the video to conform with the U.S. standard. Most TV's will lock up with no problem in fact out of 7 televisions I have tried the only two that didn't work were those in the C.T. offices! Wavering of the display can sometimes be cured by moving the power supply as far as possible away from the TV.

Assuming then that when switched on there is a steady display of random characters the machine is ready for use and can be initialised by pressing the break key. This produces the prompt "D C W or M". Before any key is accepted the shift lock key must be locked down. It is only used in the released position for lower case. D boots up the disc software and as I didn't have a disc I'll skip this one.

C stands for "cold start" and puts the machine into BASIC, clearing the RAM. At this stage the memory size can be specified. This enables memory space to be reserved and protected against everything except turning off and cold starting — very useful if the "clear screen" subroutine mentioned later is to be used. If memory size is not specified a memory test procedure is instituted and the amount of RAM available is reported. Terminal width can now be selected. A reply of between 16 and 72 inserts a carriage return after that number of characters. So formatting for a variety of printers and terminals is simple. The video output is limited to 24 characters per line so the display is only affected if a terminal width of between 16 and 24 characters is selected. In this case it can be used to compensate for right hand over-scan, which can be a problem on some televisions. The machine I had was modified so that the horizontal framing of the picture could be adjusted. Setting the terminal width to 24 characters leads to two carriage returns being inserted, one from the VDU circuitry and one by the terminal width control, at the end of each line of display aiding legibility but of course halving the number of lines it is possible to get on the screen. The machine is now in BASIC mode but before going into this I'll mention the other two initialising modes.

W stands for "warm start" and calls up BASIC after a break without clearing RAM thereby preserving any programs that may be there. M after break calls up the monitor and programs can be written, inspected and run in machine code. The contents of one memory location are displayed and any location can be stepped to and its contents altered using the "/" and "." keys as described in table 2. Anyone wishing to use machine code on the Superboard should arm themselves with a 6502 manual, because the Ohio manuals are little help. I understand that there is a tape assembler

SUPERBOARD II REVIEW



The left hand photo shows the Superboard plugged into Lotus Sound's PSU and modulator box. On the right hand photo the spare RAM sockets are clearly visible at the rear right of the board. The veroboard add-on at centre rear is a slugging circuit to try to stabilize the timebase circuit so it will sync on 50Hz.

which is not generally available over here although your local Superboard supplier may be able to obtain one.

Back To BASIC

To anyone familiar with the BASIC language Microsoft's version will present few surprises. The full list of commands etc. available are given in the table. The only facility I hadn't seen before was being able to incorporate the list command in a program. Not something with any obvious use. But for a program requiring updating, the data statements can be listed along with explanatory REM's and then retyped by the user. Might work — mightn't it?

Error messages consist of one letter and a graphic and are adequately explained in the BASIC manual. Other than this the BASIC seems standard but is fast enough to make animated graphics in high level language feasible.

The Ins And Outs (Or How To Get Loaded And Save It!)

The only peripheral I had was a battered old cassette machine but according to the manual the procedure is much the same whatever you hang on the end of your Superboard.

The SAVE command does not produce immediate results but henceforth until a load command is encountered all that goes on to the VDU is written to the serial port.

Using the SAVE command not only programs can be recorded but sequential files can easily be set up using PRINT statements. As well as this, data files can be set up in the same way and used with INPUT statements in a program. The "trick" as the manual puts it is to make sure that the INPUT statement is encountered before the data.

The procedure thus for saving a program is SAVE (return key) LIST (return key) and as the program is written onto the screen it is also written to the cassette.

LOAD cancels any previous SAVE and opens the port for incoming information from cassette, modem or any other suitable source. The machine treats this information the same as if it had come from the keyboard and displays it as it is read.

All in all a very straightforward I/O system. The only thing it really lacks is both remote switching of the cassette and program search facilities. These two failings together can lead to some problems if more than one program is recorded per side of each cassette.

I have a couple of suggestions of how to make things easier; save a RUN command after each program or save a LOAD command. In this way even if programs follow one another very closely on the tape it is not so likely that the second will overwrite the first.

The Display

First impressions are that the alphanumerics are squashed vertically, an impression added to by the fact that there is very little separation between lines. It doesn't take long to

According to the graphics manual the display is 25 x 25 but I only counted 24 characters across. This may not sound very significant but it means that the screen locations for POKE and PEEK statements are not as shown on the matrix in the graphics manual. Add to this the fact that the memory location for the beginning of one line doesn't follow numerically from the end of the line above and you have unnecessary problems in POKEing graphics to specific locations. The "missing" screen locations are in fact to be found off screen to the right and this is where the Starship Enterprise goes to when it's not visible — It's not in hyperspace after all. A little experimental POKEing soon gives some idea of what is where in the VDU memory.

Another omission on the display side is the lack of an in-built "clear screen" function and to achieve this the manual suggests that you either:

The circuit diagram shows a power supply and modulator. It starts with a 240 VAC input connected to a LAMP and a MAIN NEON indicator. The power is then stepped down by a transformer with a 250V:10V ratio. The secondary winding is connected to a 3 AMP BRIDGE rectifier. The output of the bridge is filtered by a 15000uF 40V capacitor. The positive rail is then connected to a 50uF 35V capacitor, which provides the +5V supply to the LM 3231 modulator. The negative rail is connected to ground. The LM 3231 modulator is also connected to a 220nF capacitor to ground. The output of the modulator is connected to a 50uF 10V capacitor, which provides the 0V supply to the UHF MOD block. The UHF MOD block has VIDEO IN and VIDEO OUT connections, both of which are connected to ground.

The latter is by far the most satisfactory, the routine being called at any time during a BASIC program using the `USR` command.

As well as the 8 spare RAM sockets on board the memory can be expanded via the 48 line bus. According to the manual Ohio have lots of plug-in goodies including memory, disks, A/D, D/A etc. and no doubt they will be filtering into this country — hopefully in a steadier stream than they have been so far.

Overall a useful machine despite my grouses on the display. Certainly at around £300 up and running for 4K RAM and 8K BASIC in ROM Superboard represents value for money. It is very tempting to compare the machine with others available but it seems to fall in between the extremes. It is not merely the enthusiasts machine it appears at first sight, the BASIC and potential for adding peripherals such as disc and printers without too much modification must mean that "serious" users will find it worth a look.

Our thanks are due to Lotus Sound for lending us the machine for a generous period, in order to prepare an accurate report of its facilities.

Fig. 1. Circuit diagram for the recommended power supply and modulator.

SUPERBOARD II REVIEW

Table 1

BASIC commands available		IF.THEN	Conditional statement. The THEN will only be executed if the IF is true. Can incorporate AND, OR or NOR.
LIST	Lists program Range of lines to be listed can be specified	GOSUB.RETURN	Jumps to specified line number. On encountering RETURN program jumps to line number following GOSUB
RUN	Starts program execution at lowest line number Line number for start may be specified	INPUT	Takes in data from keyboard or cassette
NEW	Deletes current program	POKE	Loads specified memory location with value
CONT	Continues program after a Control C or STOP	PEEK	Determines value of specified memory location
LOAD	Alerts machine to input from serial port	RESTORE	Restores initial values of DATA statements
SAVE	Causes subjects of PRINT or LIST statements to be written to serial port	PRINT	Outputs information. Can be abbreviated to ?.
		STOP	Stops program execution, program can be restarted using CONT
		Functions	
<u>Operators</u>			
=	Assigns value to variable	ABS	Returns the absolute value of variable ignoring sign
-	Negation	INT	"Rounds down" and returns next lowest whole number
	Eponentiation	RND	Generates random number
*	Multiplication	SGN	Positive numbers result in "1", negative numbers result in "0"
/	Division	SIN	} Trig functions (machine works in radians)
+	Addition	COS	
<>	Inequality	TAN	
>	Is greater than	ATN	
<	Is less than	SQR	Square root
≤	Is less than or equal to	TAB	Spaces print head
≥	Is greater than or equal to	USR	Jumps to machine code sub-routine
<u>Statements</u>		FRE	Gives number of bytes left in workspace
DATA	When READ is encountered information is taken sequentially from DATA statements	LOG	Returns natural Log
DEF	Identifies a user defined function	POS	Returns position of terminal print head
DIM	Defines dimension(s) or array(s)	SPC	Returns specified number of spaces
END	Terminates program	<u>Strings 'n' Things</u>	
FOR.NEXT	Used for incremental loops. Size of step can be specified	Any character or group of characters in a string can be isolated using LEFT\$, MID\$ and RIGHT\$. Strings are permitted up to 255 characters long.	
GOTO	Jumps to line specified. Can be incorporated into IF statements		

Table 2

Special key functions

@ (shift P)	Erases line being typed
- (shift 0)	Erases last character
Control C	Interrupts execution of program or list.
"/"	Amend contents of memory location displayed
."	Step to specified memory location
G	Goto specified location and runs program



The twin mini floppy disc system provides off line storage of programs and data using IBM 3740 compatible formatting providing 128 bytes per sector 16 sectors per track 40 tracks per disc. Media is reversible.

The drive and controller are housed in a saddle maintaining an integrated configuration, one of the major features of the PET. Connection is via the PET memory or IEE port. The system comes complete with a PROM for booting the disc resident P-DOS into RAM. P-DOS is completely transparent to BASIC. Control of the disc system is via PET BASIC USR instruction with simple commands from either the keyboard or under program control.

The following commands are available LOAD, SAVE, CREATE, DELETE and CATALOGUE. The file management system provides for up to 8 files to be opened concurrently. Files can be opened in READ, WRITE, UPDATE and APPEND mode. The user may write his own disc system modules to expand the facilities of the disc resident system.

£850.00 excluding VAT.

Applications programs available for sales, purchase and general ledger as well as stock control, payroll and cost accounting.

PICO BYTE 65 VICEROY CLOSE.
BRISTOL.
EDGBASTON
BIRMINGHAM B5 7UT

IN SCOTLAND

IN SCOTLAND

NASCOM 1

Z80 Microcomputer kit

Undoubtedly the finest value for money kit available anywhere. Fully socketed.

INTERFACE FOR:

- TV (UHF)
- TV Monitor
- Cassette
- Teletype
- 32k Ram expansion board

May be seen working — 9 a.m. — 5 p.m. Mon — Fri
Callers welcome

Please note that the Nascom is occasionally in use at exhibitions.

Please telephone before calling to avoid disappointment.

Price £165.00 + VAT (8%)

8K BASIC ON TAPE £37.80

Digivision agents — professional monitors at sensible prices in kit form please send for details.

Now in stock: 8K RAM, 16K RAM, 32K RAM, BUFFER BOARDS, 3K SUPER TINY BASIC ZEAP ASSEMBLER, MINI-MOTHER BOARDS. We now stock a variety of books on the subject of personal computing.

Callers welcome



STRATHAND
44 ST. ANDREW'S SQ.
GLASGOW G1 5PL
041-552 6731

Callers welcome



Tel. order welcome with Access and Barclaycard

WHICH BRITISH SYSTEM CAN OFFER THE FOLLOWING:

- ★ COLOUR — Aerial Input, Alphanumerics and Graphics
- ★ CEEFAX — BBC Television Teletext service
- ★ ORACLE — IBA Television Teletext service
- ★ BASIC — ROM — Resident Interpreter
- ★ MONITOR — Motorola 6800 Machine Code
- ★ VIEWDATA — Instant Information service

TECS:

**TECHNALOGICS
EXPANABLE
COMPUTER
SYSTEM**

Prices start at
around **£360**



Rack Mounting and Tabletop Versions (illustrated).
The logical development everyone has been waiting for.
Please send large size for details to:

TECHNALOGICS (DEPT. CT)

**8 EGERTON STREET, LIVERPOOL
L8 7LY**

Triton Breakpoint Routine

Mr. Andrew F. Lack

Unfortunately the standard TRITON monitor (V4.1) does not have a BREAK routine. A break routine allows the user to break a machine code programme and to examine the status of all the internal registers — it is a kind of 'snapshot' of the inside of the CPU where it is believed a fault may be occurring.

This snapshot must give the status of the flags as well as the internal registers. The biggest problem is how to convert the binary contents of the registers to 2 hexadecimal digits, and then print them. This is easily got round here by making use of the stack pointer and the monitor's LIST routine, which converts bytes of RAM into 2 hex digits. The routine is called by interrupt 3 — a halt instruction (76) being placed in the next 'valid' instruction byte following the suspected fault (i.e. not inside an address field, for example). When the CPU halts, it will respond to interrupt 3, and jump to Debug and stop again. List can be called via an interrupt 2 and then the register's status can be found. Debug, listing and use.

```

1618  C3  F0  14  ;JMP, 14F0  Call to debug
Debug
14F0  31  F0  14  ;LXI SP, 14F0
14F3  F5          ;PUSH PSW
14F4  C5          ;PUSH B
14F5  D5          ;PUSH D
14F6  E5          ;PUSH H
14F7  FB          ;EI
14F8  76          ;HALT

```

Use

As stated above, 76 (HALT) should be entered after the fault (or suspected fault). Interrupt 3 is then operated, and then interrupt 2 to take the user to the monitor L14E1 is entered and this lists the region of RAM that holds the registers contents. The RAM is designated as follows:—

```

14E8  L
14E9  H
14EA  E
14EB  D
14EC  C
14ED  B
14EE  Flags (PSW)
14EF  A

```

The contents of the SP and PC is not, however, held on the stack.

Debug gives the PSW at the instance of call. The PSW is made up as follows:—

7	6	5	4	3	2	1	0	BIT NO.
S	Z	0	AC	0	P	1	C	

Note that bits 3 and 5 are always 0 and bit 1 is always 1.

Thus, if for example the data in byte 14EE was 95 after a debug call, then this would correspond to the flags S, AC, P being set and the flags Z and C being reset. Parity is set for even parity, and S is set for negative numbers (based on the two's compliment nomenclature).

It should be remembered that bytes 1618 . . . 161A (inclusive) are reserved for the debug call address. Thus the user programme should jump round this:

```

1615  C3  1B  16
1618  C3  F0  14
161B  . . . user programme

```

Nascom Random Number Generator

Mr. E. A. Parr

The subroutines were written to provide a random number in the range 1 — 6 (i.e. a dice) for a games program running on the Nascom 1.

Several unsuccessful programs were tried which ended up giving continuous 00 or a fixed sequence. The final solution is very simple, whenever the computer is waiting for an input from the keyboard, it sits "rolling the dice" giving a true random number.

The number is held in OC50 and is read by the rest of the program. Obviously there has to be a keyboard input prior to each read of the dice.

OC50	Dice	01	Holds value of DICE
1	ROLL	3A 50 0C	Ld Dice
4		3C	Inc A
5		FE 07	Compare with 7
7		20 02	Skip if not 7
9		3E 01	Load A with 1
B		32 50 0C	Replace dice
E		C9	Return
OC5F	INPUT	CD 51 0C	GO SUB ROLL
OC62		CD 69 00	GO SUB NASBUG INPUT
			FROM KBD
5		30 F8	Jump back to input if no key pressed
7		C9	Return

When a character is required from the keyboard the instruction:—

```

CD 5F 0C      GOSUB INPUT
enters the subroutines, and they return with the character in
A and location OC50 randomised in the range 1 — 6.

```


electronics today

international

What to look for In the August Issue: On sale July 6th

STRING THING

To call this project an electronic piano would be an injustice. To call it a string ensemble likewise fails to explain all the mysteries and beauties awaiting the builder once this beast is activated. Yes it can be a piano. Yes it can play string sounds.

The designer (Tim Orr who also can be blamed or praised for the Transcendent 2000) wanted to call it a "Digital Multi-

Voice String Synthesising Keyboard Instrument". But we wouldn't let him. We couldn't think of a better title ourselves, but we still wouldn't let him. It's the way we are.

Being fitted with a CCD choraliser allows our String Thing to sound like several of 'em at once. Why not tune in and be amazed next month?



BENCH AMPLIFIER

One for the workshop or table top. How many times have you been half-way through a project and needed to test something, somehow, somewhen. And that of course is exactly when it occurs to you that there is nothing around suitable.

A bench amp is worth its weight in soldering ten times over, and if you DON'T build this you will regret it.

MICROSENSE

MPUs are definitely for you. Oh yes they are, don't give me that old line about them being all covered in mystery and incomprehension. MPUs are nice friendly little chips, and next month we've got the definitive article to prove it. Based on a book by John Miller Kirkpatrick it takes you through the subject from scratch in a thorough but light-hearted manner.

LED AUDIO DISPLAY

A really lovely little design to amaze, astound and hypnotise the entire universe. This project takes the input from your hi-fi or TV or budgie and turns it into a dazzling and bemusing shifting pattern of light upon a LED matrix.

Build it any size you like it'll add a bit of visual spice to the hi-fi rack — or simply keep mother-in-law quiet while you nip off down the local.

NASCOM PACKAGE

Mr M.J. Bell

This months NASCOM program is for a sort routine

Sort routines are many and various depending on the type of information that is required to be sorted. The way in which the sorting is carried out can be complex, and many books have been written on the subject. I have chosen the "bubble" method because it is particularly suited to the small microprocessor and is easy to understand.

What Does It Sort

The program has been designed to sort up to 65 entries of data each with a maximum length of seven characters and a minimum length of 1 character. It will handle both numbers and words or a mixture of both displaying the result with numbers first.

e.g. 86, 2, FRED, CAT4, JOHN, 3862, CAT40, XYZ.
Sorted to 2, 86, 3862, CAT4, CAT40, FRED, JOHN, XYZ.

The possible uses are therefore to sort; numbers, words, names, dates, catalogues etc.

The writer has found that 65 entries of mixed length and form have taken less than 3 seconds to be processed.

The Program

The program is entered at address 0C50. The screen is cleared and the instruction "LOAD DATA NOW" is displayed. Data is entered from the keyboard, each item separated by a comma ",". The data entered will be tabulated on the screen. Backspace is operative for the current item ONLY. When all the data has been entered an equals "=" will initiate the sort. While sorting is taking place "WAIT" is displayed at the top of the screen. On completion the sorted data is displayed in tabular form with the legend "*** DATA SORTED ***". If another set of data is required to be processed, depressing the "space" bar will reinitialise the program.

This program will sort words or numbers or letters, or a combination of both, up to a maximum of seven characters in length. To restart the program after a sort the "Space Bar" should be pressed.

MAXIMUM NUMBER OF WORDS IS 65

EXECUTE FROM 0C50


C50	3E 1E	'START'	A = 1E
C52	CD 3B 01		Call CRT
C55*	01 08 00		BC = 0008
C58	21 DF 0C		HL = 0CDD
C5B	11 E2 0C		DE = 0CE0



The authors NASCOM installed with cassette in a cabinet.

COMPUTING TODAY - JULY 1979

NASCOM PACKAGE



The flowchart for the sort program.

NASCOM PACKAGE

D03 CB 4B
D05 20 29
D07 CD 20 0D
D0A B9
D0B 28 23
D0D 18 D5
D0F CB 4B
D11 20 D1
D13 CD 20 0D
D16 00
D17 18 CB
D19 00 00
D1B 81
D1C 28 C6
D1E 18 D8

'a/n'
D20 AF
D21 CD D7 0C
D24 B8
D25 C8
D26 B9
D27 28 07
D29 18 F6

EXX
D30 D9
D31 AF
D32 77
D33 12
D34 D9
D35* 06 08
D37 CB D3
D39 D5
D3A DD E5
D3C FD E5
D3E D1
D3F E1
D40 4E
D41 1A
D42 77
D43 79
D44 12
D45 23
D46 13
D47 10 F7
D49 D1
D4A 18 98

OUTPUT

D50 3E 1E
D52 CD 3B 01
D55 21 B6 0D
D58 01 D9 0B
D5B CD 82 0D
D5E 21 C8 0D
D61 AF
D62 BE

'SORT 2'

'SORT 3'

'EXX 1'

'O/P 0'

TEST E BIT 1
JRNZ - 'EXX'
Call 'a/n'
CP = C
JRZ - 'EXX'
JR - 'NEXT'
TEST E BIT 1
JRNZ - 'NEXT'
Call 'a/n'
NOP
JR - 'NEXT'
NOP NOP
ADD C
JRZ - 'NEXT'
JR - 'SORT'

A = 0
Call 'INC'
CP = B
RZ
CP = C
JRZ - 'EXX'
JR - 'a/n'

EXX
XOR A
(HL), A
(DE), A
EXX
B = 8
Set E Bit 2
PUSH DE
PUSH IX
PUSH IY
POP DE
POP HL
C, (HL)
A, (DE)
(HL), A
A, C
(DE), A
INC HL
INC DE
DJNZ - 'EXX 1'
POP DE
JR - 'NEXT'

A = 1E
Call CRT
HL = 0DB6
BC = 0BD9
Call 'PRINT'
HL = 0DC8
XOR A
CP = (HL)

D63 28 17
D65* 06 08
D67 7E
D68 FE 00
D6A 28 08
D6C CD 3B 01
D6F 23
D70 10 F5
D72 18 F1
D74 23
D75 CD 3C 02
D78 10 FA
D7A 18 E5

END

D7C CD 3E 00
D7F C3 50 0C

PRINT

D82 7E
D83 FE 00
D85 C8
D86 02
D87 03
D88 23
D89 18 F7

MESSAGES

1 D8B **,SORT,**,,,LOAD,DATA,NOW@
2 DA7 ,,,,WAIT,,,,@
3 DB6 **,DATA,SORTED,**@

DATA MEMORY

DC8 - FEO

* Locations to be changed for different entry lengths
(See Table 1)

Note ", " indicates a "space" and @ indicates 00Hex

**SORT
TABLE 1**

To change the length of the entries make the changes as shown
in the table below:-

entry length (decimal)	0 C 5 6	0 C 7 9	0 C B 3	0 D 3 6	0 D 6 6	max number of entries (decimal)
3	04	04	CC	04	04	130
7	08	08	D0	08	08	65
15	10	10	D8	10	10	32
23	18	18	E0	18	18	21
47	30	30	F8	30	30	10

ELF II



ELF II
BOARD WITH VIDEO OUTPUT

NOW ONLY
£79.95 + £6.40 VAT



THE TRIED AND
TESTED
MICROCOMPUTER
SYSTEM
THAT EXPANDS
TO MEET
YOUR NEEDS

SPECIFICATION
*RCA 1802 8 bit microprocessor,
with 256 byte RAM
expandable to 64K bytes
*RCA 1861 video IC to display
program on TV screen via the RF
Modulator
Single Board with
Professional hex keyboard fully
decoded to eliminate the waste
of memory for keyboard decoding
circuits
Load, run and memory protect
switches
16 Registers
Interrupt, DMA and ALU
Stable crystal clock
Built in power regulator
5 slot plug in expansion bus
(less connectors)

To: Newtronics
The personal computer division of
HL Audio Ltd
138 Kingsland Road, London E2 8BY 01-739 1582
Please send me the items ticked below:
(Choose either components or wired and tested units)

	INC. VAT £
ELF II KIT COMPLETE WITH FULL WIRING INSTRUCTIONS AND OPERATING MANUAL	86.35
ELF II KIT WIRED AND TESTED	107.95
ELF II DELUXE CABINET	24.95
POWER SUPPLY (8.3V) FOR ELF II	5.40
EXPAND YOUR ELF II with the following hardware, a comprehensive range that is being continually increased through research and development.	
GIANT BOARD KIT — includes a system monitor/editor that works on all 64K bytes of possible memory; a cassette I/O routine for recording programs on an ordinary cassette; two 8 bit parallel I/O ports with handshaking for connecting the ELF II to a printer and ASC II keyboard or any 8 bit parallel interface. The serial RS 232 and 20ma TTY I/O's allow connection to printers, terminals or any serial I/O device	
GIANT BOARD WIRED AND TESTED	58.40
4K STATIC RAM BOARD KIT — Add up to 16K on board. ELF II will accept up to 64K and is addressable to any page to 64K. Requires ELF II expansion power supply	76.00
4K STATIC RAM BOARD WIRED AND TESTED	97.15
EXPANSION POWER SUPPLY — required when adding 4K RAM Boards	20.52
ASC II KEYBOARD KIT — Complete with connector to plug directly into the ELF II Giant Board and is powered by the ELF II Expansion Power Supply. The ASC II Keyboard follows the standard typewriter configuration and generates the entire 128 character ASC II upper/lower case set with 96 printable characters, with onboard regulator, parity logic selection and 4 handshake signals	54.63
ASC II KEYBOARD WIRED AND TESTED	76.22
ASC II DELUXE CABINET	16.22
RF MODULATOR to use with TV	3.00
KLUGE PROTOTYPE BOARD — accepts up to 36 IC's in 40, 24, 18, 16 pin formats with space available for an onboard regulator	13.62
56 PIN GOLD PLATED CONNECTORS (One required for each add on Board)	4.32
ELF II LIGHT PEN TO WRITE OR DRAW ON TV SCREEN	7.02
AVAILABLE SHORTLY TO EXTEND THE SCOPE OF YOUR ELF II:	
VIDEO GRAPHICS BOARD	
VIDEO DISPLAY BOARD KIT — 32 or 64 characters 16 line upper and lower case	75.55
VIDEO DISPLAY BOARD WIRED AND TESTED	97.15
THE SOFTWARE that makes ELF II an ideal machine with which to learn computer techniques rapidly:	
ELF II TINY BASIC CASSETTE TAPE — Makes programming even easier. Commands include: Save, Load, Let, If/Then, Print, Goto, Gosub, Return, End, Rem, Clear, List, Run, Plot, Peek and Poke. TINY BASIC ALSO INCLUDES: 16 bit integer arithmetic + x - () and 26 variables A-Z and also comes fully documented with an alpha-numeric generator for direct display on your TV	14.58
ELF-BUG Monitor Cassette eliminates the need to single step through a program to find the contents, with the ability to run and edit from any point in the memory	14.58
'SHORT COURSE IN PROGRAMMING' by Tom Pittman. Written specifically for the ELF II as a step-by-step course which fully exploits the potential of ELF II	4.00
'SHORT COURSE IN TINY BASIC' by Tom Pittman teaches how to program in Tiny Basic	4.00
RCA 1802 Users Manual	4.00

I enclose cheque/PO No.
(Add £2 post and packing for orders over £20)
or charge
Barclaycard No.
Access Card No.

Name

Address

Signature

Hours of business: Mon-Fri 9.30 — 5.30, Sat 9.30 — 1.00

Dealer Enquiries Welcome

Telephone Orders Accepted 01-739 1582

for £

POWER-one

D.C. POWER SUPPLIES

Now, like Intel, Motorola and National you can buy Power-One open frame power supplies and enjoy quality and reliability at LOW LOW prices. Over 70 different models to choose from including floppy disc drive supplies as well as single, double, triple and quad output.



Single Output

5V at 2.7A w/OVP	£19.50
5V at 5.4A w/OVP	£41.50
12V at 6A	£67.50
15V at 5.4A	£67.50

Dual Output

±12 to 15V at 1.5A	£41.00
±18 to 24V at 0.4A	£32.50
±5V at 5.4A w/OVP	£78.00

Floppy Disc Drive Supplies

— with connectors and cables for Shugart drives if required.

CP-249 — drives one mini drive	£33.00
CP-323 — drives two mini drives	£60.00
CP-205 — drives one Shugart SA800 or equivalent 8" drive	£58.00
CP-206 — drives two SA800	£76.00

Triple Output

5V, 9-15V, -5, -12, -15V at 1.8A to 10.6A	From £41.00 to £137.00
---	------------------------

Discount available to bona-fide educational establishments. Quantity discounts start at five units. Trade enquiries welcome.
Send large SAE for full catalogue and price list.



COMPUTERS LTD.,

133 Woodham Lane, New Haw, Weybridge, Surrey
KT15 3NJ. Telex. 8813487

P. & R. COMPUTER SHOP

3982 IBM I/O Printers	£170.00
Re-furnished	£230.00 inc VAT
AScii Keyboards	£40.00
ASR Teletypes	From £175.00
KSR Teletypes	From £90.00
Fans 4", 5" and 6"	From £3.50
Paper Tape Readers	From £18.00
Paper Tape Punches	From £30.00
VDUs IBM 2260 Monitors including Keyboards	£30.00
Various power supplies and — store cores, test equipment. Plus an assortment of miscellaneous computer equipment	

COME AND LOOK AROUND

**Solcott Mill, Goldhanger Road,
Heybridge, Essex. Phone Maldon
57440**



American shows. One up on England?

It is a rare event nowadays if a month goes by without at least one invitation to a Press reception or exhibition, with its attendant food and drink. The rate of change in the industry today tends to mean that if you miss out on going to one of these you may well miss something of vital importance. Sods Law and all that! On the other hand of course if you go to all of them then you never get any work done at all.


At the beginning of April news of a show reached my ears, shows are getting almost as common as Press do's now, and this one really caught my attention. It was to be held in sunny Florida. Visions of sun, palmy beaches, sun-tanned bodies all appeared before me so I went to see if the Editor's arm could be twisted. After a considerable amount of very hard bargaining it was agreed that I could go so the rest of my story is told in words and pictures from the show.

I should point out at this early stage that I am by no means a professional photographer and the quality of some of the photographs may have suffered due to an excess of the duty-free whisky and a local brew known as "Flaming Hurricane".



Anticlockwise:—
Bright and early on Saturday morning, the attendance was well up on Friday but still no crowds. A new Tandy printer, Centronics by looks, will it come over here? A small business system based on the Horizon but with double density disks.

SHOW REPORT



Micro-computers, Micro-show

The show itself was called the Southern Micro-computer Industries Show, SMIS for short, and was held in Exposition Hall, Orlando, Florida. It really was a Micro-fair in all the senses of the word as there were only about two dozen exhibitors present. I attended on both the Friday and Saturday, mainly to avoid the bulk of the general public, talked to as many of the local exhibitors as I could, and sat in on a couple of the seminars as well. For the general public the show cost \$3, that's about £1.50, but that included free access to the seminars as well so the price was not too high.


The tone of the whole show was very informal with everybody willing to talk and be of any assistance to the public, a welcome change from some of the British shows that I have been to. The thing that seemed to surprise them most of all was to find a British journalist wandering around!

The areas of interest that the show covered were from the home and small business systems area, there was only one stand that was selling anything at all for the home constructor. The range of machines on show was very varied, they ranged from an AIM 65 right up to an LSI 11, but there were some notable exceptions, not a single PET or KIM or even a Superboard. There was only one new machine there called the INFORMER, an SCMP/Z80 based machine running on the ubiquitous S100 bus with integral discs. Unfortunately there appears to be little hope of it arriving on this side of the puddle.



Clockwise:—
A wierd Tandy game called Eggs.
The excellent Cromenco Three running a business system. The old and faithful Imsai VDP 80 with its neat integral disks, again running a small business system. The sharp end of a 747, the INS is the central console and is computer controlled. The aircraft flies between accurately known points on the Earth.





As you will be able to see from some of the photos the American versions of familiar machines are sometimes slightly different, the Compucolor that we reviewed last month has had another facelift, apparently to iron out a few bugs that we did not find when we reviewed the machine last month. The new look machine will be the one that is shipped over here apparently.

British Micro's?

A large number of the exhibitors had not even heard of such famous British systems as Nascom, Rair or Micros but a generally expressed view was a desire to come over to Europe and see just what is going on. The pricing of systems over here raised even more eyebrows, the Dollars to Pounds rule still seems to be holding true unfortunately.

Some of the most amusing moments of the whole show were to be found in the seminar hall, I attended three of the lectures and found them all to be on a very low technical level and held almost like a club evening. The first one was given by a gentleman called Gary Dozier who runs a mail order book and program service in New Hampshire. The lecture was entitled 'How I Stopped Fearing & Loved The Computer' and was really a life history of how he started out in the game, most entertaining. He finished off the session by offering helpful advice and answering any questions from the floor. The second lecture was a rather more serious affair entitled 'Analog Devices—Real Time



Anticlockwise:—
A new high-speed line printer from NEC being used to generate "computer photos". An Attache stripped down. A Texas 9900 based machine with integral dual cassettes and thermal printer, dual floppies and a Centronics 702 on-line. It played a real mean game of Star Trek.

SHOW REPORT




Interface To Microprocessing" in which Gary Miller explained just what you could do with an analogue input board and how this helped you to control your environment with an analogue output board, this was in fact the best given talk on the subject that I have heard and I think quite a few people produced their cheque books at this stand in the main hall.

The third talk was given on "The Role Of Microcomputers In Business Today" by Mike Kelly of Veytec Inc. but was really about the use of modems and how to connect up your home micro to your business machine over the telephone. The Americans seem to have little problem in hooking up modems unlike this country, that possibly accounts for the large proportion of the home computer people in that country who use on-line systems.

In Excelsis

In summary the show was well worth attending as it revealed a lot about what makes the American market tick, as well as establishing valuable links with their personnel. As for the thoughts of sun, sea and sand? It rained!

Many thanks are due to the people who made my brief visit a pleasure, Mr Bud Felsburg who organised the show, Mr Gary Dozier and Mr Gary Miller who introduced me to the American drinking habits and to Capt. Thomas of British Airways who allowed me on the flight deck of the 747 to take some photos, most of which Miami customs ruined with their 'safe' X-Ray machine.



Clockwise:—
A reconfigured
Compucolor with
its new keyboard.

The bugs that
occurred with the
HT have been
ironed out. Gary
Miller expounding
on Analog Devices.

An AIM 65 in a
briefcase, with its
acoustic coupler
it can be used as a
remote system. Not
a Superboard but
the guts of a
Challenger.

POWERFUL

Pet BUSINESS PROGRAMS

Now
PETACT BUSINESS SYSTEMS
offer mainframe quality at micro prices:

SALES ACCOUNTING

provides all the facilities for maintenance of Sales Ledger, preparation of a list of outstanding balances and printing of statements

Cassette based system £225+VAT Disk version £350+VAT

PURCHASE ACCOUNTING

handles Purchase Ledger, preparation of a list of outstanding balances, printing of remittance advices.

Cassette based system £225+VAT Disk version £350+VAT

Written by ACT's own software team, each package handles 200 accounts and 800 transactions in memory at once giving true real time operation on a 32K PET and printer (typical cost £1,350+VAT). Alternatively the disk-based version may be used with the addition of a dual mini floppy drive (price £740+VAT)

Other PETACT BUSINESS SYSTEMS

include: Invoicing, Payroll, Stock Control, Nominal Ledger, and Management Information

Send for a free copy of our new 16-page catalogue. It contains details over 160 programs from £3 to £375, covering Business Packages, Programming Aids to help you make the most of your PET and some super Games to play with it. Here are just a few examples:

TRY THESE PROGRAMS AT YOUR NEAREST PET DEALER *Prices include VAT*

Addressbook £6
6502 Assembler/Editor £25
Backgammon £8
Bridge Challenger £10
Civil War £7.50
Data File Handler £12
Discounted Cashflow £8
Estate Agents Pack £25
Graphics Package £12

Hotel Finder £5
Linear Programming £8
Line Renumber £8
Mailing List £15
Micro Chess £14
Music £10
Payroll £25
Percentage Costing £49.50
Pet Basic Tutorial £12

Program Merger £8
Sales Analysis £10
Statistics £7
Super Startrek £8
Tax £8
VAT Pack £17.50
Word Processor £25
76 Common Basic Programs £15

For full details of these and the other cassette and disk programs in our free catalogue, complete the coupon or ring us today. We also accept credit card orders over the telephone.

Petsoft

Specialists in
personal computer
programs,

5-6 Vicarage Road, Edgbaston, Birmingham B15 3ES.
Tel: 021-454 5348 Telex: 339396.

Petsoft A member of the ACT Computer Group.

PET is the trade mark of Commodore

To **Petsoft**
My name is _____
My PET lives at: _____
5-6 Vicarage Rd., Edgbaston, Birmingham B15 3ES.
MY PET NEEDS FEEDING Please rush me a
copy of your free 16 page catalogue of PET
programs without obligation.

UK Club roundup

For a long time we have wanted to publish a listing of as many UK computer clubs as possible and at last this ambition has been achieved. While this list is by no means an exhaustive survey we hope that it will encourage those of you who have a club to write in and tell us all about it, and also to provide a service to those clubs that we have mentioned in bringing more members into your ranks. We would like to thank those clubs that regularly correspond with us for their help in producing the survey and wish them and all the rest of you a successful future.

Please address any mail for publication under the club news section to:—

Club Forum, CT, 145 Charing Cross Road, London WC2
as we will shortly be moving to this new address.

The format of the clubs mentioned in this report is as follows:

Primary contact and address if known, Telephone number if known, Approximate membership:Primary meeting day and week of month:Membership fee:Special membership if known:Features and services if known.

If we get a suitable response to this feature we will endeavour to publish an update at least four times a year so the future is in your hands.

Processor Groups

UK PET Users Club

Commodore Systems, 360 Euston Road, London NW1 3BL
Richard Pawson, newsletter Editor
0926-25942

1500: :£10 UK,£15 o'seas:Newsletters.

Independant PET Users Group

Mike Lake, 9 Littleover Lane, Derby
Derby 23127

250: :£2.50:

PET User Group

Norman Fox, 22 Firs Walk, Tewin Wood, Welwyn, Herts.
Bulls Green 433

Northeast PETS

Mr T Turnbull, 49X 9th Row, Ashington, Northumberland

TRS80 User Group

Brian Pain, 40A High Street, Stony Stratford, Bucks.

TRS 80 User Group (Chelmsford)

Michael Dean, 22 Roughtons, Galleywood, Chelmsford,
Essex
0245-76127

Hull And District TRS80 Users Club

Frederick Brown, 421 Endicke Lane, Hull
0482-859169
:Tu3:

TRS80 Users Group

Leon Heller, 8 Morris Walk, Newport Pagnell, Bucks

Nascom User Group Nascom Microcomputers

121 High St., Berkhamstead, Herts HP4 2DJ
Miss Beverly Hamill
04427-74343

2000: :£1 & £5: :Newsletters:Program Library

Independant Nascom Users Group

Reliance Buildings, Damside Street, Lancaster
0524-33596

:£5:Newsletters, Program exchange

Sorcerer Program Exchange Club

G F Counsell and M P Hannaby, 65 Trafalgar Road, Birkdale,
Southport, Merseyside

Cosmac Users Club

James Cunningham, 7 Harrowden Court, Harrowden Road,
Luton LU2 0SR

Cromenco Users Group

313 Kingston Road, Ilford, Essex

77/68 User Group

Newbear Computing Store, 40 Bartholomew Street,
Newbury, Berkshire
0635-30505

600: :£1.50: :Newsletters, Programs, Hardware, Members list.

TI990 User Group

Simon Garth, 8 Kestrel Place, St. Neots, Huntingdon, Cambs.

Bywood Scrumpi User Group

66 Ebbens Road, Hemel Hempstead, Herts HP3 9QRC
0442-62757

UK Apple Users Group

Dr Tim Keen, 5 The Poultry, Nottingham
Nottingham 583254/5/6

:£5:

Research Machines Users Group

PO Box 75, 209 Cowley Road, Oxford
0865-49792

MK14, SC/MP Users Club

Mr G Phillips, 8 Poolsford Road, London NW9

PDP/LSI 11 User Group

P Harris, 119 Carpenters Way, Potters Bar, Herts

PDP 8 User Group

Nigel Dunn, 21 Campion Road, Widmer End, High Wycombe

IM6100 User Group

S P Fiala, 95 Felmongers, Harlow, Essex CM20 3DL

6502 Users Working Party

W R Wallenborn, 21 Argyll Avenue, Luton LU3 1EG
0582-2697 evenings
33:

6800 User Group

Eric Stancliffe, 4 Withensfield, Wallasey, Merseyside
L45 7NP
051-709-6022

Ithaca S100 User Group

Dave Weaver, 16 Etive Place, Condorrat, Combernauld by
Glasgow, Scotland
Sae for details

Regional Groups

CAMBRIDGESHIRE

Cambridge University Processor Group
Emrys Williams, Cavendish Laboratory, Downing College,
Cambridge

DEVON

Exeter and District Amateur Computer Club
David Carne, 44 George Street, Exmouth, Devon EX8 1LQ
03952-74479
65:Tu Fort:£5,25p Stud:Newsletter,Workshops.

South West Group Amateur Computer Club
G V Barbier, Palmers Hill, Calverleigh, Tiverton, Devon

BRISTOL

Brunel Technical College Computing Club
S Rabone, Electrical and Electronic Engineering Department,
Brunel Technical College, Bristol

Bristol Amateur Computing Club
Rex Godby, 16 Williamson Road, Ashley Down, Bristol BS7 9BH
Bristol 46981

Bristol Computing Club
Mr L Wallace, 6 Kilbernie Road, Bridge Farm Estate, Bristol
BS14 0HY
:W3:

WALES

Gwent Amateur Computing Club
Pete Hesketh
Shire Newton 596

ESSEX

Colchester Amateur Computing Club
Donald Clarke, 21 The Avenue, Colchester, Essex CO3 3PA
Colchester 66637

GLOUCESTERSHIRE

Cheltenham Amateur Computer Club
M P Pullin, 45 Merestones Drive, The Park, Cheltenham
Cheltenham 25617

HAMPSHIRE

Southampton University Amateur Computer Club
c/o Mr P G Doney, School of Bio Chem & Physio Sc.,
University of Southampton

KENT

Gillingham User Group
A Aylward, 194 Balmoral Road, Gillingham, Kent
Medway 56830

Bromley and Orpington
Phil Wheeler, 1 Irene Road, Orpington, Kent
Orpington 23800

Sittingbourne
J M Baron, 27 Wisers Lane, Borden, Sittingbourne, Kent
Sittingbourne 70160

LIVERPOOL

Liverpool University
Malcolm Taylor
051-709-6022 extn 2955

Merseyside Microcomputer Group

Mr John Stout, Department of Architecture, Liverpool
Polytechnic
:£2, £1 student:

DORSET

Bournemouth and Poole Area Computer Club
Mr Ian Preece, 246 Stewart Road, Charminster,
Bournemouth, Dorset

TYNE AND WEAR

Newcastle Personal Computer Society
Dr W G Allen, Department of Electrical Engineering and
Physical Electronics, Newcastle Upon Tyne Polytechnic,
Ellison Place, Newcastle Upon Tyne NE1 8ST

LONDON

North London Hobby Computer Club
The Secretary, c/o Dept of Electronics, Polytechnic of
North London, Holloway Road, London N7 8DB
01-607-2789 ext 2162 afternoons
320:W1:£10,inc course,£2.50 students:Courses,Newsletters,
Workshops,Sub Groups.

Southeast London Microcomputer Club
Don Hicks, Breakspears Road, Lewisham Way, SE4 1UT
01-692-0353 extn 358
:W3:

East London Amateur Computer Club
Jim Turner, 63 Millais Road, London E11
:Tu3:

Southgate Technical College Computer Club
Mr I E Williams, c/o Southgate Technical College, High
Street, London N14 6BS
Paul Woolley 01-886-6521
35:We1 Th3:£1: :Workshops,Newsletter,Next to Southgate tube.

Eltham Amateur Computer Club
R I Mitchell, 58 Kenilworth Gardens, Shooters Hill, London
SE18 3JB
01-856-2489

IRELAND

Computer Education Society of Ireland
7 St Kilmaind, Blackrock, Co Dublin, Eire

Belfast Amateur Computer Club
John Peacocke, 22 Wheatfield Gardens, Belfast 14

NOTTINGHAMSHIRE

Nottingham Amateur Computer Club
Mr Draga, 3 Troutbeck Crescent, Bramcote, Beeston
0602-256622

Nottingham Microcomputer Club
Mr P C McQuoney, 28 Seaford Avenue, Wollaton,
Nottingham
:M1:

STAFFORDSHIRE

M J Brough, 11 Beech Drive, Kids Grove, Stoke on Trent
07816-4387

OXFORDSHIRE

Oxford and District Amateur Microcomputer Club
S C Bird, 139 The Moors, Kidlington, Oxon

CLUB SURVEY

SUSSEX

Brighton Amateur Computer Club

P Weaver, 30 Warren Way, Telscombe Cliff, New Haven,
East Sussex BN9 7DJ

Sussex Personal Computing Society

N Latchem, 23 Silverdale Road, Hove, Sussex

MANCHESTER

Manchester User Group Amateur Computer Club

P Wade, 26 Wolseley Close, Radcliffe, Manchester M26 0AG
061-723-1021

LANCASHIRE

Northwest Group Amateur Computer Club

Ken Horton, 50 Lymefield Drive, Worsley, Manchester

YORKSHIRE

Bradford Amateur Computer Club

Barry Waite, 315 Toller Lane, Heaton, Bradford 9
Bradford 498750

South Yorkshire Amateur Computer Club

N Beard, High Street, Braithwell, Rotherham

South Yorkshire Personal Computing Group

Tony Rycroft, 88 Spinneyfield, Moorgate, Rotherham,
S. Yorkshire

Rotherham 74889 evenings

:W2:£3:

LINCOLNSHIRE

Lincolnshire Microprocessor Society

Michael Lyne, Far End, Far Lane, Coleby, Lincoln LN5 0AH
0522-810468

Lincoln Amateur Computer Club

M Alexander, 5 Brattelby Crescent, Lincoln LN2 2EB
Lincoln 23084

MIDLANDS

Midlands User Group Amateur Computer Club

Roy Diamond, 27 Loweswater Road, Coventry CV3 2HJ
0203-454061

West Midlands Computer Club

Tony Bridgewood
021-557-6709

West Midlands Amateur Computer Club

John Tracey, 100 Booth Close, Crestwood Park,
Kingswinford DY6 8SP
0384-70097

MIDDLESEX

Harrow Group Amateur Computer Club

Jim MacDonald, 19 Cowper Road, London W7 1EL

Harrow Local Group

Alan Secker, 209 Olbury Drive, Pinner, Middlesex
01-428-0844

Richmond Computer Club

Mr R A Forster, 18A The Barrons, St Margrets, Twickenham,
Middx
01-892-1873

30:M2:£0.15 per meeting:
Community Centre.

:6800 Library, Richmond

West Drayton RAF Amateur Computer Club

Squadron Leader Harrot
West Drayton 44007 extn 2410

SCOTLAND

Scottish Amateur Computer Club

S Stevenson, Lindisfarne, New Well Wynd, Linlithgow,
West Lothian
Linlithgow 2657

Grampian Amateur Computer Society

Mr Michael Brown, 282 Queens Road, Aberdeen AB1 8DR
16:M2:

LEICESTERSHIRE

Leicester Amateur Computer Club

G B Foden, 11 Gaddesby Lane, Rearsby, Leicester
Rearsby 247

BUCKINGHAMSHIRE

High Wycombe User Group

Roy Woodbridge, Department of Engineering, College of
Higher Education, High Wycombe

BERKSHIRE

Thames Valley User Group

Dave Howland, 4 Kent Lodge, Courtlands, Maidenhead,
Berkshire
0628-36976

:Thl:

ACC Specialist Groups

2650 Library

R A Munt, 51 Beechwood Drive, Feniscowles, Blackburn,
Lancashire BB2 5AT
0254-22341

6800 Software Library

Roy Hall, 89 Hicks Avenue, Greenford, Middlesex
01-5798-9136

COSMAC (1802) Library

R C Sheppard, 15 Kinnaird Way, Cambridge

9900 User Group and Library

Simon Garth, 67 De Parys Avenue, Bedford

ACC 8080/Z80 Library

Neil Harrison, 24 Copenhagen Street, London N1 0JD

ACC General Library

Frank Cato, 3 Rykneld Way, Derby DE3 7AT
0332-513769

Small Processor Library


J R Knight, Department of Meteorology, University of
Reading, Earley Gate, Whiteknights, Reading RG6 2AG

6800 Hardware Library

Bob Forster, 18A The Barrons, St Margarets, Twickenham,
Middlesex
01-892-1873

New Low-Cost ASCII Keyboards-Ex Stock Delivery.

KB771 — Latest addition to the range — ideal for the VDU-builder 71 Keystations incorporating separate numeric/cursor control pad and installed in a custom-built steel enclosure with textured enamel finish. Case dimensions: 17 1/4" x 7 1/2" x 3 1/2". Total weight: 4Kg



Price £95.00 (mail order total £108.00) 25-way D-Type connector for KB771 £4.25 (mail order total £5.13)

NEW KEYTOP/KEYSWITCH KITS — ASCII CHARACTER SET BRAND NEW SURPLUS

Pack of 58 keytops and keyswitches comprising 49 "Qwerty" set TTY format + 9 Edit/Function keys.
PRICE: £15.00 (mail order total £17.28)

NEW SHUGART FLOPPY DISC DRIVES

SA400 Minifloppy — 110KB capacity, 35 tracks, transfer rate 125Kbits/sec, AV access time, 550msec. Power requirements +5VDC +12VDC.
PRICE: £195.00


SA800 Floppy — 400 KB capacity, 77 tracks, transfer rate 250Kbits/sec, AV access time 260msec. Power requirements +24DC +5VDC — 5VDC.
PRICE: £395.00

KB756 56-keystations, mounted on PCB
KB756MF, as above, fitted with metal mounting frame for extra rigidity

Mail order total
£49.50 £55.08

Optional Extras:

KB15P Edge Connector	£ 3.25	£ 4.05
KB701 Plastic Enclosure	£12.50	£14.31
KB702 Steel Enclosure	£25.00	£28.62
KB710 Numeric Pad	£ 8.00	£ 9.18
KB2376 Spare ROM Encoder	£12.50	£14.04
DC-512 DC/DC Converter	£ 7.50	£ 8.64



Quantity discounts available

All the above keyboards are fully TTL-compatible, providing the full 128 ASCII character set, and requiring +5V — 12V Power Supply. Full technical data and circuit diagrams supplied

SEAELECTRO PATCH BOARDS

Programme boards for switching and interconnecting input/output circuits. 11 x 20 XY matrix. Interconnection is by means of shorting Skip and component holding pins (not included). Dimensions: 7 1/2" x 5 1/4" x 1".
PRICE: £12.50 (mail order total £14.58)

Reconditioned EDITING VDU SAVE £100!

HAZELTINE H-2000A
NOW ONLY £395.00
HAZELTINE H-2000B
NOW ONLY £495.00

Superb specification includes full edit capability, direct cursor addressing, standard V.24 (RS232) interface. 90 days' warranty.

- * Teletype Compatible
- * 12" Diagonal Screen
- * TTY Format Keyboard
- * 27 Lines of 74 characters
- * 64 ASCII Character Set
- * 5 x 7 Dot Matrix
- * 5 Switch-selectable Transmission: Speeds up to 9600 baud.

- * Switch-selectable Parity
- * Standard CCITT V.24 Interface
- * Direct Cursor Addressing
- * Full Edit Capability
- * Detachable Keyboard
- * Printer Port
- * 90-day Warranty


We also specialise in: DEC minis — PDP8 and PDP11 processors, add-on memory, peripherals and spares. Hard copy terminals — ASR33 and KSR 33 Teletypes, Data Dynamics 390, Texas Silent 700. Send for complete lists.

A copy of our trading conditions supplied on request.



Electronic Brokers


49/53 Pancras Road London NW1 2QB Tel: 01-837 7781. Telex 298694



DIRECT DATA MARKETING LTD

44 High Street, Brentwood, Essex. CM14 4AJ

DDM Have Chosen !Commodore Pet! Now available from £499



- * Add-ons include new DEC LA 34 table top printer
- * Floppy disks for faster access storage
- * Ready-made software for many applications
- * As a first machine for business, for college, for home




TO BUY OR RENT TEL:

BRENTWOOD (0277) — 229379/213273

CT MARKETPLACE

DIGITAL ALARM



THIS IS THE THIRD digital alarm clock that we are offering (we regret the earlier versions are no longer available). We have sold thousands and thousands of these and our buying power enables us to offer a first rate branded product at a really excellent price.

The Hanimex HC-1100 is designed for mains operation only (240V/50Hz) with a 12 hour display, AM/PM and Alarm Set indicators incorporated in the large display. A switch on the top controls a Dim/Bright display function.

Setting up both the time and alarm is simplicity itself as buttons are provided for both fast and slow setting and there's no problem about knocking these accidentally as a 'locking' switch is provided under the clock. A 9-minute 'snooze' switch is located at the top.

An example of this clock can be seen and examined at our Charing Cross Road offices.

£9.95

(Inclusive of VAT and Postage)

To:
Hanimex Alarm Offer
CT Magazine
145 Charing Cross Road
London WC2H 0EE

Please find enclosed my cheque/PO for £9.95 (payable to CT Magazine) for a Hanimex Digital Alarm Clock

Name _____
Address _____

Please allow 28 days for delivery

LCD CHRONO



We feel we've got to tell you carefully about this offer which we're introducing for the first time. Why? Because our price is so enormously lower than anywhere else you may suspect the quality.

The exact same watch is currently being offered by another magazine as a special at £24.95 — some of the discounters are selling it at £29.95, the price to ETI readers for exactly the same watch is £12.95

The display is LCD and shows the seconds as well as the hours — and minutes — press a button and you'll get the date and the day of the week

Press another button for a couple of seconds and you have a highly accurate stopwatch with hundredths of a second displayed and giving the time up to an hour. There is a lap time facility as well — and of course a back light

Our Chrono comes complete with a high grade adjustable metal strap and is fully guaranteed

A sample of this watch can be seen and examined at our Charing Cross Road offices.

£10.95

(Inclusive of VAT and Postage)

To:
LCD Watch Offer
CT Magazine
145 Charing Cross Road
WC2H 0EE

Please find enclosed my cheque/PO for £10.95 (payable to CT) for my LCD Chrono-graph.

Name _____
Address _____

Please allow 28 days for delivery

ALARM- CHRONO LCD



This new addition to our unbeatable selection of bargains is no ordinary LCD watch. It's a slim, multi-function, dual time chronograph alarm watch, no less.

This model will show hours, minutes, seconds, date, day of the week, stop watch, split time, alarm and alternate dual time zone — not all at once, of course. There is also a night light.

Hours, minutes, seconds and day of the week are displayed continuously, while the date will appear at the touch of a button. The day of the week is indicated by a flag. When used as a stopwatch, the maximum count is 0.1secs. short of thirteen hours

An example of this watch can be seen and examined at our Charing Cross Road offices.

£18.95

(Inclusive of VAT and Postage)

To:
ALARM/CHRONO LCD WATCH Offer,
CT Magazine,
145 Charing Cross Road,
London WC2H 0EE.

Please find enclosed my cheque/PO for £18.95 (payable to CT Magazine) for my Alarm/Chrono LCD watch.

Name _____
Address _____

Please allow up to 28 days for delivery

Discretes Rule OK?

Ever since the development of the integrated circuit back in the mid-1950s, a recurrent theme in our industry related to the impending demise of the discrete semiconductor business. The press, some of our friends in the financial community, and many other observers of the semi-conductor scene, have often tended to downplay the importance of discrete components in the future of the industry. The usual scenario drawn by these observers called for the discrete industry curve to generally flatten during the 1970s — continue on a descent throughout the 1980s — and almost fall completely off the industry charts by the 1990s.

The primary reason for this somewhat gloomy outlook, of course, was the phenomenally rapid growth of the IC technology, in which a steadily growing number of discretes were and are, being integrated into the silicon chip and losing their identity as discrete components. As you know, the integrated circuit technology advanced, in a relatively short period of time, from devices containing 10 or 15 transistors to the current situation in which they contain thirty or forty thousand transistors in the same sized silicon chip. And, there certainly isn't any doubt that the number will escalate to the hundreds of thousands by the early 1980s, and to perhaps a million per chip by 1985 or so.

The advent of the microprocessor, and the rosy future that all of us in the industry are predicting for it, has no doubt tended to compound the "image" problem that exists within the discrete component industry.

Changing Society

The microprocessor has been the most publicised product ever developed by the semiconductor industry, and perhaps rightly so. I honestly believe that the microprocessor will eventually be recorded in history as one of the most important, if not THE most important, industrial development of the twentieth century.

The amount of change, and the speed of change, that the microprocessor will bring to the worldwide social, political and industrial institutions during the next decade will stagger even the most fertile of imaginations. The number of new or improved electronic products for the home, the automobile, the factory, the office, the school,

the government and the military organizations not only in the U.S., but around the world, will number in the thousands. And that will only be the beginning, we will barely have scratched the surface of what can be accomplished through the microcomputing technology.

The rapidly growing volumes of microprocessors being used are, to a large degree, responsible for our predictions that the U.S. semi-conductor industry will double its present size in the next four or five years. Another reason, less dramatic perhaps than the growth in microprocessors, is the quiet but significant revolution that the MPU technology is creating within the discrete component industry.

It is estimated that more than 50 per cent of the microprocessors being produced today are for new product applications which previously were not feasible for either technical or financial reasons. While these new microprocessors are having somewhat of a negative impact on conventional standard logic integrated circuit families, their impact on discrete components is definitely positive. Microprocessors cannot function by themselves. Depending on the application, a number of different types of discretes are required for rectification, for voltage regulation, for power handling and for carrying out the actions determined and ordered by the microprocessor.

What Of Discretes?

Before I get more deeply involved in the subject of MPU-related discrete components, I would first like to spend a few minutes on the industry's outlook for the discrete component business in general.

In the fall of 1978, in my capacity as chairman of the Semiconductor Industry Association, I had the opportunity to unveil our industry outlook at the association's annual forecast meeting in Palo Alto.

I'd like to share with you the data we presented regarding our consensus view of the next three years for the discrete component business.

(Figure 1) This chart depicts the worldwide sales of discrete components by U.S.-based semiconductor manufacturers between 1977 and 1981. No foreign manufacturers are included, and the data is presented in both current dollars and annual growth percentages.

Several points are worthy of note. First of all, we believe that industry sales will grow to slightly more than 1.5 billion dollars this year, up nearly twelve per cent from the 1977 level, which was essentially flat with the previous year.

By 1981, the industry sales are expected to climb to approximately 1.75 billion dollars, an increase of nearly a quarter of a billion dollars. During the four-year period — from 1978 through 1981 — we expect compound growth rate for discrete components of about six per cent.

The change in product mix is a little less obvious. Small signal transistors, for example, was the largest selling product line last year; the second largest seller this year, and by 1981 we find it relegated to third place — and almost a fourth place — position. This is, of course, due to the fact that small signal transistors are most vulnerable to integration.

In all other major discrete product lines we anticipate varying levels of growth. If you compare the actual 1977 sales with the anticipated 1981 sales, you can see that we anticipate modest growth for diodes, and rather dramatic growth for power transistors, rectifiers, thyristors and optoelectronics. It is precisely these four product lines whose growth will be effected, in a very positive sense, by the emerging microprocessor technology.

Current Dollars in Millions					
	1977	1978	1979	1980	1981
Diodes	167	178	169	174	176
Small Signal Transistors	318	317	304	302	300
Power Transistors	313	347	359	375	407
Rectifiers	226	271	271	289	309
Thyristors	146	158	159	173	189
Optoelectronics	155	209	228	260	285
All Other Discretes	68	78	77	82	87
Total Worldwide	1394	1558	1567	1655	1753

Annual Growth in Percent					
	1977	1978	1979	1980	1981
Diodes	0	6.6	-5.0	2.9	1.1
Small Signal Transistors	1.9	0	-4.1	0	0
Power Transistors	1.3	10.8	3.5	4.5	8.5
Rectifiers	1.3	19.9	0	6.6	6.9
Thyristors	22.7	8.2	0.6	8.8	9.2
Optoelectronics	-21.7	34.8	9.1	14.0	9.6
All Other Discretes	-5.6	14.7	-1.3	6.5	6.1
Total Worldwide	0.5	11.8	0.6	5.6	5.9

Fig. 1. Discrete product forecast by major product category.

BITS, BYTES & PIECES

In next year's forecast, when we add a 1982 column, and the following year, when we add the 1983 forecast, I think the comparisons will be even far more startling than they are right now, because the 1981 forecast reflects just the onset of high-volume microprocessor applications.

Growth

Figure 2 shows the growth we anticipate for all MPU-related discrete products. As in the charts that will follow, this is a relative growth chart, with 1978 unit sales being equal to one.

It's easy to see that we anticipate the most MPU-related growth being enjoyed by rectifiers and power transistors. Both of these product lines begin to take off from their already high level during 1979, and by 1981 their sales

will be about three and one half times their current level. Zener diodes and small signal transistors will be nearly three times their present level, while optoelectronics and thyristors will increase just slightly. This graph has even more impact if you'll recall that Fig. 1 indicated that power transistors became the largest selling discrete line this year and rectifiers are in the number three position. The growth of these two product lines alone for MPU-related applications will account for a large percentage of the total discrete industry growth between this year and 1983.

In the next two figures, I have segregated this same data into automotive and non-automotive microprocessor-related applications. I did this to dispel any notion that the anticipated MPU-related discrete growth is entirely due to the widely publicized, high-volume automotive applications




Fig. 2. 1978-83 growth trends, total MPU-related discretes.




Fig. 3. 1978-83 growth trends, non-automotive MPU-related discretes.

that loom on our horizon. Automotive applications will certainly be the major cause of the discrete growth, but non-automotive MPU applications will also be very respectable.

Non-automotive

Figure 3 shows how the data looks without the automotive applications. Power transistors and thyristors are the leaders in this case, more than doubling their current MPU-related applications. Optoelectronics and diodes, starting from a lower base, will triple their present usage in MPU applications, while small signal transistors will remain relatively flat.

The markets most impacted by these new MPU and discrete combinations are the computer, industrial and consumer sectors, in reverse order of their importance.

Computers

While the computer applications will be large and varied, they will be less spectacular than either the industrial or consumer applications. The main product areas in which discrete usage will increase because of MPU applications are rigid discs, electrostatic printers, line printers, matrix printers, floppy-disc systems and both CRT monitor and keyboard terminal systems. A wide variety of discretes will be used to drive hammers in MPU-controlled printers, to position heads in MPU-controlled disc memory systems, and in the horizontal and vertical circuits for CRT monitors, as well as in the power supplies of most computer products.

Industrial

In the industrial market, the volume and variety of discrete MPU-related applications will be greater than they are in the computer market. The most obvious usage will be in automated process control and production equipment. Everything from making steel to McDonald hamburgers will be improved, in terms of speed and precision, by the microprocessor technology. Again, a variety of discretes will be required to handle the power and carry out the orders of the MPU. While it's impossible to peg a precise discrete usage number for these applications, they will certainly be used by the tens of millions each year.

There are several other industrial applications I would like to mention briefly, because they are interesting and possess the potential for extremely high discrete component usage.

The first is in the area of large displays, such as the animated sign boards that are beginning to appear in our major sport stadiums. The display technology is quickly evolving, and I think we will see a proliferation of this type of equipment over the next few years, not only for sporting events, but in promotional and advertising signs of every size and description. The potential for discretes here is very large. Some of the current sports displays, for example, already contain as many as 60,000 thyristors or power transistors alone. In addition, a great number of discretes are already being used in the associated power supply systems. Again, this is a market that will probably require millions of discrete devices each year.

Another important industrial market that is on the verge of explosion is the entire field of energy management. Because of the nationwide concern for energy conservation, various states are beginning to legislate "time of day" or "demand" measurements of energy usage to allow for higher charges during peak load periods. As this legislative movement gains momentum, we will see the emergence of many different types of energy management systems. One of the

first to appear will be a new generation of electric meters that will employ the MPU technology as well as a number of discrete components. Other energy management systems will soon follow, and they will all use discretes as well as microprocessors. The potential for thyristors alone in this newly emerging market over the next five years should be well in excess of 15 million units.

Traffic control is another newly emerging market for discretes, again because of the application of microprocessors in traffic signals. In the past, conventional logic such as HTL or CMOS have been used in such signals, but the number of MPU-controlled signals is growing readily. This, in turn, will greatly increase the usage of opto-couplers and thyristors in such applications.

Another very important area, in which a dramatic shift in the technological make-up of the industry will result in significant growth potential for discretes is in telecommunications. The present shift from electromechanical to digital switching is the result of the tremendous cost effectiveness of MPUs and the associated, dedicated LSI devices. This development is again increasing the demand for discrete components, particularly power transistors and bridge rectifiers. The accumulated potential for these discretes in switching alone should be greater than 15 million dollars during the next five-year period.

Discrete usage in telecommunications will also be enhanced as the new fibre optic transmission techniques become refined and applied. The potential for emitters and detectors in this area alone is in the neighbourhood of another 15 million dollars over the next five years.

While the computer and industrial applications are diverse and growing, some of the most exciting potential lies in the consumer segment of the discrete market.

Consumers — Watch Out!

The home appliance market is a good example. Microprocessors will be used in huge and steadily growing numbers in washers and dryers, refrigerators, dish washers and microwave ovens. An even greater number of discretes will be required. The MPU-controlled electronic system will replace the mechanical clocks and cams in order to provide more effective control and flexibility to the user. In most of these major appliances, four to eight thyristors will be required. In addition, opto-couplers will be required to isolate the electronics from the rest of the appliance in order to reduce the potential of electrical shock and provide the high levels of product safety being required by present government legislation.

The security systems market is another new and rapidly emerging business that holds great potential for additional discrete usage. A popular political slogan of the past was "A chicken in every pot." The slogan of the future appears to be "A security system in every home." This market is on the verge of tremendous growth, and I suspect that at some point in the future every new home will come equipped with a sophisticated security system. While these systems will be MPU-controlled, a great number of discrete will be required to actuate the alarms and indicators.

There are a number of other emerging consumer markets that bode well for increased discrete component usage. MPU-controlled video games . . . electronic TV tuning . . . and home environmental control systems . . . to name just a few. All of these new, MPU-generated product developments will require discrete components each year.

Now let's turn our attention to the automotive applications for MPU-related discretes.

BITS BYTES & PIECES




Fig. 4. 1978-83 growth trends, automotive MPU-related discretes.

Automotive Uses

Figure 4 shows the relative growth trends for the major discrete product lines in automotive applications. While opto-electronics will grow slightly, major growth will be recorded by the four others: rectifiers, power transistors, zener diodes and small signal transistors.

While the initial application of microprocessors to automobiles has created a great deal of excitement in the marketplace, there is a great deal yet to come.

In their current application, which extends through the next two or three model years, MPU's are being used primarily in ignition control systems. After collecting data on such things as speed, temperature, humidity and altitude, the microprocessor automatically adjusts the carburation, spark and timing. In effect, it tunes the car while it is being driven. This application is the auto industry's first step in meeting the government-mandated challenges to reduce emissions, improve safety and increase fuel efficiency.

The engine control systems of the future will add a pre-ignition system to the vehicle, primarily for the purpose of knock detection. Also, such things as oxygen sensors will be added to the exhaust system to monitor the efficiency of the combustion. This information will then be fed back through a microprocessor which would further adjust the carburation, if required.

Another future MPU application in autos is in the area of load management, or more simply put, transmission control. Transmissions of the future will not include definite gears such as first, second, or third. Instead, they will have an MPU-controlled servo-mechanism that will automatically adjust itself according to the load the vehicle is being required to carry. As a result, the proper gear ratios will always be chosen to maintain optimum torque efficiency and maximum engine efficiency.

Another interesting application which is down the road a bit will be in levelling systems. Federal regulations are already requiring that all bumpers be a certain distance from

the ground in order to minimize the damage from impact. To accomplish this, bumpers either have to be very wide to take into account bumper height changes brought about by acceleration and deceleration, or systems need to be developed to keep bumper height constant at all times. Such systems are already under development, using Hall effect sensors to detect uneven loading or levelling situations. The detected data is then coupled back to a microprocessor, which, in turn, drives an actuator which self-corrects or compensates for the uneven loading. In all cases, the actuators would be driven by discrete devices, most likely power transistors or thyristors.

There are also a number of other new automotive applications for discretes that are indirectly related to the MPU applications. The emergence of the one-wire electrical system utilizing fibre optics seems to be a distinct possibility. This, in turn, would create brand new markets for such things as opto-couplers and other discretes. New types of digital dashboard displays will also provide new liquid crystal applications sometime in the future.

These are just a few examples, but I think they illustrate the reason for our confidence for the steadily increasing penetration of discretes in the automotive market. This year, total discrete sales for automotive applications amounts to about \$3.80 per car. By 1982 or 1983, that amount will grow to about \$11.50 per car. The difference — about \$8 — will be almost entirely created by the variety of new, MPU-related applications. In addition, nearly \$6 of that \$8 growth will be in engine control systems.

Who Says Discretes Dead?

Perhaps these reliable workhorses of the industry have less glamour, and receive less publicity, than some of our more exotic LSI developments, but they provide an extremely critical link between the feasibility of exotic integrated circuits and their actual implementation. Discretes are alive and well and growing, and such will be the case for many years to come.

Dear Sir,

I read with interest the article on M5 in the May issue of Computing Today. Mr Bell had obviously studied the language very closely and with great skill.

The modifications he suggests to increase program space may be useful, and if variables need not be kept between programs, a "clear screen" before execution is an aid to clarity.

Mr Bell may however be pleased to learn that the ">" and "<" characters are available on NASCOMs with T1 and T2 monitors. They can be obtained by "SHIFT ." and "SHIFT ," with T2 or "SHIFT N" and "SHIFT M" with T3, and they look clearer when used in an edit line.

M6 will reside in a 1K ROM, and contain subroutine facilities, character handling, array manipulation, tape dump and load, with various other useful functions and a more powerful editor.

The lunar lander program is very impressive, and takes some time to learn to fly.

Yours sincerely,
Raymond Anderson

A29 Harvey Court,
West Road,
Cambridge.

Dear Sir,

I was most interested to hear about the M5 language, which is obviously a close relative of the programmable calculator keystroke languages. I thought Mr Bell failed to point out some of the obvious advantages of such languages which can be made as powerful as any BASIC. If Mr Bell doubts this I suggest he try a HP9815. I don't pretend that such a machine is good value for money, but I think the software is excellent and easy to learn and use. The advantages of this sort of language are:

1) The interpreter is much smaller than the equivalent BASIC interpreter. The M5 is shorter than many monitors and most assemblers. Equally obvious is that a 2K or 4K keystroke language can be very much more powerful than the BASIC interpreter in the same space.

2) Programs take much less space. For instance the first two lines of the lunar lander program shown contain 48 characters compared with BASIC source code which requires about 98 (3 fig line numbers).

3) You can get useful hard copy of a program in keystore language with as few as 12 characters per line (eg PC100A for TI calculators). This makes for a much cheaper system.

4) Keystroke languages have inherently simple syntax and this fewer errors (syntactical).

There are two ways of looking at microcomputer systems. One is to ape mini and larger computers and have mini floppy discs, mini BASIC, mini modules. This is incidentally good business for the manufacturers because they can always lure you up the scale.

The other way is to make micro systems into super calculators. By that I do not mean that they necessarily should all be number crunchers, but to be calculator like plus

more memory, peripheral interfacing, mass storage, etc.

Incidentally, why have I never seen a cassette tape system which can be run forwards and backwards, fast and normal, under program control? (see HP9815 again) Such a system, would, I suspect, dent sales of floppies due to its very much lower price.

Yours sincerely,
Nigel Falden.

Bright's Farm,
Bramfield,
Haleworth,
Suffolk.

Dear sirs,

Having read A.R. Ingleson's comments in the May issue regarding bad etching and faulty components in the "Nascom I" kit, I am glad that I decided in favour of the "Triton" kit.

The printed circuit board was first class and the only problem with components was a few weeks delay on some of the chips. This system did work first time, and as this was my first attempt at constructing anything electronic, I am very pleased.

Your 'Softspot Special' section is a very good idea. Long may it continue.

Yours faithfully,
G.A. Slyfield.

29 Helston Road,
Springfield,
Chelmsford,
Essex.

Dear Sir,

I cannot let the letter from Mr. Ingleson pass without a reply in defence of the Nascom kit. It is true that I didn't actually get my kit up and running first go. I found I had a most peculiar repeating column effect on the display. I traced this to a single pin I had failed to solder on the screen driving chain of I.C.'s. A moments work with the soldering iron and — magic!

I had assembled one other smaller kit before. In comparison with that I found the Nascom construction manual most helpful and detailed, and most explicit on the silly things that cause all the real trouble, like which way round all the components go. No trouble with the cassette interface. I'm now using T-4, which gives a faster rate also, and the 'generate' command is rather nice.

The construction manual does point out that to build a Nascom you have to solder some 1300 joints, and advises you not to hurry. I did build the system slowly, and it worked!

Yours faithfully,
T.M. Spence.

23 Thorburn Road,
Edinburgh EH13 0BH.

HANOI TOWER

Ray Anderson

This program runs on a standard Nascom 1. Its purpose is to give instructions to a person trying to solve the "Towers of Hanoi" puzzle. The puzzle is in the form of three rods and a

set of different sized discs, which fit on the rods. The object is to move the discs from tower A to tower C, one at a time, while ensuring that after each move of a disc between towers, no disc is placed over a disc smaller than itself. The discs start on tower A. Every time a key is pressed, the correct move to make next will be displayed. When the transfer is complete, the monitor is re-entered.

```

1      ;
2      ; Program to Give directions for
3      ; the Towers of Hanoi, showing
4      ; how recursion can be used.
5      ;
013B   6      CRT      EQU 013BH ; Nascom Routine.
003E   7      CHIN     EQU 003EH ; Returns when key pressed.
0286   8      PARSE    EQU 0286H ; Nasbug re-entry.
9      ;
001F   10     CRET     EQU 1FH   ; Nascom Newline.
11     ;
0C60   12     ORG      0C60H
13     ;
0C60 EF44697363 14     START DB 0EFH,'Discs?',0
0C65 733F00
0C68 CD3E00
0C6B D630
0C6D FE09
0C6F 30F7
0C71 47
0C72 C630
0C74 CD3B01
0C77 0E41
0C79 1643
0C7B 1E42
0C7D CD830C
0C80 C38602
15     LOOP    CALL CHIN
16     SUB '0' ; Make a number.
17     CP 9 ; IF too high
18     JR NC,LOOP-$ ; try again!
19     LD B,A
20     ADD A,'0'
21     CALL CRT
22     LD C,'A' ; On entry to MOVE, C contains "from"
23     LD D,'C' ; tower, D contains "to" tower, and
24     LD E,'B' ; E contains spare tower.
25     CALL MOVE
26     JP PARSE
27     ;
0C83 78
0C84 A7
0C85 C8
0C86 C5
0C87 D5
0C88 05
0C89 7B
0C8A 5A
0C8B 57
0C8C CD830C
0C8F CD9C0C
0C92 79
0C93 4A
0C94 53
0C95 5F
0C96 CD330C
0C99 D1
0C9A C1
0C9B C9
28     MOVE    LD A,B ; Routine tells what
29             AND A ; moves for B discs
30             RET Z ; unless B=0
31             PUSH BC
32             PUSH DE
33             DEC B
34             LD A,E ; Swop about registers.
35             LD E,D
36             LD D,A
37             CALL MOVE ; Try moving B-1
38             CALL SHOW ; Show what to move
39             LD A,C ; Swop registers again
40             LD C,D
41             LD D,E
42             LD E,A
43             CALL MOVE
44             POP DE
45             POP BC
46             RET
47     ;
0C9C EF1F4D6F76 48     SHOW DB 0EFH,CRET,'Move disc ',0
0CA1 6520646973
0CA6 632000
0CA9 78
0CAA C631
0CAC CD3B01
0CAF EF2066726F 52
0CB4 6D2000
0CB7 79
0CB8 CD3B01
0CB9 EF20746F20 55
0CC0 00
0CC1 7B
0CC2 CD3B01
0CC5 C33E00
49     LD A,B
50     ADD A,'1'
51     CALL CRT ; Display B
52     DB 0EFH,' from ',0
53     LD A,C
54     CALL CRT
55     DB 0EFH,' to ',0
56     LD A,E
57     CALL CRT
58     JP CHIN ; Wait for a key before
59             ; continuing with next move
60             ; via return from chin.
61     END

```


Britain is a nation of PET lovers

**THE No. 1
Personal
Computer
in the
U.K.**

**Hobbyist
Commercial
Scientist
Education**

**NOW FROM
£450
plus V.A.T.
(4K model)**

for the first time
user and the professional
check out the PET, the world's
most popular personal computer

- * **AVAILABLE** in either 4K, 8K, 16K* or 32K* RAM.
(*with large typewriter style keyboards.)
- * **CAPABLE** - just like a traditional computer.
- * **UNDERSTANDABLE** - fast, comprehensive and powerful - BASIC is one of the easiest computer languages to learn, understand and use. Machine language accessibility for the professionals.
- * **PERSONAL** - easily portable and operated - just "plug in" and go. Unique graphics make fascinating displays.
- * **EXPANDABLE** - built in IEEE-488 output, 8K RAM expandable to 32K, parallel user port 2nd. Cassette interface.
- * **SERVICEABLE** - easily serviced - only 3p.c. boards all readily accessible.

Commodore PRINTERS and DUAL DRIVE FLOPPY DISCS now available.

Contact your local dealer for a demonstration, also for memory expansion and peripheral details, also list of readily available software.

AUTHORISED COMMODORE PET DEALERS

Birmingham
Taylor Wilson Systems Ltd
Knowle (05645) 6192

Bolton
B & B Consultants
0204-26644

Bristol
Sumlock Tabdown Ltd
0272 26685

Cardiff
Sigma Systems Ltd
(0222) 21415

Derby
Davidson-Richards (Int) Ltd
0332 366803

Durham
Dyson Instruments
0385 66937

Grimsby
Allen Computers
0472 40568

Guildford
P.P.M.
0483 37337

Hemel Hempstead
Data Efficiency Ltd
0442 57177

Leeds
Holdene Ltd.
0532-459459

Hove
Amplicon Micro Systems
0273-720716

Liverpool
Rockliff Brothers Ltd.
051-521 5830
Liverpool
Dams Office Equipment Ltd
051 227 3301

London N.W.4
Da Vinci Computers Ltd.
01-202 9630

London W.C.2
TLC World Trading Ltd
01 839 3893

London EC1
Sumlock Bondain Ltd
01-2542117

Manchester
Cytek (UK) Ltd
061 832 7604
Sumlock Electronic Svcs.
061 228 3507

Morley (W. Yorks)
Yorkshire Electronic Svcs.
0532 522181

Northern Ireland
Medical & Scientific
08462 77533

Nottingham
Betos (Systems) Ltd
0602 48108

Reading
C.S.E. (Computers)
0734 61492

Southampton
Symtec Systems Ltd
0703 37731

Business Electronics
0703 748248
Swansea
Radio Supplies (Swansea)
079223130

Thame, Oxon
Memec Systems Ltd
084 421 3149

Woking
Petalect Ltd
048-62-69032

Yeovil
Computerbits Ltd
0935 26522

In case of difficulty call **COMMODORE SYSTEMS DIVISION**
360 Euston Road, London. Tel. 01-388-5702

This month Phil Cornes takes a look at extended BASIC

Up to now, all the facilities we have described should be found on any machine that can run any form of BASIC. Unfortunately, Extended BASIC is not so cut and dried. Different manufacturers tend to have different ideas on the facilities that should be provided, and they tend to pick some facilities because they highlight some of the best points of their machines.

Having said this, however, there are still plenty of facilities common to most machines: just don't be too upset if we describe a facility your machine doesn't have, or miss a facility it does have.

When we first started the series, we took a look at the meaning of words like variable, and operator. We are going to go back and look at these again now, as their scope has been broadened somewhat with the introduction of Extended BASIC

Variables

The first thing to note about Extended BASIC is that the number of variable names increases somewhat. Whereas in Tiny BASIC we had 26 variable names, A-Z, and one single subscript variable, A(X) or @(X), in Extended BASIC we have many more. Typically these include —

1. The letters A—Z;
2. Any letter followed by a single digit 0—9 (eg A1, S5, Z9 etc. where A1 is totally distinct from A(1) and so on);
3. Many BASIC versions also include combinations of two or more letters (eg ZQ, PT, ID etc.);
4. In addition to this, any common variable name (T, B4, PR etc.) may also be made into a subscripted variable of the form T(X), B4(X), PR(X) etc.
5. String variables of the form any common variable name followed by a \$ sign (eg B\$, C8\$, ST\$ etc.).

The first three types of variable name (common variables) listed above are quite straight forward. They are just an extension of Tiny BASIC's 26 variable names A-Z, but the other types of variable will require a little more discussion.

Subscript Variables

In Tiny BASIC we had A(X) where X could take any value from 1 to a value determined by the amount of free memory space available. Since we were only allowed one such variable, we did not need to inform the computer how many elements of this array we were going to use because the computer would keep accepting the values we assigned to the various elements of the array until it ran out of free memory space and informed us of this fact.

In Extended BASIC, there are endless numbers of possible Subscript variable names and the computer has to allocate a known amount of memory to each one that appears in a program. This means that we now have to tell the computer how many elements will be used for each subscript variable. We do this by means of a new statement.

DIM

No! This is not to tell the computer that we think it is thick. DIM is an abbreviation for the word DIMension where the word is used to mean size in this context. The following is an example of its use :—

```
10 DIM Q(4)
```

This tells the computer to reserve memory space for 5 elements to be labelled Q(0), Q(1), Q(2), Q(3) and Q(4).

It is possible to dimension several variables in a single DIM statement, as follows:—

```
30 DIM B4(3), AD(7), R(19)
```

This statement is telling the computer to reserve space for 32 subscript variable elements all together (don't forget we also include zero subscripted elements (B4(0) etc.) now).

In Tiny BASIC our subscript variable only had one DIMension. Just to confuse you, one dimension here means that there was only one number in the bracket to specify which element we were referring to. In Extended BASIC, we can have subscripted variables in more than one dimension.

```
56 DIM D(3,2)
```

tells the computer to reserve memory space for the D array which has double subscripts 0—3 and 0—2 (12 elements in all). You can imagine this to be a two dimensional matrix set out as follows.

D(3,0)	D(3,1)	D(3,2)
D(2,0)	D(2,1)	D(2,2)

D(1,0)	D(1,1)	D(1,2)
D(0,0)	D(0,1)	D(0,2)

Some versions of BASIC will allow more than two dimensions, e.g.

```
71 DIM GT(3,7,6,4)
```

contains four dimensions. Indeed I have seen one version of BASIC which will allow 9 or 10 dimensions (heaven knows what you would do with them all!).

Consider the following:—

```
10 DIM A(3,2), V(2)
20 V(0)=0
30 V(1)=8
40 V(2)=12.5
50 FOR X=0 TO 3
60 READ PR
70 FOR Y=0 TO 2
80 A(X,Y)=PR+PR*V(Y)/100
90 NEXT Y
100 NEXT X
110 DATA 520,630,704,931
120 END
```

This program is calculating VAT at the three different rates, 0%, 8% and 12.5%, on the prices of items listed in the DATA statement of line 110. The three VAT rates are stored in the V array, [V(0) to V(2)] by lines 20 to 40.

Each price in line 110 then has VAT added to it by line 80. All the answers are stored in the A array, a two dimensional array. Each of the columns in this array stores the three prices, one for each VAT rate, and each row stores the price of each of the four items at a single VAT rate.

String Variables

This is a totally new kind of variable and one that we shall spend much time discussing as there are many facilities associated with it.

Just as a common numeric variable (A,XZ etc.) can be assigned a value which can then be manipulated and used in calculations and decisions, so can a string variable be assigned a value which can be used similarly. The main difference is that a string variable doesn't have to consist of digits but can consist of any string of characters that are available on the keyboard (usually with three exceptions — comma, inverted commas and carriage return). Eg:—

```
10 A$ = "THIS IS THE STRING CALLED A$"
```

In this example, the computer will assign to the variable A\$ the value

```
THIS IS THE STRING CALLED A$
```

note that the inverted commas are not assigned to A\$. They are used by the computer to show where the string begins and ends.

As with any other variable, the statement —

```
30 PRINT A$
```

would cause the above message (minus inverted commas) to appear on the output peripheral. Consider the following —

```
5 PRINT "INPUT YOUR NAME";
10 INPUT A$
20 IF A$ = "PHIL" THEN 50
30 PRINT A$; "IS NOT ACCEPTABLE — PROGRAM ENDED"
40 END
50 PRINT "HI PHIL — WHAT'S ON TODAY"
60 .....
70 .....
```

Here we see two more examples of string variables being used in the same way as numeric variables can be used.

Line 5 asks you to INPUT YOUR NAME. Line 10 will assign any string of characters you input to A\$. You do not need to input inverted commas here as the computer knows where your input string starts and ends. Line 20 checks your input string for a particular combination of characters (in this case PHIL) and if this combination is found, the program branches to line 50 and continues.

If your input string is not the particular combination being considered then the program terminates in line 40 after printing an error message in line 30.

It would have been quite acceptable to use any relational operator (=,>,<,>,<=,<>) instead of the = sign in line 20. For example, suppose we had used =, what would this mean? In ASCII code (the most popular computer code) every character is given a 7 bit binary number, as its representation, so that —

```
A in ASCII is 1000001
B is 1000010
C is 1000011 etc.
```

in ascending binary order, so when the computer is faced with —

```
20 IF A$> = "PHIL" THEN 50
```

then it will compare the first character of the word PHIL (P=1010000 ASCII) with the first character of A\$. If the ASCII for the first character of A\$ is less than 1010000 then the test fails. If the ASCII for the first character of A\$ is greater than 1010000 the test succeeds. If the two ASCII codes are equal, then the computer knows that the two words have the same first letter. It does not know the relationship between subsequent letters, and so these have to be checked — second letter of A\$ with second letter of "PHIL" etc — until the test fails with one of the letters of A\$ being less than one of the letters of PHIL, or passes with one of the letters of A\$ being greater than one of the letters of PHIL, or passes with all of the letters of A\$ being the same as all the letters of PHIL. Therefore, if —

```
A$ = "PHI"   the test will fail (A$<PHIL)
A$ = "PHIL"  the test will pass (A$ = PHIL)
A$ = "PHILIP" the test will pass (A$> PHIL)
```


BEGINNING BASIC

PHI<PHIL because the letter L in PHIL will be compared with the fourth letter of PHI which is a NUL character, which has ASCII code 0000000 and is therefore the least of the ASCII codes (the same reason applies as to why PHIL<PHILIP)

We will now make a start on some of the string functions available in Extended BASIC.

MID\$ (STRING,S,L)

It would be most useful if it were possible to extract characters at will from within a string so that they could be tested or manipulated separately (we will see an example of this later) and, indeed, it can be done using the MID\$ string function.

Consider the following —

```
10 A$ = "STRING"  
20 B$ = MID$(A$,3,4)  
30 PRINT B$  
40 END
```

the output from this program would be the word RING.

The MID\$ function tells the computer to return a substring of the specified STRING variable (here A\$) starting at position S (here 3) and containing L characters (here 4).

The word STRING in the heading above may be replaced with any string variable name or string expression, and the variables S and L may be any numeric constant, variable name or numeric expression.

The following is a short program which reads a string of characters from a data statement and searches through it to find the start position of a three-character sub string which is also contained in the DATA statement.

```
10 READ A$, B$  
20 L=3  
30 S=1  
40 T$=MID$(A$,S,L)  
50 IF T$=B$ THEN 80  
60 S=S+1  
70 GOTO 40  
80 PRINT B$;"STARTS AT POSITION";S;"OF";A$  
90 DATA "EDUCATION","CAT"  
100 END
```

If this program were run, its output would be

CAT STARTS AT POSITION 4 OF EDUCATION

Just for practice, look through this program and see if you can see how it works.

Before we finish for this month, we will look at just one more of the string functions available to Extended Basic because you will need it for this month's homework.

LEN (STRING)

The LEN function returns a numeric value equal to the length of the string in the brackets, so that —

```
10 A$ = "PHIL"  
20 L = LEN(A$)
```

would assign a value of 4 to L. Similarly, we could have said —

```
20 L=LEN("PHIL")
```

and L would have taken the same value.

This Month's Homework

There is an old saying which says that you should only eat pork in months whose name contains the letter R. So you could eat PORK in MaRch or SeptembeR, but not in May or June.

For homework this month try to write a program which will ask for name of a month to be input, accept an answer as a string, and then search through the input, character by character, looking for an R. If an R is found, a message telling you that you may eat pork in this month should be printed. If no R is found, the opposite message should be output. So if the input was APRIL, the output would be, YOU CAN EAT PORK IN APRIL etc.

Test your program to make sure that it works by using the following test input data.

- 1) MAY
- 2) OCTOBER
- 3) MARCH
- 4) ENGLAND

Next month we shall go on to examine some more string functions.

THETA III from PICODYTE



Z80 COMPUTER SYSTEM

Memory expansion to 64k or with paging to 256k. Either 2 or 3 integral BASF Mini Diskette Drives. Integral 12" CRT 24 x 80 with detachable keyboard. Serial RS232/20ma and parallel I/O ports.

System software available: CP/M, USCD Pascal, BASIC, FORTRAN, Micro-C, PL/M, COBOL, OPUS and TEMPO.

Optional multiprocessor configurations with custom character sets and graphics, alternative mass storage options and choice of industry standard backplanes.

Dual Disk System £2,900.

PICO OYTE

65 VICEROY CLOSE
BRISTOL ROAD
BIRMINGHAM B5 7UT
021-440-5631

Pet Expansion



Computhink
Dual drive
minifloppy

Complete with 4K disk operating system in ROM, plugs into Expandapet memory. Adds 15 new commands to Pet's Basic to give full disk extended Basic. Loads 8K in 2.6 seconds. Automatic reorganisation of free space. Utility Disk

£833 + V.A.T.

Expandapet memory

Powered by Pet's own powersupply and mounted internally in 5-10 minutes without special tools.


16K..... **£261** + V.A.T.

24K..... **£320** + V.A.T.

32K..... **£374** + V.A.T.

All units are fully built and tested.

Apple II




Apple II was the original with full colour high resolution microcomputer Basic, and it is still the best. With a very wide range of expansion available, including disk drive, interface cards, voice recognition card, light pen and many others.

Apple II has been well tried and approved by the public (over 200,000 sold) because of its thoroughly professional design and high quality engineering. You cannot get better value for money. Please send us a large s.a.e. for further details.

With 16K user RAM only **£820** + V.A.T.

New 7khz 16 channel A to D board p.o.a.

Super Board II



EX STOCK

This 6502 based microcomputer comes with a full 8K Microsoft basic in ROM. Full keyboard, 4K static user RAM (on board expandable to 8K). Kansas City standard interface for use with an ordinary cassette recorder. Machine code monitor and I/O utilities in ROM. Direct Video access with 1K dedicated RAM (besides 4K user RAM) and full graphics set.

Fully built and tested only needs a 5V 3amp power supply and T.V. Monitor or R.F. modulator to be up and running.

£263.84 + V.A.T.

Apple II & TRS80 Memory Expansion



Save Over £100

TRS 80 and Apple II memory expansion kits. Fully guaranteed and with full specification 4116 16K RAMs.

Kits come with full instructions and new jumper sets where necessary. Fitting takes 5-10 minutes, or bring along your Apple or TRS 80 and we will fit it for you for £5.

16K upgrade kit **£85** + V.A.T.

LOTUS SOUND

4 MORGAN STREET
LONDON E3 5AB

TELEPHONE: 01-981 3993
TELEX: 261426 ATN. LOTUS SOUND

This month we continue the 6800 programming course and develop your expertise

After last month's introductory article on the D2 programming course we continue with another set of programs. These are aimed at using more of the various facilities on the kit and in the 6800 instruction set.

It will be useful to have a copy of last month's article to hand for reference purposes while trying out any of these programs.



The Motorola D2 development kit.

Program 6 PERFORM ALL OPERATIONS AS SHOWN IN "REMARKS"								
1	0000	8E 00 FF		LDS		#00FF		Set SP
2	3	48		ASL	A			Double A
3	4	78 00 26		ASL		0026		Double (0026)
4	7	53		COM	B			Invert all bits in B
5	8	7F 00 27		CLR		0027		Set all zeros in (0027)
6	B	70 00 28		NEG		0028		Change (0028) to "2s comp
7	E	7A 00 29		DEC		0029		Subtract 1 from (0029)
8	F	06		TAP				Transfer A to CCR
9	0010	3F		SWI				Stop

This program is just to show off some of the tricks programmers get up to.

Line 2 doubles the contents of ACC A by using ASL which shifts the accumulator one place to the left. It is important to realise that this gives the correct answer only if the shift does cause the sign bit to change; ie, providing the result will not exceed +127 decimal.

Line 3 similar to line 2 except that the shifting refers to address 26. Note however that ASL does not allow DIRECT addressing so the operand must be written as 0026.

Line 4 inverts all bits in ACC B by using COM which means

"complement" (actually the "ones complement").

Line 6 uses NEG which means change to "twos complement" which in turn will change a positive number into a negative number. Be careful not to confuse COM with NEG.

Line 7 uses DEC, meaning "subtract 1".

Line 8 loads the ACC A into the CCR (Condition Code Register).

Strange operation but no doubt useful later on.

The program of course is nonsense and is only included to illustrate some of the way-out instructions so check it out with sample data.

Program 7 USING X TO STORE TWO BYTES IN CONSECUTIVE ADDRESSES								
1	0000	8E 00 FF		LDS		#00FF		
2	3	CE A3 52		LDX		#A352		
3	6	DF 26		STX		26		Stores A3 in (26) and
4	8	3F		SWI				52 in (27)

This program's sole object is to illustrate how to load/store 16 bit registers. Obviously, we can't fill it with a single memory location. In fact the rule is as follows:

The operand quoted "belongs" to the HIGHER-ORDER BYTE of the register.

The LOWER-ORDER BYTE "belongs" to the next higher address.

Line 3 uses STX (Store the Index Register) with the operand 26. This will cause the higher-order byte (X_H) to be stored in address 26 and the lower-order byte (X_L) to be stored in address 27. Thus two adjacent memory locations share the contents of X between them. Line 2 loads X with data using IMMEDIATE addressing with a four hex-digit operand.

Program 8

CLEAR bits 0, 1, 2 IN (43) AND bits 5, 6, 7 IN (44)

1	0000	8E 00 FF		LDS		#00FF	
2	3	96 43		LDA	A	43	
3	5	84 F8		AND	A	#F8	
4	7	97 43		STA	A	43	
5	9	96 44		LDA	A	44	
6	B	84 1F		AND	A	#1F	
7	D	97 44		STA	A	44	
8	F	3F		SWI			

This program illustrates the property of the AND instruction to selectively clear (set to zero) bits within a word without harming the other bits. Remember that a bit pattern (called the "MASK"), when "ANDED" into an Accumulator, will cause the result to be zeros wherever zeros appeared in the mask and unchanged wherever ones appeared in the mask. Thus to clear certain bits, work out a suitable mask word on a piece of paper first, just to "test it". This is wise because the AND instruction is a LOGICAL rather than a familiar ARITHMETICAL instruction and it is not easy to visualise mentally which bits in the mask should be ones and which should be

zeros. It helps to consider how an AND logic gate behaves.
Line 3 ——— The mask is F8. Why? Because we are to erase bits 0, the least signif. bit as well as bits 1 and bits 2. Thus the correct mask word to AND into the ACC is 1111 1000 which is F8 in hex. Note that we can't AND a mask pattern while the data remains in memory. An LDA must first be used to bring it out into an accumulator. The ANDing can then be done and finally the result can be stored back in memory by using an STA (lines 2, 3 and 4 respectively).
Line 6 ——— The mask is now to be 0001 1111 which is 1F in hex and again the process requires three instructions (lines 5, 6 and 7).

Program 9

SUBROUTINE TO PRODUCE A DELAY. *STARTING ADDRESS ARBITRARY

*	0040	CE 00 00		LDX	# 0000	
	3	09	LOOP	DEX		
	4	26 FD		BNE	LOOP	
	6	39		RTS		

Note: The starting number in X is called the TIMING PARAMETER which in the above case is 0000. This is the longest delay, about 0.85 seconds, because 2^{16} subtractions must take place before 0000 is again reached.

Mathematics: CLOCK = 614.4 Kilohertz so one clock cycle = 1.63 microseconds. DEX and BNE each take 4 clock cycles so one rev round the loop takes 1.304×10^{-5} seconds. Thus total delay of 2^{16} revs = $1.305 \times 10^{-5} \times 2^{16} = 0.85$ seconds.
The shortest delay is when 0001 is in X.

This is a subroutine, not a program, so it is useless trying to run it as it stands. The delay is produced by counting down to zero the number in X; the delay mathematics are fully described in the program text.

Note that a subroutine MUST END WITH RTS (Return from Subroutine), code 39.

Program 10

USING ABOVE SUBROUTINE TO GIVE LONGER DELAY

1	0000	8E 00 FF		LDS		#00FF	
2	3	86 10		LDA		# 10	
3	5	BD 00 40	DELAY	JSR		0040	
4	8	4A		DEC	A		
5	9	#26 FA		BNE		DELAY	
6	B	3F		SWI			

TIMING PARAMETER IN ACCA IS "10" IN THIS EXAMPLE (14 Seconds).

This provides a simple example of the use of a SUBROUTINE, ie, makes use of a block of instructions which can be effectively "spliced" into a program by simply knowing whereabouts in memory it is stored and jumping to it with the instruction JSR (Jump to Subroutine). When the subroutine instructions have been executed, its LAST instruction automatically returns control back to the program again. The return (which may be to a different address each time it is used) is ensured by using the instruction RTS (Return from Subroutine) which must be the LAST instruction in the subroutine. How does the RTS instruction "know" where to return? This is where the STACK comes in. The mechanism is as follows;

- When JSR is used in the program, the computer automatically dumps all the registers in the stack including the PROGRAM COUNTER (which is always pointing to the NEXT INSTRUCTION to be executed).
- When RTS is used at the end of a subroutine, the registers in the stack are reloaded (or rather the contents of the stack are reloaded) back into the registers INCLUDING the Program Counter. Thus the program can carry on as if the jump to and back from the subroutine

had never taken place. Even the Accumulators, Index Registers etc will still have their original contents preserved after the return, even if they were temporarily corrupted by the subroutine itself. Returning to Program 12 again note that it uses a subroutine at Line-3. The code BD 0040 will cause a jump to "Program 11" (which of course is assumed to be in memory at address 0040). Note the last instruction in the subroutine is coded 39, which is a single byte instruction RTS. With regard to the logic of program 12, one or two useful little tricks are illustrated such as using an accumulator as a "loop-counter". This is a good opportunity to introduce a flow-chart (which shows the overall strategy of a program). This program uses the maximum 0.85 second delay possible with the subroutine alone and "stretches" it out by using it "N" times, where N is the number loaded into ACC A. In example, N=10 and gives a delay of about 14 seconds, ie, the blank display time between pressing the G button and the appearance of 000B 3F in red. If you have the time, change the value of N in Line 3 to 00 instead of 01 and note how long it takes to arrive at 000B 3F!

Program 11

PIA B OUTPUTS GO HIGH IF ANY PIA A INPUT GOES HIGH

	0000	8E 00 FF		LDS	#00FF	Set SP
	3	CE 00 04		LDX	#0004	Initialise PIA A as
	6	FF 80 04		STX	8004	inputs
	9	CE FF 04		LDX	#FF04	Initialise PIA B as
	C	FF 80 06		STX	8006	outputs
	F	7F 80 04		CLR	8004	Clear PIA A and
	0012	7F 80 06		CLR	8006	PIA B
	5	B6 80 04	BACK	LDA	8004	Test if any input is
	8	27 FB		BEQ	BACK	HIGH
	A	73 80 06		COM	8006	Change PIA B output
						states
	D	3F		SWI		

This program uses that diabolically brilliant device known as the PIA (Peripheral Interface Adapter). It is brilliant in action but, because of the flexibility built into the thing, requires a considerable amount of mental torture before confidence is gained. The MOTOROLA PROGRAMMING MANUAL defines the action of the various registers which lurk within its silicon bowels but it will do no harm to repeat a few of the less obscure features:

- The PIA consists of two almost identical halves, called the A side and the B side.
- Each side has three registers, the DATA REGISTER, the DIRECTION REGISTER and the CONTROL REGISTER.

- These registers can be used by knowing where they are situated in the memory mapping. In the D2 kit, they have been allocated the following addresses,

A SIDE		B SIDE	
DIRECTION REGISTER	8004	DIRECTION REGISTER	8006
DATA REGISTER		DATA REGISTER	
CONTROL REGISTER	8005	CONTROL REGISTER	8007


Note that the Direction and Data registers "share" the SAME ADDRESS

- The address 8004 is the A side DIRECTION register if BIT TWO in the A side CONTROL register is a "0" but the DATA register if a "1"
- The DIRECTION register defines which of the eight data wires in each half are inputs and which are outputs, the RULE being:

"0" = input "1" = output


Thus under RESET conditions, when all PIA registers contain ZEROS, the address 8004 will refer to the DIRECTION register of the A side and the address 8006 to the DIRECTION register of the B side.

A small diagram may not be amiss here:



Until we start using the "handshake lines" CA1, CA2, CB1 and CB2, there is no need to know anything else about the CONTROL registers apart from BIT TWO. As soon as you have set the required directions of the I/O lines, bit two should be set to "1", the remaining bits can be left all "0". Thus after setting direction, load the pattern 04 into the control register to ensure that in future, the DATA register is addressed by 8004 (A side) or 8006 (B side).

Returning now to the actual program; the A side I/O lines are to be INPUTS and the B side I/O lines are to be OUTPUTS so it follows that we must load the hex pattern 00 in the A side DIRECTION register and the pattern FF in the B side. Now the INDEX register X can be used to set the direction and the control register in one go because these occupy CONSECUTIVE ADDRESSES (refer back to program 7). Now examine Line 2 of Program 13 together with Line 3. Note that 00 will be placed in address 8004 (lower order byte of X) and 04



Flowchart for the delay subroutine on the left.

in 8005 (the higher order byte of X). Thus we have set the DIRECTION register as inputs and set bit two in the CONTROL register. This really means that we have no further use for the direction register and in future, the address 8004 is to refer exclusively to the DATA register.

Lines 4 and 5 initialise the B side as outputs (note the pattern is this time FF04 instead of 0004). Lines 6 and 7 simply ensure that both data registers start "empty".


Lines 8 and 9 perform the test (see if any input has gone high). This is done by loading the A side PIA into an ACCUMULATOR and branching back if it contains all zeros. In fact the computer will be rushing round and round lines 8 and 9 thousands of times per second, waiting patiently for someone to turn on a switch. When a switch, any one, is finally turned on, the computer (with a sigh of relief) will at last reach Line 10 which is Complement PIA B side; in other words, turn every lamp from OFF to ON.

It is assumed that the D2 kit has been equipped with a set of lamps and switches on the A and B sides of the PIA. A typical system which

has proved simple and quite satisfactory is shown below.

All PIA I/O lines and handshake controls terminate in a socket, for experimental connections to external logic. This socket is permanently monitored by a LED lamp via an inverter (LS 7404). An input socket is provided close to all I/O lines which provides a TTL logic switched source. Note the output is HIGH with the switch open and LOW when it is closed. For a fully flexible system, twenty of the circuits are required (16 data lines and 4 handshake lines).

The LS (Lower Power Schottky) species of inverter doesn't steal much current from the PIA I/O lines thus allowing reasonable brilliance for the LED with still the odd milliamp to spare for driving external logic gates. Note that when the RESET button is pressed the PIA outputs "float" to the HIGH state. Thus the inverter outputs are LOW turning ALL THE LEDS ON. This was an unintentional bonus, useful for checking out the lamps. It is a useful exercise to run program 13 through under singleshot conditions (using the V and N buttons) in order to check which instruction turns the lamps off.




Circuit diagram for the PIA experiment program.

Program 12 ROTATE A "1" ROUND PIA A WITH DELAYS

1	0000	8E 00 FF		LDS	#00FF	Set SP
2	3	CE FF 04		LDX	#FF04	Initialise PIA A
3	6	FF 80 04		STX	8004	
4	9	7F 80 04		CLR	8004	Clear PIA
5	C	0D		SEC		Set carry bit
6	D	CE 00 00	B	LDX	#0000	
7	0010	09	E	DEX		Delay
8	1	26 FD		BNE	E	
9	3	79 80 04		ROL	8004	Rotate
10	6	20 F5		BRA	B	

Provides an example of the instruction ROL (Rotate Left). Any pattern within a register (or a memory location) can be endlessly revolved by successive ROL instructions. The following diagram of the action of ROL is almost self-explanatory:



Flowchart for rotating a bit round the PIA.


Bits are shifted left one place by ROL and, via the "CARRY" bit, re-enter again at the right hand end. Note that there is room for a NINE-BIT pattern in the loop. Suppose a single binary "1" is required to circulate around the system, say the PIA. The simple way is to first clear the PIA and then use SEC (set carry) which is a single-byte instruction. This places the single "1" in the system which will now circulate one bit at a time for each execution of ROL.

Lines 2 and 3 initialise the A side of the PIA to behave as Outputs. Lines 4 and 5 ensure the "1" is in the system.

Lines 6, 7 and 8 will probably be recognised from previous work in PROGRAM 11 where it was called a "Subroutine to cause a delay". To break the monotony and to provide a "theme and variations" it is not being used here as a subroutine because there is no RTS.

Instead, the three instructions are simply employed within the body of the program and after $X = 0$, the program exits to line 9. Line 9 is the actual rotate instruction and is followed by an unconditional branch back to line 6. Thus the rotation of the "1" is continuous and will appear as a single lamp "moving" from right to left. The speed of rotation can be increased by changing the operand in line 6. Try changing 0000 to 1010. The following flow chart shows the idea behind the program.

Flowchart for the program.



Program 13

CLEAR CONTENTS OF ADDRESSES 40 TO 50 INCLUSIVE

1	0000	8E 00 FF		LDS	#00FF	Set SP
2	3	CE 00 00		LDX	#0000	Clear X
3	6	6F 40	LOOP	CLR	40, X	Clear contents of (40 + X)
4	8	08		INX		
5	9	8C 00 11		CPX	#0011	There are 11 addresses to be cleared.
6	C	26 F8		BNE	LOOP	
7	E	3F		SWI		

This introduces the concept of INDEXED ADDRESSING, an ingenious little trick for performing the same process on adjacent memory locations. Most of the instructions in the M6800 repertoire can be used with Indexed addressing mode so it is essential that an apprenticeship in programming includes this useful dodge in the syllabus.

The assembly format for indicating Indexed Addressing is as follows:
 ZZZ BB, X where ZZZ is the normal OP Code,
 BB is the Operand and X implies
 the INDEX REGISTER.

The actual address (known as the absolute address) is not BB but obtained by adding the contents of X to BB.
 Example: Suppose the instruction is LDA A 05, X. If by chance, X contains 03, the absolute address will be 08. Thus the ACC A will be loaded with the contents of address 08. The value of indexed addressing can be stated as follows:

INDEXED ADDRESSING allows the same instruction to operate on consecutive addresses by incrementing the INDEX REGISTER each time round a loop.

Program 16 will now be examined line by line:

Line 2 simply clears the index register to zero.

Line 3 is the important one; CLR 40, X which will clear contents of address 40

(because X starts off with zero inside it)

Line 4 adds 1 to X, using the single byte instruction INX.


Line 5 compares the contents of X with the number 11 (because there are 11 addresses to be cleared altogether).

Line 6 is a branch back to line 3, causing the instruction CLR 40, X to be executed again but this time, because X contains 1, it will clear contents of address 41. The loop will revolve, clearing successive addresses until X has reached 10, thus clearing address 50. The final INX however will make $X = 11$ and the loop will exit at BNE to stop at SWI.


Because many programs perform the same operation on many consecutive addresses it is worth trying to arrive at a "general purpose" flow chart which can handle such a task.

To see if you have grasped this indexing lark, re-write the program so that addresses 42 to 56 inclusive are cleared—and test it afterwards!

Although the above example has dealt with a very simple process (just clearing addresses) the above general scheme will remain valid for more sophisticated tasks so it is well to study an even more generalised version of the flowchart.



General flowchart for the program.



Some Common BASIC Programs

76 short practical programs, most of which can be used on any microcomputer with any version of BASIC. Complete with program descriptions, listings, remarks and examples.


(200 pages)

B1

Price £6.00



AN INTRODUCTION TO MICROCOMPUTERS




Volume 0 — The Beginner's Book

If you know nothing about computers, then this is the book for you. It introduces computer logic and terminology in language a beginner can understand. Computer software, hardware and component parts are described, and simple explanations are given for how they work. Text is supplemented with creative illustrations and numerous photographs. Volume 0 prepares the novice for Volume 1.

B5 (300 pages)

Price £5.65




Volume 1 — Basic Concepts

This best selling text describes hardware and programming concepts common to all microprocessors. These concepts are explained clearly and thoroughly, beginning at an elementary level. Worldwide, Volume 1 has a greater yearly sales volume than any other computer text.

B6 (350 pages)

Price £6.00



Volume II — Some Real Products (revised June 1977)

Every common microprocessor and all support devices are described. Only data sheets are copied from manufacturers. Major chip slice products are also discussed.


B7 (1250 pages)

Price £18.95

without binder

£24.40

with binder B4




PROGRAMMING FOR LOGIC DESIGN

- C 8080 Programming for Logic Design
- D 6800 Programming For Logic Design
- E 280 Programming For Logic Design

These books describe the meeting ground of programmers and logic designers; written for both, they provide detailed examples to illustrate effective usage of microprocessors in traditional digital applications.

B2/C/D/E

(300 pages each)



PROGRAM BOOKS WRITTEN IN BASIC

- F Payroll With Cost Accounting (400 pages)
- G Accounts Payable And Accounts Receivable
- H General Ledger

These books may be used independently, or implemented together as a complete accounting system. Each contains program listings, user's manual and thorough documentation. Written in an extended version of BASIC.

B3/F/G/H



ASSEMBLY LANGUAGE PROGRAMMING

- J 8080A/8085 Assembly Language Programming
- K 6800 Assembly Language Programming

These books describe how to program a microcomputer using assembly language. They discuss classical programming techniques, and contain simplified programming examples relevant to today's microcomputer applications.

B4/J/K

(400 pages each)



HOW TO ORDER

Payment can be made by sending cheque, postal order, Barclay, Access or American Express card numbers. Write your name, address and the order details clearly, enclose 30p for post and packing or the amount stated. We do not wait to clear your cheque before sending the goods so this will not delay delivery. All products carry 1 year guarantee and full money back 10 day reassurance. All prices include VAT.

Trade enquiries: Send for a complete list of trade prices — minimum order value £100. Telephone Orders: Credit card customers can telephone orders direct to Daventry or Edgware Road.

24 hour phone service at both shops: 01-723 4753 03272-76545.

CALLERS WELCOME
Shops open 9.30 — 6.00.

Metac

**ELECTRONICS
& TIME CENTRES**

North & Midlands
67 High Street, DAVENTRY
Northamptonshire
Telephone: 03272 76545

South of England
327 Edgware Road
LONDON W.2
Telephone: (01) 723 4753

PLEASE MENTION CT WHEN REPLYING TO ADVERTIZERS...

... OUR NEW ADDRESS IS:

145 CHARING CROSS RD. LONDON WC2H 0EE. TEL: 01-437-1002

computing today

WHAT TO LOOK FOR IN THE
AUGUST ISSUE!
ON SALE JULY 27TH.

CT Systems Reviews

We have two for you next month, the new Acorn 6502 based kit, a super MK14 (some would say) and an even newer educational and development kit called the Nanocomputer.

Ancient and Modern

One of the things that we love to hear from you about are your applications for microcomputers. In this tale from the past a PET is being used to collate old parish records. Not a bit ghoulish either!



The PET Bus

Computer busses often seem to be misunderstood, the PET's no exception. In this article we delve in and give you the facts.



Dateline 5000 AD

Your chance to colonise the galaxy from the comforts of the armchair. Despatch your fleets to investigate 'target' stars, determine the mineral value etc, and (of course) do battle with the baddies. Star Trek eat your heart out.



BASIC Football Game

Mr. John N. Bell

This program was produced on a mini in "Standard" BASIC. It should be easily converted to run on any micro running the language. The game plays football and is fairly self-explanatory.

'Welcome to the old firm game at Ibrox, the rules are as follows; the park is 100 yards long and 50 yards wide, the goal is 10 yards wide and 9 feet high. There is a goalie in the goalmouth and you have to judge how hard to strike the ball in order to beat him. The strike range is between 0 and 125. You will be shown a diagram of the pitch.'

```
0001 PRINT "ARE YOU READY.....(1)
      YES.....(2)NO"
0002 INPUT U
0010 IF U=1 THEN GOTO 0014
0011 IF U=2 THEN GOTO 0001
0012 PRINT
0014 PRINT "*****"
0015 PRINT "* CELTS          *"
0016 PRINT "*                  *"
0018 PRINT "*                  *"
0019 PRINT "*****          *"
0020 PRINT "* *          *"
0021 PRINT "* *          *"
0022 PRINT "* * CENTER * LINE"
0023 PRINT "*****          *"
0024 PRINT "*                  *"
0025 PRINT "*                  *"
0026 PRINT "*                  *"
0027 PRINT "*****"
0030 PRINT
0040 PRINT "WHAT SIDE ARE YOU....
      (1)RANGERS...OR (2)CELTIC"
0045 INPUT X
0046 LET R=0
0047 LET T=0
0048 IF X=2 THEN GOTO 0056
0050 IF X=1 THEN GOTO 0052
```

```
0052 PRINT "RANGERS KICK OFF"
0054 GOTO 0060
0056 PRINT "CELTIC KICK OFF"
0060 RANDOMIZE
0061 LET Y=INT(60*RND(0))
0070 LET Z=INT(24*RND(0))
0080 LET C=INT((Y^2+Z^2)^.5)
0100 LET D=C+5
0110 LET E=C-5
0120 LET F=C+1
0130 LET G=C-1
0140 LET H=C-20
0150 LET I=C+20
0160 PRINT
0170 PRINT "THE BALL IS.....";Y"..
      YARDS FROM THE GOAL"
0171 PRINT "AND IS....."Z"..YARDS
      FROM THE CENTER LINE"
0180 PRINT "HOW HARD DO YOU WISH
      TO STRIKE THE BALL?"
0181 INPUT S
0182 IF S<=20 THEN GOTO 0391
0183 IF S>=100 THEN GOTO 0391
0184 LET A=S-40
0185 IF A>H THEN GOTO 0187
0186 GOTO 0196
0187 IF A<E THEN GOTO 0400
0188 IF A>D THEN GOTO 0190
0189 GOTO 0196
0190 IF A<I THEN GOTO 0400
0196 IF A<H THEN GOTO 0190
0197 IF A>I THEN GOTO 0320
0201 IF A=C-2 THEN GOTO 0380
0202 IF A=C-3 THEN GOTO 0380
0203 IF A=C-4 THEN GOTO 0380
0204 IF A=C+2 THEN GOTO 0380
0205 IF A=C+3 THEN GOTO 0380
0206 IF A=C+4 THEN GOTO 0380
0210 IF A=D THEN GOTO 0420
0220 IF A=E THEN GOTO 0420
0250 IF A=F THEN GOTO 0340
0260 IF A=G THEN GOTO 0340
0270 IF A=C THEN GOTO 0360
0280 IF A<H THEN GOTO 0320
0290 IF A>I THEN GOTO 0320
0300 IF A<E THEN GOTO 0400
0310 IF A>D THEN GOTO 0400
0317 PRINT
0320 PRINT "DEFENDER TACKLES
      AND WINS BALL"
0325 PRINT
0330 GOTO 0590
0340 PRINT "GOALKEEPER SAVES SHOT"
```



```

0345 PRINT
0350 GOTO 0530
0360 PRINT "SHOT HITS CROSSBAR
      AND GOES OVER"
0365 PRINT
0370 GOTO 0530
0380 PRINT "WHAT A FANTASTIC
      GOAL!!!!!!!!!!!!!!"
0385 PRINT
0390 GOTO 0440
0391 PRINT "YOU HAVE JUST SCORED
      AN OWN GOAL!!!!!!!!!!!!!!"
0392 PRINT
0395 GOTO 0442
0400 PRINT "SHOT WENT WIDE.....
      GOAL KICK"
0405 PRINT
0410 GOTO 0530
0420 PRINT "WOW!!!!!!...SHOT HIT
      POST AND WENT PAST"
0425 PRINT
0430 GOTO 0530
0440 IF X=1 THEN GOTO 0450
0441 IF X=2 THEN GOTO 0470
0442 IF X=1 THEN GOTO 0470
0443 IF X=2 THEN GOTO 0450
0450 LET R=R+1
0460 GOTO 0490
0470 LET T=T+1
0480 GOTO 0510
0490 PRINT "CELTIC KICK OFF"
0491 LET X=2
0492 PRINT
0494 LET X=2
0495 PRINT "THE SCORE IS RANGERS..
      ";R"..CELTIC.. ";T
0496 PRINT
0500 GOTO 0680
0510 PRINT "RANGERS KICK OFF"
0511 PRINT
0515 LET X=1
0520 GOTO 0495
0530 IF X=1 THEN GOTO 0550
0540 IF X=2 THEN GOTO 0570
0550 PRINT "CELTIC HAVE BALL
      AFTER KICK OUT"
0551 PRINT
0555 LET X=2
0560 GOTO 0060
0570 PRINT "RANGERS HAVE BALL
      AFTER KICK OUT"
0571 PRINT
0575 LET X=1


```

```

0580 GOTO 0060
0590 IF X=1 THEN GOTO 0610
0600 IF X=2 THEN GOTO 0640
0605 PRINT
0610 PRINT "CELTIC HAVE BALL"
0620 LET X=2
0630 GOTO 0060
0640 PRINT "RANGERS HAVE BALL"
0645 PRINT
0650 LET X=1
0660 GOTO 0060
0680 LET Y=T+R
0690 IF Y=6 THEN GOTO 0700
0691 IF Y=8 THEN GOTO 0710
0692 GOTO 0060
0700 IF T=R THEN GOTO 0750
0705 PRINT
0710 PRINT "THE FULL TIME
      WHISTLE HAS GONE DO
      YOU WISH TO PLAY AGAIN?"
0720 PRINT "... (1) YES.... (2) NO...."
0725 INPUT V
0730 IF V=1 THEN GOTO 0040
0735 IF V=2 THEN GOTO 0800
0750 PRINT
0751 PRINT "THE FULL
      TIME WHISTLE HAS GONE,
      DO YOU WISH TO PLAY ANY"
0752 PRINT "EXTRA TIME?"
0755 PRINT "... (1) YES.... (2) NO...."
0760 INPUT W
0770 IF W=1 THEN GOTO 0060
0780 IF W=2 THEN GOTO 0870
0800 IF T>R THEN GOTO 0830
0810 IF R>T THEN GOTO 0860
0830 PRINT
0840 PRINT "CELTIC--CELTIC--CELTIC
      ....ECHOES THROUGH THE GROUND"
0841 PRINT "AS THE CELTIC
      FANS CELEBRATE YET
      ANOTHER FAMOUS OLD"
0842 PRINT "FIRM VICTORY
      OVER RANGERS"
0850 GOTO 0870
0860 PRINT ""
0861 PRINT "WE ARE THE PEOPLE...
      WE ARE THE PEOPLE...
      WE ARE THE PEOPLE"
0862 PRINT "CHANT THE RANGERS
      FANS AS THE FAMOUS
      GLASGOW RANGERS"
0863 PRINT "THUMP CELTIC ONCE
      AGAIN AT IBROX STADIUM"
0870 END

```


SPECIALS



TOP PROJECTS

Book 1 + 2: £2.50 + 25p P&P.

Master mixer, 100W guitar amp., low power laser, printmeter, transistor tester, mixer preamp., logic probe, Ni-Cad charger, loudhailer, 'scope calibrator, electronic ignition, car theft alarm, turn indicator canceller, brake light warning, LM3800 circuits, temperature alarm, aerial matcher, UHF-TV preamp., metal locator, four input mixer, IC power supply, rumble filter, IC tester, ignition timing light, 50W stereo amp. and many more.

Book 3: SOLD OUT!

Book 4: £1.00 + 25p P&P.

Sweet sixteen stereo amp., waa-waa, audio level meter, expander/compressor, car theft alarm, headlamp reminder, dual-tracking power supply, audio millivoltmeter, temperature meter, intruder alarm, touch switch, push-button dimmer, exposure meter, photo timer, electronic dice, high-power beacon, electronic one-armed bandit...

Book 5: £1.00 + 25p P&P.

5W stereo amp., stage mixer, disco mixer, touch organ, audio limiter, infra-red intruder alarm, model train controller, reaction tester, headphone radio, STD timer, double dice, general purpose power supply, logic tester, power meter, digital voltmeter, universal timer, breakdown beacon, heart rate monitor, IB metal locator, temperature meter...

Book 6: £1.00 + 25p P&P.

Graphic equaliser, 50/100W amp. modules, active crossover, flash trigger, "Star and Dot" game, burglar alarm, pink noise generator, sweep oscillator, marker generator, audio-visual metronome, LED dice, skeet game, lie detector, disco light show...


Graphic Equaliser...Marker Generator
Power Amplifier Modules...£2 Sound
CCTV Camera...Headphone Adaptor
LED Dice...Sound-Light Flash Trigger
Expander-Compressor...Skeet Game
Ranch...
ETI TOP PROJECTS
NO 6 electronics today £1
Burglar Alarm...Digital Thermometer
Stars & Dots Logic Game...Lightshow
Active Crossover...Hear and Tell Unit
Pink Noise Generator...GSR Monitor
Sweep Oscillator...Stereo Simulator



ELECTRONICS TOMORROW

Comprised entirely of new material, the edition covers such diverse topics as Star Wars and Hi-Fi! The magazine contains projects for everyone — none of which have appeared in ETI — and a look at the future of MPUs, audio, calculators and video. How can you not read it?

75p + 25p P&P.



ELECTRONICS — IT'S EASY

Books 1, 2 & 3.

Our successful beginners series came to an end some time ago now, and the whole series is available from us in reprint form. The three books between them contain all the information presented in the series (sometimes in more detail!) and together form an excellent starting point for anyone interested in learning the art of electronics.

£1.20 + 25p P&P each.

FROM THE PUBLISHERS OF
ELECTRONICS TODAY INTERNATIONAL

ETI CIRCUITS No 2

£1.50

ETI CIRCUITS

Books 1 & 2.

Each volume contains over 150 circuits, mainly drawn from the best of our Tech-Tips. The circuits are indexed for rapid selection and an additional section is included which gives transistor specs, and plenty of other useful data. Sales of this publication have been phenomenal — hardly surprising when the circuits cost under 1p each!

£1.50 + 25p P&P each.

ORDER FROM

Specials Modmags Ltd 145 Charing Cross Road London WC2H 0EE

Postage and packing also refers to overseas. Send remittance in Sterling only.

Please mark the back of your cheque or PO with your name and address.

from ETI

APPRECIATING MPU's

An explanation of the why's and wherefore's of the microprocessor revolution

Periodically, the media goes berserk over some device which is supposed to "revolutionise technology", their latest toy being the poor microprocessor. In fact, the microprocessor is in no way revolutionary; it was the inevitable consequence of circuit integration which began in the mid sixties when someone managed to persuade more than one transistor to rest on a silicon chip. (The media can't even get this right ——— they call it the silicone chip which indicates some relation exists between microprocessors and furniture polish).

Evolution

The cost of developing an LSI chip is high, very high and can only become a profitable exercise if the sales are enormous. But——the more complex the IC the more dedicated it becomes and the global demand falls. In 1971 a small firm (no longer small) called INTEL launched a general purpose computing chip which they called a "microprocessor". Because of the unrestricted applications of the device, the deadlock was broken. Without in any way wishing to deny INTEL the glory they deserve, there is little doubt that in 1971, if INTEL had not produced the microprocessor somebody else would have done. There was a need for it so it was invented. Prior to the middle of the 18th Century there was no desperate need for the calculus but when the need arose, it was invented simultaneously by Leibnitz and Newton. Thus the microprocessor was evolutionary rather than revolutionary.

Impact

The impact of the microprocessor on technology can be summed up in one sentence. It has enabled computing power to be used in situations, which prior to its introduction, would have been dismissed as outrageously expensive. Computing power enables sophistication, intelligence and versatility to be built into any system. Thus multimeters, signal generators, wrist-watches and door-chimes are beginning to boast of a microprocessor "brain".

Another spin-off is the growing popularity of what is called "Distributed Processing". Thus instead of a large central processor having elevated status, completely controlling every trivial activity of its subordinate peripherals, it is now economic and sensible to delegate power to the various subsystems. Distributed Processing is not a new idea; it is just that microprocessors have allowed it to flourish.

Home Computing

The year 1978 will be remembered in the UK as the dawn of the home computer. Perhaps the most outstanding event of the year was the launching of the PET 2001 by Commodore Business Machines (CBM). Inside this neat cabinet (fit enough in appearance to sit on a lounge table) was a micro-processor, some semiconductor memory chips, power supply, a keyboard with full ASCII plus graphics, a tape cassette backing store and a VDU display. It could be programmed in Assembly language or BASIC with an ambitious operating



The ubiquitous PET home computer.

system almost self-explanatory in use. The launching price was about £700 but early in '79 was reduced to £499. For those who have grown up through the computer age, a price like this must have been unbelievable.

Only three or four years prior to the PET, equivalent computing power would have cost something in the order of £5000. Bearing in mind inflation over that period the relative cost has dropped by a factor of almost twenty to one. Anyone who doubts that the home computing craze is here to stay would be advised to examine the bookstalls. The competition in this comparatively new market is fierce and it is doubtful if the PET will retain its present dominance.

Application

The obstacle in the road of microprocessor development at the moment is not programming. It is invention of APPLICATIONS. We are not yet used to the idea of cheap computing devices freely available over the shop counter. Computers have been around for many years in the role of the mathematical or clerical labourer but their insides have been taken for granted. An engineer, technician or manager considered a computer as a general purpose tool which crunched up input data and presented "answers". The computer was the keyboard! Conversations were carried out in almost plain English with the help of operating systems designed to enable almost anyone to benefit from the computer without necessarily knowing anything about computers.

It is the cheapness of the microprocessor which will force it to intrude into the engineering environment, not in the traditional computing role of a "question and answer data crusher" but as the controlling power in some comparatively trivial black box.

What Is A Microprocessor?

A traditional "computer" was considered to be a black box containing the following subsystems:

- a. Central processor (consisting of a control unit and

arithmetic and logic unit)

- b. Internal memory to store instructions and data and constructed from tiny magnetic cores which were able to retain their information even if the power supply was switched off—a so-called NON VOLATILE memory.
- c. An input/output buffer to communicate with peripheral devices such as teletypes, tape or disk backing-stores.

The internal core memory of the computer was very expensive and because its manufacture was labour-intensive, the device showed signs in the early seventies of succumbing to the new technique of "semiconductor" memories. They were much faster, less bulky, consumed less power and were more reliable.

As mentioned, INTEL decided to launch an IC which contained all the logic required for the function of Central Processor. Thus a provisional definition of a microprocessor is simply the "central processor part of a computer". To produce a fully operational "computer", it is necessary to connect a memory chip (or chips) and another chip designed to act as an input/output interface. (Such is the rate of advance in this area that before long, most manufacturers will integrate all three chips into one).

Microprocessor systems emulate the Meccano principle. Buy the microprocessor chip, as much memory as desired and an I/O chip and wire up. In order to allow such flexibility, the microprocessor chip is equipped with three bus systems called the ADDRESS BUS, the DATA BUS and the CONTROL BUS. They have the following functions:

- a. ADDRESS BUS is used by the microprocessor to select a particular memory location according to the address code it puts out on the bus.
- b. DATA BUS collects data from memory or stores data in memory.
- c. CONTROL BUS is a collection of lines carrying pulses to synchronise the system and to tell the memory when to output data and when to allow fresh data in.

Figure 1 shows the plan:




Figure 1. Internal structure of an MPU.

The Address Bus

The number of wires in the address bus determines the maximum number of memory locations which can be uniquely addressed. This is because every memory location must have a unique address code.

Most microprocessors have 16 wires in the address bus, so it would be possible to build up the memory to a maximum of 2^{16} which is 65,536. This is a convenient time to introduce the symbol "K" used as a shorthand unit in binary systems:

$$1K = 2^{10} \text{ (which is 1,024 decimal)}$$

Thus instead of relating 2^{16} to an awkward decimal number, it becomes a round 64K.

It would be most unusual for a system to require 64K of memory.

Note from Figure 1 that the address bus is uni-directional; the information can only come from the microprocessor. The voltage levels on the bus are normally standard TTL, ie a HIGH is any voltage between 2V4 and 5V and a LOW is any voltage between 0 and 0V4. The available current drive from the bus wires is unfortunately seldom sufficient to drive all the required memory chips unless extra buffer drivers are used.

The Data Bus

The number of wires in the data bus defines the word-length of the system. A simple definition of word-length is the number of bits transferred or processed by a computer instruction. Alternatively, word-length is the "width" in bits of a memory location and is probably the most important parameter in a computing system. Most microprocessors have a word-length of EIGHT bits which is very short when compared with traditional minicomputers. Nevertheless, for the role of controlling a system, 8 bits is normally adequate.

It has become accepted that a block of eight bits is termed a BYTE; most modern computing systems are "byte-orientated" because the standard keyboard code is the ASCII (American Standard Code for Information Interchange). Pressing one key on an ASCII keyboard outputs a seven bit group of bits which is normally joined by an error checking bit (known as the parity-bit), bringing the total up to 8 bits.

One of the inevitable results of standardisation is the growth of variations! Thus there are variations on the ASCII such as the "restricted" form of six bits (allowing only 64 different characters instead of 128).

A glance at Figure 1 confirms that the data bus is bi-directional to allow the microprocessor to place new data in memory (called writing) and to allow data in memory to be routed into the microprocessor (called reading).

One difficulty of the 'Meccano' system is ensuring that only one byte of data is on the data bus at one time. Figure 1 shows that the data wires of all the boxes are connected to the one data bus. There are two solutions:

WIRED OR

The memory output buffers to the data bus are the "open-collector" type which demands that pull-up resistors are required on each bus line to the +5 V power line (assuming of course the buffers are TTL.) This is generally regarded as a sloppy solution.

TRI-STATE-CONTROL

A two state logic output is either in the HIGH state

APPRECIATING MPU's

or the LOW state. A tristate logic system has an extra, non functional state which presents a high (ideally infinite) impedance to any line to which it is connected. Thus a memory box with tristate output buffers can be made to appear non-existent to the data bus. However many boxes are connected across the data bus, providing only one is functional at the same time, there is no chaos.

The Control Bus

This is a hotchpotch of wires, each having a dedicated function. Some of them are outputs to the memories, some are signals from the memories, some may be "messages" from the outside world (peripherals). Their number and function will depend on the particular microprocessor type, which in turn will depend on the degree of sophistication offered. The following are more or less typical of most microprocessors:

RESET

A signal from this input (usually from an external push-switch) starts an initialisation routine which sets the internal registers to zero and outputs a special address code.

READ/WRITE

This is an output from the microprocessor to inform the memory chips when they are to READ onto the data bus or WRITE from it. It is usually a single wire and could be marked R/W, which is an abbreviated symbolism to indicate that when the wire is in the HIGH state it is commanding the memory to READ and when LOW write.

VALID MEMORY ADDRESS (VMA)

Although some species of microprocessor differ in the way synchronisation is achieved most of them use one clock pulse to send out an address on the bus, and the next one to read the contents onto the data bus. Some time interval must elapse before the address bus has stabilised (even if it is only a few nanoseconds) so the microprocessor sends out a VMA signal which is arranged to be comfortably delayed on the clock pulse. By ANDing this with the clock and the R/W line, the data is made healthy.

INTERRUPT REQUEST

"Interrupt" is a technique allowing a peripheral device to barge in on the computer and divert its attention to another program previously written for the peripheral, ie, it is a peripheral initiated sub-routine. After the peripheral servicing (which may be something quite ordinary like inputting one character from a teletype) the computer returns automatically to the point in the program at which it was interrupted. To initiate an interrupt, a wire is provided called IRQ which when activated, will REQUEST permission to interrupt. This is granted, subject to the state of a special control bit called the "interrupt" (which is programmable).

NON-MASKABLE INTERRUPT

This line (when present) has higher priority than IRQ and is not subservient to the state of the interrupt mask bit.

Semiconductor Memories

There is an abundance of memory chips available differing in semiconductor type, word-length, access time and of course capacity. There is also an abundance of related jargon which demands explanation:

CAPACITY

Superficially, the capacity of a memory is the amount of information it can store. Capacity can be measured in terms of how many BITS it can store or how many WORDS it can store. Most memories, intended for microprocessor use, are arranged in blocks of "pigeon-holes" each storing one byte (8 bits).

Thus a memory chip described as "1K X 8" would hold 1024 bytes of information. Each of the 1024 pigeon holes or LOCATIONS would have a unique ADDRESS CODE associated with it.

Since 1971, technology has developed a lust for packing more and more locations into less and less space. The latest craze is the media's obsession with the "64K" memory, although they appear disinterested in whether this means bits or bytes!

SEMICONDUCTOR TYPE

There are two primary divisions:

Bipolar, employing normal bipolar junction transistors. These are very fast, relatively expensive and seldom necessary in the majority of microprocessor applications.

MOS, cheaper than bipolar, capable of higher packing densities but not as fast. Until recently, the majority of MOS memories employed p-channel enhancement mode which required two supply voltages, one of which was (rather awkwardly) negative to ground. In spite of early difficulties, n-channel MOS memories are now becoming commonplace and because of the single +5 V power supply, are very popular.

STATIC OR DYNAMIC

The primary storage element in a "static" memory is the bistable flip-flop which can rest in either of two states. In contrast, the "dynamic" memory is virtually a capacitor storage register which must be kept refreshed. The 1s and 0s are stored in the inter-electrode capacitance of MOS transistors. To ensure stored data is preserved, a "refresh" cycle is required every few milliseconds. Thus; STATIC memories store data, even at rest; DYNAMIC memories require periodic refresh cycles. This is an annoyance to grin and bear if large capacity memories are required at minimum cost.

RAMS and ROMS

Traditional computing engineers were accustomed to core memories which were supposed to be non-volatile. After switching off at night, they expected their data to be available again in the morning (an optimism not always justified).

The introduction of semiconductor memories, capable of being read from and written in to in the same way as core memories, forced engineers to abandon their loyalties to non-volatility (always a kind of sacred cow). For some unaccountable reason, semiconductor memories with read/write functions are called "RAMS" (which originally meant Random Access Memories to distinguish them from

APPRECIATING MPU's

sequential access backing stores such as magnetic tape drives).

It is not difficult to appreciate that the ability to read and write is a valuable asset but the habit of losing data everytime the power is interrupted can be downright unpleasant. Fortunately, there are ROMs.

ROM stands for "Read Only Memory", implying that in return for the non-volatility we have to forego the ability to write new information into it. There is of course an obvious question: How did the data get into the ROM in the first place? There are two types of ROM:

MASK PROGRAMMABLE ROMS.

The user tells the manufacturer the bit-pattern required and a mask is prepared which produces the ROM. This is expensive as a "one-off" but tolerable in mass-production projects.

USER PROGRAMMABLE ROMS.

The ROM is supplied "naked" and the user can "burn" in the required bit pattern—but there is no second chance if even one bit is entered in error since it can't be changed.

PROMS

This stands for Programmable Read Only Memory, a sickly example of modern gobbledegook resulting from the craze to force an acronym into existence. Superficially the PROM would appear to be the same as a RAM because if it can be read from and new data can be programmed in then technically it is a RAM! Nevertheless, there is a difference:

A PROM can be read normally but its data can only be changed by erasing the old data (by a special process) and re-programming with special voltage pulses. If a mistake is made, the PROM can be erased again and the process recommenced.

The most popular PROM on the market is the "ultra-violet erasable" which has a small transparent quartz window on the top, directly above the active chip area. To erase the data, the chip is placed in a box fitted with a powerful ultra violet lamp.

Connecting Memories

This is best explained with the aid of a diagram (Figure 2).




Figure 2. Hanging memories onto a bus.

There are two categories of address wires on a memory chip:

- INTERNAL ADDRESS wires** to select a particular location, the number of them depending on the memory capacity. Thus the RAM shown in Figure 3 has seven, allowing 128 different address codes. They are labelled A_0 to A_6 and connected to the corresponding lower-order address lines on the microprocessor address bus. The ROM requires ten internal address wires, labelled A_0 to A_9 in order to select any one of 1024 address codes. These are also connected to the corresponding lower-order lines on the address bus.
- CHIP SELECT wires** to select which chip is to be "enabled". The term "enabled" means to make functional or make "live". A "disabled" box is dead. In practice the chip select wires control the tristate output buffers to the data bus; The number of chip select wires on any make of memory varies, some have as many as six. However many there are, they must ALL be enabled to make the box live. They are usually labelled, CS0, CS1, CS2 etc. although some are crowned by the negator bar indicating they must be held LOW to enable. The chip select wires are connected to the higher order address lines in any arbitrary arrangement providing it is impossible for any address to enable two or more boxes simultaneously; addresses should be mutually exclusive.

Notice that only the RAM requires a R/W driver: the ROM can only read!


Input/Output Ports

Microprocessor systems connect with the outside world via buffer stages known as "ports". The design of these ports would appear to be a trivial exercise, unworthy of a special paragraph; indeed, some manufacturers share this view and merely provide a few pins on the microprocessor chip. Others have different ideas, considering the I/O ports merit status almost equal to that of the microprocessor itself and produce special ICs as part of the package deal.

- SERIAL**, meaning the input data is received bit by bit, each arriving one after the other. Most teletypes deliver data words in serial form and receive them in the same manner.
- PARALLEL**, meaning data words can be delivered or received in parallel. These have a higher selling power than serial because, in principle, they can combine both functions. They may be called Peripheral Interface Adapters (PIA), although manufacturers choice of names are often quite exotic.

It follows that any I/O port IC must contain some registers in order that:

- input or output data can be buffered (often called data registers).
- to set the desired direction of data, ie, whether a particular line is to behave as an input or an output. These matters are often decided by the pattern of bits programmed into the direction registers. These of course would only be necessary if the peripheral lines were undedicated.



With the promise of hot summer days ahead you will all want to get your hands on one of our Computing Today T shirts. Available at a bargain price of £2 each they are in black cotton with our logo in white on both front and back. We don't guarantee that you will look quite as stunning as our model but it's bound to be a talking point. Order yours today from:

Computing Today,
145 Charing Cross Road,
London WC2H 0EE

Don't forget to give us your size (S, M or L)!

- e. control registers to program a particular behaviour response (if there are many to choose from).

Programming I/O Ports

There are two methods:

- a. By the use of special I/O instructions.
- b. By treating the port as a memory location (or group of locations). For example, suppose a particular PIA has four internal registers and the specification demands they be allotted consecutive address codes, it follows that the system designer can wire up a PIA anywhere he chooses with the knowledge that only four address codes are "wasted". This method is known as the "Memory Mapped" I/O port and is more flexible because there is no limit (apart from the upper limit of 64,536 address codes) on the number of PIAs which can be connected.

A Typical PIA

Figure 3 shows the interface presented to peripherals by the Motorola PIA, which is a good example of a memory mapped I/O port.




Figure 3 The Motorola PIA.

For precise details, consult Motorola data sheet on the IC but the basic facts are as follows. There are two virtually identical halves (side A and side B). Each of the 8 data lines can be programmed independantly of each other as inputs or outputs according to the pattern of 1s and 0s in the direction register. The programmer can place a "1" in this to define the corresponding data wire as an output and a "0" to define an input.

The primary object of the control register is to define the behaviour of the special "handshake" lines CA1 and CA2 on the A side (CB1 and CB2 on the B side). CA1 is dedicated as an Input which can be used to set a "flag bit" in the control register and (if the programmer desires) cause an interrupt request. CA2 can also behave in the same manner but can also be programmed to behave as an Output. The handshake lines are a valuable addition to the versatility of the PIA, particularly when handling peripheral machinery.

Field Of Choice

Assume that you are thinking of using a microprocessor to

control "something" and a preliminary outline system is simmering somewhere in the back of the mind. How do you decide on which microprocessor? Is it to be an INTEL 8080, a MOTOROLA 6800, a ZILOG Z80, a TEXAS 9900 or a ROCKWELL, a FERRANTI etc.

The trouble is there is *too much* information about them, *too many* glossy sales brochures, *too many* embarrassingly polite salesmen eager to "explain" the relative superiority of their particular product. Adding to the confusion is the falling prices and the increase in sophistication of the new species (or "Mark 2" models of existing species). In fact the situation is a classical example of Sods Law.

We can proceed to dissect out the individual features which appear in the brochures. Only facts are given and no attempt will be made to compare actual processors.

Word Length

Most microprocessors have an 8 bit word length, one or two have 12, and an ever increasing number of the new varieties have 16 bits. Ignoring the 12 bit (which frankly is a bit of an oddity in the modern climate) the question is which is the best?

For a given clock frequency, a 16 bit microprocessor can process data at twice the speed of an 8 bit. Arithmetical quantities expressed as a 16 bit positive integer are accurate to 1 part in 65,536 whereas 8 bits are accurate to 1 part in 256.

If a microprocessor is considered as a number-crunching "calculator", the above arguments clearly brand the 8 bit as a poor relation. If for example the intention is to make a microprocessor the brain of a fully fledged desk-top computer, capable of programming in BASIC or FORTRAN and able to project fascinating pictures on a CRT, the 16 bit has the edge.

But there is a credit side to the 8 bit microprocessor. It is cheaper, there are more of them about, they have at least 8 pins less on the chip (unless the 16 bit job employs a rather irritating trick called "multiplexing") and when employed on system control (rather than number crunching) tend to be less wasteful on memory. It is possible to use "double precision" arithmetic in which two memory locations are used to store double length words. This is not difficult either but, as mentioned before, tedious. Although open to the charge of over-simplification, it appears that the subject of word length can be resolved as follows:

If most of the data handled is of 8 bit precision there is little overall benefit in choosing a 16 bit microprocessor.

Clock Frequency

All microprocessors require some form of clock to provide the master timing pulses. Some of the later arrivals have a built in clock circuit so only the external crystal need be supplied extra. In general, the higher the clock frequency the greater the "throughput" (an ugly but quite descriptive jargon word which means how fast data is processed). The user has a certain amount of freedom in choice of clock frequency subject to an upper frequency limit and, strangely, a lower frequency limit. Most microprocessors are designed with dynamic internal registers which must set a minimum clock frequency. Typical upper frequency limits vary from 500Hz (considered slow), 2MHz (considered reasonable) to above 5MHz which is fast!

However, it must not be thought that a high clock frequency automatically implies high throughput. Other

APPRECIATING MPU's

things being equal then of course a high clock frequency must mean a speedier work force. But other things are seldom equal. For example, the number of clock cycles required to perform the "average" instruction is as important as clock frequency. Thus a microprocessor working at 2MHz clock frequency may take four clock cycles to execute an "Average" instruction, whereas a competing species may operate on 1MHz clock but only take two clock cycles to execute this instruction. Thus from this viewpoint they are both as fast.

Number Of Accumulators

A computer requires somewhere to breathe, to carry out the various arithmetic and logical processes which the programmer directs. It is not easy to perform these operations on data residing in memory so certain registers are provided equipped with complex electronic circuits. The data can then be placed into these registers, processed and perhaps returned back to memory. These general purpose registers are called accumulators.

Some microprocessors have only one accumulator, some two and some have eight or more. There is no doubt that multiple accumulators make for easier programming and can increase throughput. Thus if there is only one accumulator, there is a continual "to and froing" between memory and accumulator, ie, tedious repetition of load and store instructions because of the lack of breathing space.

It is worth mentioning that the TEXAS 9900 is unique in having no accumulators at all! Instead, the programmer can pick a block of memory locations and virtually designate them as "accumulators" or "working space".

The Instruction Set

The pages of frightening hieroglyphics called the Instruction Set can strike terror in the hearts of some people (including the writer's). It is a list of all the machine instructions which the particular brand of microprocessor is capable of carrying out. It is an indispensable document to the machine or assembly language programmer, couched in precise legal terms and rich in symbolism. Every instruction is allotted a unique "machine code" (which the computer "understands" even if the human doesn't) and a corresponding group of letters having mnemonic value (which the computer doesn't understand but the human does). It is not profitable at this point to dwell too much on the gory details of the instruction set except insofar as they influence the choice of a microprocessor.

In general, there are two parts to a machine instruction:

- The Operation Code (OP code) which tells the machine WHAT to do.
- The Operand which tells the machine WHERE to find the data.

Thus the format of (most) instructions is as follows:

OP code	Operand
---------	---------

For example, using letter groups for the OP code (instead of machine numerals) an instruction might appear as:

ADD	34
-----	----

ADD of course implies "add to the accumulator" but the "34" introduces a complication. Does it for example mean

literally add the number 34 to the accumulator or does it mean add the contents of address 34 to the accumulator? It all depends on the machine code. Thus there will be several different types of ADD instruction depending on the significance to be attached to the operand. These variations on the ADD (or indeed any other instruction) are called addressing modes.

It is probably true to say that the number and novelty of the possible addressing modes available on each instructions is of greater value than the total number of instructions. Thus a processor with say, 200 different instructions with four addressing modes may very well be inferior to one with only 70 instructions but with seven or eight addressing modes.

It is convenient to first discuss the addressing modes which are common to almost all microprocessors which are:

LITERAL or IMMEDIATE——the operand is the data.

DIRECT——the operand is the address in memory of the data.

IMPLIED or INHERENT——no operand is required; the code itself is sufficient (example: clear Accumulator).

The more sophisticated addressing modes (and very powerful in programming) are not all found in every microprocessor:

INDEXED——the operand and the contents of an INDEX REGISTER are added together, the result being the absolute address of the required data. Useful for making the same instruction operate on different memory locations by changing the contents of the INDEX REGISTER.

INDIRECT——the operand is the address of a location in which the required address of the data is stored. (this should be read a few times before it makes sense).

Example: Suppose the operand is 34. Suppose also that in an address 34 is the number 56. Then,
34 is the INDIRECT ADDRESS
56 is the address of the required data.

Indirect addressing is used for the same purpose as Indexed addressing, ie, the indirect address can be changed to alter the effect of the instruction. However, indirect addressing is in many ways superior to indexed addressing because any memory location can be used as an indirect address instead of the limit imposed by having a single (or perhaps a few) index registers.

PRE-INDEXED INDIRECT——the operand and the contents of an index register are first added, the result is the location where the indirect address is stored. A good programmer can work "miracles" with this facility. Unfortunately, if he expires in the middle of a program it could be a nightmare for someone else to debug and complete.

POST-INDEXED INDIRECT——similar to pre-indexed but the contents of the index register is added to the indirect address to produce the absolute address.

RELATIVE——these are only used in BRANCH or JUMP instructions; the operand is a number indicating how many instruction address backward (or forward) the computer must jump to obtain its next instruction. The term "relative" means with respect to the current instruction address.

Hardware Within The Microprocessor

Instead of throwing a dead microprocessor chip away it will

be found a rewarding exercise to prise away the case (somehow?) to expose the active chip area. To the naked eye, only a blur of ridges and valleys appear but on the microscope stage, with say, a times four objective and times ten eyepiece, the full beauty is exposed. Even a low priced chip will probably contain twenty to forty thousand active semiconductor devices arranged in a geometric order which only a computer could design. Having marvelled for a few minutes, forget it. Any attempt to unravel the detailed architecture will lead to despondency. For practical purposes, it is sufficient to be aware of the major registers available to the programmer and perhaps an overall crude idea of the operating sequence. The major registers common to most microprocessors are:

- a. **PROGRAM COUNTER** is the major domo because the contents is the address of the next instruction to be executed. It is automatically incremented after each execution thus defining the rhythm of a "Von Neuman" machine, ie, instructions executed in numerical address sequence. The exception to the rhythm is when a Branch is executed and the Program Counter has an abrupt change of contents.
- b. **ADDRESS COUNTER** contents determine the location of the data (operand). In fact the way in which a computer "knows" what is data and what is an instruction is simple:
If the address bus was loaded from the Program Counter it assumes it is an instruction.
If the address bus was loaded from the Address Counter, it assumes it is data.

INSTRUCTION REGISTER holds the OP code whilst it is being decoded and implemented. An instruction, although a single item of action as far as the programmer is concerned, requires many individual actions carefully worked out during the embryonic stage of design. Each different instruction must have its own set of steps, forming a "Microprocessor". The microprograms are stored in a ROM inside the microprocessor chip (not to be confused with the external ROM which hold the program). The contents of the Instruction Register hold the starting address of the microprogram; the OP code becomes an address!

DATA REGISTER is the buffer between the microprocessor and the external data bus and is bi-directional.

ADDRESS REGISTER is the buffer between the microprocessor and the external address bus.

ACCUMULATOR/S have been previously described as general purpose registers available to the programmer.

INDEX REGISTERS, used in the indexed addressing mode, often double-length.

STACK POINTER is in some ways similar to the Program Counter except it points to the address of a data item instead of an instruction. Special instructions called PUSH and PULL (or Poke and Pop) allow data to be stored or retrieved from a selected block of memory locations on a "Last in, First out" basis, often described as a LIFO stack.

Condition Code Register (CCR) keeps tally on the result of most instructions by setting to 1 or resetting to 0 certain bits. Thus if the last result yielded a negative result, the "N" bit would be set to 1. Branch instructions must "look" at the CCR before deciding whether or not to branch.

There may also be a special bit called the "Carry" which is set if the last arithmetic instruction resulted in a carry. Overflow bits and Interrupt mask bits may also be allocated positions in the CCR. An alternative name for this register is the Program Status Register.

Figure 4 may give some idea of the data paths expected in a "typical" chip.




Figure 4. Pathways for the data to roam!

Communication between the various registers is via the internal data highway, each register having an input gate and an output gate. The individual steps of an instruction microprogram are triggered off by timing pulses which "read" the ROM. The pulses are normally subdivisions of the clock pulse, produced by the timing pulse generator. The word read out from the ROM is virtually an input to a decoding matrix which selects the appropriate pair of gates and/or timing pulses. As mentioned previously, the OP code received, by reading the external ROM holding the program, is brought into the instruction register, where it functions as the starting address of the microprogram associated with that OP code. As far as the overall picture is concerned, the action can be broken down into:

a. FETCH PHASE

The next instruction is brought out from external ROM and routed internally via the data bus and highway. The Program Counter is then incremented.

b. EXECUTE PHASE

The instruction is executed.

APPRECIATING MPU's

Thus the action is a repetative FETCH, EXECUTE, FETCH, EXECUTE ad infinitum until the program is halted.

With the short word length of microprocessors, the situation is a little awkward because the average instruction cannot be "Fetched" in one go. In fact, many instructions are three-bytes in length: one byte for the OP code and two bytes for the operand which means that the Program Counter must be incremented three times to fetch such instructions. During the Execute phase, the same problem can exist because the operand is normally an address which necessitates a further couple of trips to external RAM. Thus it can be seen that some instructions can gobble up three or four clock pulses. If the "average" instruction takes n pulses, then the average execution time of an instruction is clearly equal to $\text{Clock frequency}/n$, a disappointing drop in apparent performance! The advantage of choosing Inherent addressing mode should now be clear——no operand. Because some rather disparaging comments were made earlier regarding the doubtful advantage of the 16 bit microprocessor, it would be ethical at this point to highlight the speed advantage during the Fetch phase. Thus the complete instruction, code and operand, can often be fetched in one clock pulse because of the longer word length.

Microprocessor Or Hardwired?

In the present euphoric atmosphere surrounding micro-


processors it is easy to become infatuated with them and to cultivate a condescending air towards systems employing hardwired logic (gates, counters flipflops etc.) If a system is to be designed, the first question should not be "which microprocessor" but rather "is a microprocessor necessary at all"? In fact it may be considered strange that such a fundamental question should be left until the last paragraph of these notes. But, until some idea of the complexity surrounding the things have been discussed there would be no solid ground to make such decisions. Even with knowledge, it is not easy although the following can be taken as rough guidelines:

a. HARDWIRED

If a system is not too complex, if very high speed is essential, if subsequent modification is not envisaged and development time is at a premium, then the hardwired solution is probably the better solution.

b. MICROPROCESSOR

If the system demands the opposite to the above then use a microprocessor. Also if one is used, extra sophistication which would have been useful but rejected on grounds of cost if hardwired, can be introduced at little extra cost.



The exciting new
TRITON
 Personal Computer
 exclusively from:

TRANSAM



EXPANSION MOTHERBOARD KIT (including power supply, buffering, 2 sockets) £50
 8k STATIC RAM BOARD KIT (including 16 4K static rams, lower power 450ns) £97
 8k EPROM BOARD KIT (including 8 blank 2708 EPROMS — £31 without) £97

Full details available in our brand new 1979 computer products catalogue —
 so order your copy now! Don't forget, VAT is extra at 8%.
 User club £4 per annum.

Complete kit of
 parts available
 only £286 (+ VAT) *

SELECTABLE FIRMWARE OPTIONS

L4.1 Triton system £285 + VAT (p & p £4)
 includes 1K monitor, 2K tiny basic, resides on main PCB.
L5.1 Triton system £294 + VAT (p & p £4)
 includes 1.5K monitor, extended tiny basic. Resides on main
 PCB (see June issue).
L6.1 Triton system £399 + VAT (p & p £6)
 includes 1.5K monitor, 7K scientific basic with F.P. to six
 places. Resides offboard on EPROM PCB mounted on
 motherboard. Please note that with this option you have
 the facility to add 7 more cards to bring Triton up to its full
 64K.

STAND ALONE FIRMWARE PACKS IN EPROM

L4.1 £30 + VAT (3K on main board)
L5.1 £40 + VAT (4K on main board)
L5.2 £40 + VAT (As L5.1 but with 18MHZ crystal)
L6.1 £90 + VAT (1.5K on main board, 7k on EPROM PCB)
L6.2 £90 + VAT (As L6.1 but with 18MHZ crystal)

CONVERSION OPTIONS — we like your old 2708's!

Convert L4.1 to L5.1 £25 + VAT (return 3 EPROMS)
 Convert L4.1 to L6.1 £69 + VAT (return 3 EPROMS)
 Convert L5.1 to L6.1 £62 + VAT (return 4 EPROMS)
 charges reflect programming and erasing costs.

DOCUMENTATION

Triton manual £5 + 70p p & p (included in kit)
 L4.1 listing £4 + SAE
 L5.1 listing £5 + SAE
 L5.1 user documentation £1 + SAE
 L6.1 user documentation £1.50 + SAE
 Motherboard construction details — free but send an SAE.
 RAM card and ROM card construction — same applies.

TRITON SOFTWARE

See Computing Today and our own general library — list
 available, send SAE.
 *All parts available separately or in packs. Budget your
 Triton system. It's easy to buy!

DON'T FORGET! . . . Triton has in standard L4.1 option

Basic interpreter.
 64 graphic characters.
 Buffered outputs to 64k.
 Power supply and cabinet.
 8k memory option on main PCB.
 56 station fully ASCII encoded keyboard.
 Memory mapping.
 Modem controlled tape I/O (or communications interface).
 118 page manual.
 Standard TV interface.
 Sorry, TV set and cassette not included.

TRANSAM

TRANSAM COMPONENTS LTD.
12 CHAPEL STREET
LONDON, NW1 TEL: 402 8137

NEXT TO EDGWARE ROAD TUBE STATION, MET. LINE
 TRITON COMPUTER IS THE TRADE MARK OF
 TRANSAM COMPONENTS LTD

TRANSAM

I am interested in the Triton

Name

Address (please print)


To: Transam Components Ltd.,
 12 Chapel Street, NW1.

Please send me the following:—

1. A copy of your latest Summer '79 catalogue ☐
 I enclose 40p + SAE (11 3/4" x 8 1/2")
2. A copy of your Triton manual ☐
 I enclose £5 + 70p p & p
3. A complete set of parts for the ☐
 Triton computer L4.1 L5.1 L6.1
 (please delete options not required — see
 prices opposite)
4. A Triton PCB. ☐
 I enclose £50 + VAT + £1 p & p
5. A Triton RAM Card Kit. ☐
 I enclose £97 + VAT + 75p p & p
6. A Triton EPROM Card Kit ☐
 I enclose £31 without the 2708's
 I enclose £97 with the 2708's

I enclose a total of £

CT2



BARCLAYCARD ACCESS
 VISA & MASTER CHARGE
 ARE WELCOME SEND
 YOUR CARD NUMBER WITH
 ORDER



MINI-ADS & CLASSIFIED

PROGRAMS — Complete range of business, personal and educational software from; PERSONAL SOFTWARE, PETSOFT, A. J. HARDING, GEMSOFT, GAMES WORKSHOP, SOFT SOLUTION.

DISCETTES — 5 1/4" £32.40 per box of 10.
8" £37.80 per box of 10.
State type required.

TRS80 16K upgrade — complete set of top-quality tested components and detailed fitting instructions £79.95

C60 Low-noise cassettes ideal for program and data storage (boxed) £2.70 for 10.

PET and TRS80 Dust covers £5.40.

ADDRESS LABELS and CONTINUOUS STATIONERY — phone or write for a quote.

Above prices include postage and VAT.

Mail order only from;

G. L. MANAGEMENT SERVICES

71 Heathfield Road,
Cardiff CF4 3JX.
Phone (0222) 372066.

STAND ALONE \$100 BOARD

Yes, we were surprised too but here it is —

INMOD 885

WHAT IS IT?

- * Self contained processor/console
- * 3MHZ Intel 8085A CPU
- * Integral HEX keyboard/display
- * 2K byte interactive ROM monitor — on board expansion to 6K
- * 256 bytes on board RAM
- * \$100 BUS compatible
- * Low cost (£250 1 off)
- * Made to industrial spec

For further details and order form send SAE to

RPS SYSTEMS

9 The Paddocks,
Ramsbury, Wiltshire

GEMSOFT

We are pleased to announce our new catalogue of over 50 original programs for the Pet 2001; at prices to make your mouth water. Here are a few examples:—

GAMES: Zap the Klingons, Dropout, Dominoes, Crosswords, Blackjack, X-wing attack all £6. Arrow, Richochet, Star Trek £5. Oil run, Petals, Scramble £4.50.

EDUCATIONAL:— Metric Conversion, Curfit, Triangle, Marks, Distance calculator, Arithmetic and Geometric progression, all £4.00.

BUSINESS and general programs at various prices. Mortgage, Portfolio, VAT returns, Bank account, date calculator, Keyboard record, line renumber, Tape write and read, Trace, Hexconv.

Many more programs available, send SAE for full catalogue, or contact your local computer shop.

COMING SOON: Business programs available on the Diskmon system. Programs for the EXIDY SORCERER in preparation.

Complete systems supplied for business applications based on the Pet and Exidy micro's. Business and special application programs written to order.

Gemsoft, "Alverstoke Lodge",
Wych Hill Lane, Woking,
Surrey. (04862) — 60268.

ANNOUNCING THE NEW

μHEX EPROM PROGRAMMER

PUSH BUTTON SWITCHING FOR
2704, 2708 and 2716

Needs only standard CPU power supplies.
Has on-board stabilised 26v inverter.

PERFECT FOR Nascom, Micros, etc.
or any PIO equipped CPU.

Tested and approved by
NASCOM



Includes Z80, 8080, and 6800
control programs.

Features zero force Eprom socket.



ONLY £65

Early orders ex stock
s.a.e. for details

MICRO HEX COMPUTERS
2 Studley Rise, Trowbridge, Wilts.

NASCOM USERS. Run simple BASIC programs on minimum NASCOM. Nine commands, Editor. Fully documented program, £2. Available on cassette, 55p extra. J. Alison, 35 Swallow Road, Langley Green, Crawley, Sussex.

BRITISH MOTOROLA 6800 SYSTEMS

6800S: 16K Dynamic RAM, 1K Mikbug compatible monitor, room for 8K BASIC in ROM, VDU with u/l case and graphics, CUTS and Hi Speed tap3 interfaces, Single pcb with power supply components. Price of kit from £275 with out kdb or £299.00 with keyboard.

NCU Board. This number cruncher using the MM57109 is supplied with our own Basic style program on tape (3K bytes) that will outperform any of the 8K Basics as a programmable calculator. Suitable for any 6800 system with Mikbug. Kit price £32.00

Mini 6800 MK2. 1K user RAM, CUTS, VDU with u/l case and graphics with QUERTY keyboard from £152.50

8K RAM (2114) and 5 or 10K PROM board. This pcb is bus compatible with the above systems and has all the buffering and decoding that you need. PCB only, £13.00

Microcases: Large ABS moulded case, big enough for complete system, with one disc £27.50

ALL PRICES WITHOUT VAT AND POST.
PLEASE SEND S.A.E. FOR LEAFLETS.

HEWART MICROELECTRICS

95 Blakelow Road, Macclesfield,
Cheshire.

COLOUR MODULATOR

Kit **£6.95** FOR ALL TV GRAPHICS!
Red, Green, Blue inputs (can be mixed).
SUPER EXPLOSION FLASH EFFECT FOR
TANK BATTLE. FREE INTERFACE DE-
TAILS.

WILLIAM STUART SYSTEMS
Dower House Billericay Road, Herongate, Brentwood, Essex
CM13 3SD Tel (0277) 810244
Barclaycard / Access welcome

PHILIPS ELECTROLOGICA P354/336/600

Visible Record Computer

— purchased February
1975, little used since
December 1977.

Offers to:

MacNeill Press Limited
175 Bermondsey Street,
London SE1 3UW.
Telephone: 01-403 0044

ELF II computer in temporary case with manuals and expansion power supply, UHF modulator, etc. Bargain at £85.00 Ring 0602 266748 (weekends only).

EPROM PROGRAMMING prompt service 2708 (1024 x 8) or 5204 (512 x 8) EPROMS programmed with your Hex listing £13.50 each or your chips erased and programmed £3 each. Special rates for batches. Peter Marlow, "Rosslyn", Moored Grove, Cheltenham, Glos. GL53 0EX. Phone (0242) 55133 evenings.

FOR SALE. ASR 33 Telytype with stand as new, £250, also Friden Flexywriter, £35. Phone 01-549-9901 after 6 p.m.

THIS SECTION IS A PRE-PAYMENT SERVICE ONLY

MINI-ADS: 31/4" x 21/8", 1-3 £38, 4-11 £36, 12 or more £34 per insertion. **CLASSIFIED DISPLAY:** 19p per word. Minimum 25 words. Boxed classifieds are £6.33 per col. centimetre. No P.O. Box Numbers can be accepted without full address.

Enquiries to: Advertising Department, 01-437 5982. 25-27 Oxford Street, London W1R 1RF

INTERESTED IN HOME COMPUTING?

EX
STOCK

FREE B BUG
valued at £23.00
plus 10 x C12 cassettes
valued at £4.00
plus Standard Modulator
valued at £2.25
WITH EVERY NASCOM

Start now and don't get left behind **THE NASCOM 1**
is here Ex-stock with full technical services

Plus the opportunity to join the fastest moving club of personal computer users enabling you to get the most out of your computer. You can OBTAIN and EXCHANGE programs and other software — many now available.

The Powerful Z80
Microprocessor
Professional Keyboard
1 Kbyte Monitor in EPROM
2 Kbyte RAM (expandable)
Audio Cassette interface
Plugs into your domestic TV
Easy construction from
straightforward instructions
— no drilling or special tools
— Just neat soldering
required.



SAVE
£60

Only ~~£197.50~~ + 8% VAT (includes p & p + insurance)

Manuals separately 2.95
Z80 programming Manual 6.90
Z80 Technical Manual 2.95
PIO Technical Manual 2.95

NEW LOW PRICE
£165

(All prices add 8% VAT)

Power supply suitable for
NASCOM 19.90

NASCOM AD ONS — Nascom improved monitor B Bug (2K)
featuring — *Four times tape speed *Direct text entry without
ASCII *Extended keyboard facility *Additional useful
subroutines **£23.00**

Nascom Vero Case
£22.50

Nascom Music Box Kit **£9.90**
(write your own tunes and play
them on your Nascom.
Complete with full documentation).

Nascom Joy Stick Kit
£14.90

GRAPHICS ADD ON BOARD £9.90
Complete kit to upgrade your NASCOM for graphics capability
includes full documentation and demonstration program.

NEW! AT LAST 8K BASIC **£160**
FOR NASCOM 1 Complete on **EX-STOCK**
S100 Board

THE EXIDY SORCERER.

SORCERER COMPUTER SYSTEM

The Sorcerer Computer is a completely
assembled and tested computer system.
Standard configuration includes 63-key
typewriter-style keyboard and 16-key
numeric pad, Z80 processor, dual cassette
I/O with remote computer control at 300
and 1200 baud data rates, RS232 serial I/O
for communications, parallel port for
direct Centronics printer attachment, 4K
ROM operating system, 8K ROM
Microsoft BASIC in Rom Pac™ cartridge,
composite video of 64 char/line 30 line/
screen, 128 upper/lower case ASCII set
and 128 user-defined graphic symbols,
operation manual, BASIC programming
manual and cassette/video cables, connec-
tion for S-100 bus expansion.

CPM
NOW



SAVE
£100

EX
STOCK

LOOK!

*32K RAM on board
*RS232 interface *8K BASIC ROM
*CUTS interface *4K MONITOR
*KANSAS CITY interface *S100 BUS
*User defined graphic symbols *Z80 cpu

16K ~~£860~~ **£725** * 32K ~~£950~~ **£790** * Credit facilities available. + VAT

MODULATORS UHF Channel 36

Standard 6 meg band width **£2.25**
High Quality 8 meg band width **£4.90** **EX-STOCK**

SHORT C12 CASSETTES **EX-STOCK**
FOR COMPUTER PROGRAMMES
10 for £4.00

PET COSTS LESS AT COMP and it's a pedigree

RRP £550

The No. 1 Personal Computer
in the U.K. **£499** **SAVE**
Affordable 8K + VAT **£50**

for the first time user and
the professional check out
the PET, the world's most
popular personal computer.



Also 16K big professional keyboard **£625** + VAT



**NEW! THE
ITT APPLE
(2020)**

£827
+ VAT

EX-STOCK
4K


16K
£49
+ VAT

**LOW PRICE
MEMORY UPGRADE
PURCHASED AT TIME OF
ORDER**

* Full colour - UHF output
* Audio cassette tape interface * Up to 48K RAM on board * BASIC in
ROM (graphics commands include COLOUR = VLIN, HLIN, PLOT and SCRN)
* Built in Loudspeaker * Buckets of software already available * disk system
(110 K byte per drive — includes controller) only **£425** + VAT

EX-STOCK

THE TRS-80 (SPECIAL SCOOP) Low Priced, Ready to Go!



Use your own cassette

Level-II with 4K RAM
Improved graphics, print
formatting, and a faster cassette
transfer rate are features of
Level-II BASIC.

£399 + VAT

EX
STOCK

**PLUGS INTO
YOUR OWN TV**

Level-II with 16K RAM
A combination of 16K RAM and
the powerful Level-II BASIC
produces a system capable of
handling most demands.

£499 + VAT


KEY BOARD ONLY

**COMPLETE WITH
UHF MODULATOR**

UK POWER SUPPLY — £9.90 + VAT

All prices include VAT except where shown. Orders over £5 post and
packing free otherwise add 20p. Please make cheques and postal orders
payable to COMP, or phone your order quoting BARCLAYCARD or ACCESS

OPEN — 10am to 7pm — Monday to Saturday
CREDIT FACILITIES ARRANGED



COMPUKIT UK101

LOW COST SUPERBOARD IN KIT FORM



The CompuKit UK101 has everything a one board 'superboard' should have.

- ★ Uses ultra-powerful 6502 microprocessor.
- ★ 50Hz Frame refresh for steady clear picture (U.S.A. products with 60Hz frame refresh always results in jittery displays)
- ★ 48 chars by 16 lines — 1K memory mapped video system providing high speed access to screen display enabling animated games and graphs.
- ★ Extensive 256 character set which includes full upper and lower case alphanumerics, Greek symbols for mathematical constants and numerous graphic characters enabling you to form almost any shape you desire anywhere on the screen
- ★ 8K full Microsoft Basic in ROM compatible with PET, APPLE SORCERER hence taking the headache out of programming by using simple English

FULL CONSTRUCTION DETAILS
IN P.E. AUG 1979 EDITION

SEND ONLY £10.00 DEPOSIT TO RESERVE ONE

A tape of 10 programs on cassette — educational games, etc. will be supplied free of charge with each kit.

Simple Soldering due to clear and concise instructions compiled by Dr.T. Berk, BSc.PhD

COMMANDS
CONT LIST
STATEMENTS
CLEAR DATA
GOTO GOSUB
NEXT ON GOTO
REM RESTORE
NEW
DEF IF GOTO
ON GOSUB
RETURN
NULL
DIM IF THEN
POKE
STOP
RUN
END INPUT
PRINT READ

EXPRESSIONS
OPERATORS
+ * / ^ NOT AND OR > < <> >= <= RANGE 10⁻³² to 10⁺³²

VARIABLES
A,B,C,...Z and two letter variables
The above can all be subscripted when used in an array. String variables use above names plus \$ e.g. A\$.
FUNCTIONS
ABS(X) COS(X) EXP(X) FRE(X) INT(X)
LOG(X) PEEK(I) POS(I) RND(X) SGN(X) SIN(X)
SPC(I) SQR(X) TAB(I) TAN(X) USR(I)
STRING FUNCTIONS
ASC(X\$) CHR\$(I) FRE(X\$) LEFT\$(X\$,I) LEN(X\$) MID\$(X\$,I,J)
RIGHT\$(X\$,I) STR\$(X) STR\$(X)

statements. Much faster than currently available personal computers.

- ★ Professional 52 Key keyboard in 3 colours — software polled meaning that all debouncing and key decoding done in software.
- ★ Video output and UHF Highgrade modulator (8Mz Bandwidth) which connects direct to the aerial socket of your T.V. Channel 36 UHF.
- ★ Fully stabilised 5V power supply including transformer on board.
- ★ Standard KANSAS city tape interface providing high reliability program storage — use on any standard domestic tape or cassette recorder.
- ★ 4K user RAM expandable to 8K on board £49 extra.
- ★ 40 line expansion interface socket on board for attachment of extender card containing 24K RAM and disk controller. (Ohio Scientific compatible).
- ★ 6502 machine code accessible through powerful 2K machine code monitor on board.
- ★ High quality thru plated P.C.B. with all I.C.'s mounted on sockets


Delivery date June 1979
at the 1979 MicroComputer Show
Customer orders in strict rotation only.

NO EXTRAS NEEDED JUST HIT
'RETURN' AND GO.

Build, understand, and program your own
computer for only a small outlay.

ONLY £219 + VAT
including RF Modulator & Power supply.
Absolutely no extras.

SPECIAL CHARACTERS
@ Erases line being typed, then provides carriage return, line feed.
␣ Erases last character typed.
CR Carriage Return — must be at the end of each line.
: Separates statements on a line.
CONTROL/C Execution or printing of a list is interrupted at the end of a line.
"BREAK IN LINE XXXX" is printed, indicating line number of next statement to be executed or printed.
CONTROL/O No outputs occur until return made to command mode. If an input statement is encountered, either another CONTROL/O is typed, or an error occurs.
? Equivalent to PRINT



The CompuKit UK101 Character Set

FUNCTIONS
ABS(X) COS(X) EXP(X) FRE(X) INT(X)
LOG(X) PEEK(I) POS(I) RND(X) SGN(X) SIN(X)
SPC(I) SQR(X) TAB(I) TAN(X) USR(I)
STRING FUNCTIONS
ASC(X\$) CHR\$(I) FRE(X\$) LEFT\$(X\$,I) LEN(X\$) MID\$(X\$,I,J)
RIGHT\$(X\$,I) STR\$(X) STR\$(X)

FUNCTIONS
ABS(X) COS(X) EXP(X) FRE(X) INT(X)
LOG(X) PEEK(I) POS(I) RND(X) SGN(X) SIN(X)
SPC(I) SQR(X) TAB(I) TAN(X) USR(I)
STRING FUNCTIONS
ASC(X\$) CHR\$(I) FRE(X\$) LEFT\$(X\$,I) LEN(X\$) MID\$(X\$,I,J)
RIGHT\$(X\$,I) STR\$(X) STR\$(X)

The teleplay Colour Programagame now back in stock at reduced prices

AS REVIEWED IN HOBBY ELECTRONICS

ENGLAND'S MOST POPULAR TV GAME KIT



TELEPLAY have produced a new product of easy to assemble cartridge games, for you and all your family, that will not go out of date. Just ADD each new cartridge, as it becomes available, and your colour video centre will be up to date the Teleplay way. You will save pounds in the long run. Works OK on Black and White TV.

The Teleplay Kit consists of a Professional Finished Inject Mounted Box — Joystick Hand Controls — one cartridge which consists of 10 games — Football, Tennis, Solo Squash (1 & 2 players), Shoot etc, Mains Adaptor. All holes are pre-drilled — No Special equipment required. You'll be surprised how easy it is to assemble this professional kit! Instruction Manual supplied separately at 0.45p. TELEPLAY GIVES YOU TWICE THE FUN BUILDING AND PLAYING THE MOST PROFESSIONAL TV GAME KIT EVER OFFERED.

Electrical knowledge is not a necessity to assemble this project — just simple soldering.

Every 3 months a NEW game will become available to you and those already under production include Submarines, Space War, Wipe Out and many more. The price of these will vary from £12 to £19 depending upon the complexity of the game. All Cartridges fully assembled.

STUNT CYCLE 4 games — Cartridges and Hand Controls — £12.90
WIPE OUT — 6 games — £11.90
TANK BATTLE — Cartridge and Hand Controls — £18.90
ROAD RACE — 2 games — Cartridge — Controls already with basic kit — £10.90

EUROPE'S LARGEST STOCKIST OF TV GAME COMPONENTS.

COMP IS AN APPOINTED DEALER FOR COMMODORE, EXIDY, APPLE, NASCOM, OHIO, GI, ATARI, TELEPLAY & ITHACA.

COMP COMPUTER COMPONENTS

14 STATION ROAD, NEW BARNET, HERTFORDSHIRE TEL: 01-441 2922 (Sales) 01-449 6596
CLOSE TO NEW BARNET BR STATION — MOORGATE LINE TELEX: 298755
OPEN — 10am to 7pm — Monday to Saturday CONTINUOUS DEMONSTRATIONS

VISIT OUR NEW SHOP AT 1 WALLCOT BUILDINGS, LONDON ROAD, BATH, AVON.

(PART OF THE COMPSHOP LTD. GROUP)



NewBear



NEW

BASF 5 1/4 ins disk drives

BASF 6106	- slimline
	Double density £220.00 8% VAT
BASF 6108	- slimline
	Double density
	Double sided £279.50 8% VAT

MEMORIES DOWN IN PRICE 4116 only £8.50

2102-1	£0.85	2708	£6.99
2102L-1	£0.99	SWATBUG	£16.00
2112	£2.25	MC 6803L7 (MIKBUG)	£13.65
2114	£6.99		plus 8% VAT

WE STOCK

VERO. OK TOOLS. JIM PAK. NASCOM. SYM-1.
ITHICA AUDIO. 77-68 BEAR BAGS. SORCEROR.
HORIZON AND MUCH MORE...

INTEGRATED CIRCUITS

Microcomputing I.C.'s

MC 6800	£7.15			
MC 6821	£4.63			
MC 6850	£6.74			
MC 6810AP	£3.61			
MC6840	£12.72			
MC8602P	£2.88			
MC 14536P	£3.69			
MC3459	£2.43			
Z80 CPU 2.5MHz	£8.99	100.0	KHz	£3.25
Z80 PIO 2.5MHz	£7.99	200.0	KHz	£4.20
Z80 CTC 2.5MHz	£7.99	204.8	KHz	£3.25
Z80A CPU 4MHz	£13.99	1.0	MHz	£3.50
Z80A PIO 4MHz	£10.00	1.008	MHz	£2.80
Z80A CTC 4MHz	£10.00	1.8432	MHz	£2.80
SC/MP11	£8.88	2.0	MHz	£2.60
(INS 8060N)		4.0	MHz	£2.60
INS 8154N	£8.18	5.0	MHz	£2.60
8080A	£6.00	10.0	MHz	£2.60
6502	£12.00	13.478	MHz	£3.25
6522	£6.58	36.0	MHz	£3.25
6532	£12.56			

NEW

plus 8% VAT

INTEGRATED CIRCUITS

Character Generators

74S 262	£13.70
2513 (U)	£6.50
2513 (L)	£6.50
MCM 6571P	£6.71
9368 (7 segment display decoder)	£2.45

UARTS

6402	£4.50
AY-5-1013	£4.50

plus 8% VAT

Send for
New
Hardware
Catalogue &
booklist

DEVLIN MODULAR 60 KEY KEYBOARD

Pet replacement

Mounted on PCB
X-Y matrix £38.50
Matching Hex keypad £7.20
Send for details

GAMES BOOKS

101 Basic Computer Games	D.AHL	£6.50
Star Ship Simulation		£5.10
Game Playing with Computers		£10.20
Game Playing with Basic	D. Spencer	£4.20
SARGON-A Chess Computer Program in Z80		
ASSEMBLY LANGUAGE		£9.50

PASCAL BOOKS

Pascal: User Manual & Report	Springer-Verlag	£5.52
Problem Solving Using Pascal	Springer-Verlag	£7.84
Programming in Pascal	P. Grogono	£7.50
A Practical Introduction to Pascal	A. Addyman	£3.50

PRACTICAL APPLICATION BOOKS

Programming the 6502 (SYBEX)		£8.00
The 6800 Microprocessor		£3.60
8080A BUGBOOK		£6.95
Data Acquisition Handbook		£2.00
77-68 Construction Manual		£7.50
Fundamentals of Digital Computers	D. Spencer	£7.50
National Semiconductors Interface Circuits Data Book		£2.75
Programming a Micro 6502	C.C.Foster	£7.95
Semiconductor Circuit Design Vol 1	T.I	£6.50
Semiconductor Circuit Design Vol 2	T.I	£6.50
Semiconductor Circuit Design Vol 3	T.I	£6.50
Semiconductor Circuit Design Vol 4	T.I	£6.50
Semiconductor Circuit Design Vol 5	T.I	£7.95

TERMS AND CONDITIONS

Minimum official order £10.00
Postage & packing 30p on Hardware
Hardware price plus 8% VAT.
Callers welcome Mon-Sat 9.00-5.30
but please phone us first on 0635 30505.

Barclaycard &
Access
Welcome

ALL MAIL ORDER TO NEWBURY

INTRODUCTORY OFFER

MODEL 700 VDU

- Assembled and tested
 - Upper case only
 - 64 characters x 16 lines
 - 110-1200 baud
- £299 with video monitor

Newbear Computing Ltd.,
40 Bartholomew St, Newbury, Berks.
0635 30505

Visit our Northern office at 2A
Gatley Rd, Cheadle, Cheshire.
Tel 061-491-2290

24
HOUR
DELIVERY
IN MOST
CASES